

City of Maple Ridge

COUNCIL MEETING AGENDA

July 9, 2019

7:00 p.m.

Council Chamber

MEETING DECORUM

Council would like to remind all people present tonight that serious issues are decided at Council meetings which affect many people's lives. Therefore, we ask that you act with the appropriate decorum that a Council Meeting deserves. Commentary and conversations by the public are distracting. Should anyone disrupt the Council Meeting in any way, the meeting will be stopped and that person's behavior will be reprimanded. *The meeting is live streamed and recorded by the City of Maple Ridge.*

Note: This Agenda is also posted on the City's Web Site at www.mapleridge.ca

The purpose of a Council meeting is to enact powers given to Council by using bylaws or resolutions. This is the venue for debate of issues before voting on a bylaw or resolution.

-
- 100 **CALL TO ORDER**
- 200 **AMENDMENTS TO THE AGENDA**
- 300 **APPROVAL OF THE AGENDA**
- 400 **ADOPTION OF MINUTES**
- 401 Minutes of the Regular Council Meeting of June 25, 2019 and the
Special Council Meeting of June 25, 2019 and July 2, 2019
- 500 **PRESENTATIONS AT THE REQUEST OF COUNCIL**
- 600 **DELEGATIONS**
- 601 Rogers/Davison Farm Cellular Tower, 22080 128 Avenue
- Amabile Ranta
 - Robert Shaw

650 **QUESTIONS FROM THE PUBLIC**

Note: Questions from the Public are limited to 15 minutes unless extended by a motion approved by the majority of Council. Each speaker is limited to 2 minutes at a time.

700 **ITEMS ON CONSENT**

701 **Minutes**

701.1 Minutes of the Development Agreements Committee Meetings of June 19, June 26 and July 4, 2019

701.2 Minutes of Meetings of Committees and Commissions of Council

- Active Transportation Advisory Committee – May 29, 2019
- Agricultural Advisory Committee – May 23, 2019

702 **Reports**

703 **Correspondence**

704 **Release of Items from Closed Council Status**

From the July 2, 2019 Closed Council Meeting

04.01 2019 Paid On Call Fire Fighters Salary Adjustments

800 **UNFINISHED BUSINESS**

801 **Albion Community Centre Background Information – Expression of Interest Process**

Staff report dated July 9, 2019 providing information on the Expression of Interest process for a facility operator for the Albion Community Centre.

900 **CORRESPONDENCE**

1000 ***BYLAWS***

1001 **2015-155-RZ, 23702 132 Avenue**

1001.1 **Maple Ridge Zone Amending Bylaw No. 7173-2015**

To rezone from RS-2 (One Family Suburban Residential) to RS-1b (One Family Urban (Medium Density) Residential) to permit a subdivision of 16 lots not less than 557 m².

Adoption

1002.2 **Maple Ridge Official Community Plan Amending Bylaw No. 7172-2015**

To amend Silver Valley Area Plan Figure 2 and Figure 3C from Conservation, Open Space, Low Density Residential and Med/High Density Residential to Low Density Residential and Conservation; and

To amend Silver Valley Area Plan Figure 4: Trails/Open Space to remove from Conservation, to add to Conservation, and to remove from Open Space

Adoption

1100 ***COMMITTEE REPORTS AND RECOMMENDATIONS***

For the following items that refer to staff report earlier than this agenda date: the items were presented at a Committee of the Whole meeting typically a week prior on the date of the staff report, to provide Council with an opportunity to ask staff detailed questions. The items are now before the regular Council Meeting for debate and vote. Both meetings are open to the public. **The reports are not reprinted again in hard copy**, however; they can be found in the electronic agenda or in the Committee of the Whole agenda package dated accordingly.

Public Works and Development Services

1101 **2019-183-AL, 12176 237 Street, Application to Exclude Land from the Agricultural Land Reserve**

Staff report dated July 2, 2019 providing options for consideration pertaining to Application 2019-183-AL to exclude approximately 1.12 hectares (2.8 acres) of land from the Agricultural Land Reserve.

1102 2019-126-AL, 12392 248 Street, Application for Non-adhering Residential Uses in the Agricultural Land Reserve

Staff report dated July 2, 2019 recommending that Application 2019-126-AL for residential development within the Agricultural Land Reserve be forwarded to the Agricultural Land Commission.

1103 2019-200-AL, 13055 210 Street, Application for Non-adhering Residential Uses in the Agricultural Land Reserve

Staff report dated July 2, 2019 recommending that Application 2019-200-AL for residential development within the Agricultural Land Reserve be forwarded to the Agricultural Land Commission.

1104 2018-464-RZ, 11907 223 Street, RM-3 to RM-2

Staff report dated July 2, 2019 recommending that Maple Ridge Zone Amending Bylaw No. 7563-2019 to rezone from RM-3 (High Density Apartment Residential District) to RM-2 (Medium Density Apartment Residential District) to permit the construction of a six-storey residential apartment with approximately 51 units be given first reading and that the applicant provide further information as described on Schedules A, C, D and E of the Development Procedures Bylaw No. 5879-1999.

1105 2019-090-RZ, 22090 Cliff Avenue, RS-1 to RS-1b

Staff report dated July 2, 2019 recommending that Maple Ridge Zone Amending Bylaw No. 7559-2019 to rezone from RS-1 (One Family Urban Residential) to RS-1b (One Family Urban (medium density) Residential) to allow future subdivision into 2 lots be given first reading and that the applicant provide further information as described on Schedules B, E and G of the Development Procedures Bylaw No. 5879-1999.

1106 2019-119-RZ, 12791 232 Street, RS-2 to C-1

Staff report dated July 2, 2019 recommending that Maple Ridge Zone Amending Bylaw No. 7558-2019 to rezone from RS-2 (One Family Suburban Residential) to CS-1 (Service Commercial) to permit a commercial development be given first reading and that the applicant provide further information as described on Schedules A, C and D of the Development Procedures Bylaw No. 5879-1999.

1107 2017-489-RZ, 11917 and 11903 Burnett Street, RS-1 to RM-2

Staff report dated July 2, 2019 recommending that Maple Ridge Zone Amending Bylaw No. 7407-2017 to rezone from RS-1 (One Family Urban Residential) to RM-2 (Medium Density Apartment Residential) to permit construction of 54 residential apartment units be given second reading as amended and be forwarded to Public Hearing.

1108 2017-573-RZ, 11575, 11587 223 Street and 22300 River Road (PID 011-537-141), RS-1 to RM-2

Staff report dated July 2, 2019 recommending that Maple Ridge Zone Amending Bylaw No. 7420-2018 to rezone from RS-1 (One Family Urban Residential) to RM-2 (Medium Density Apartment Residential) to permit the construction of approximately 36 apartment units be given second reading and be forwarded to Public Hearing.

1109 2016-091-DVP, 14155 Marc Road

Staff report dated July 2, 2019 recommending that the Corporate Officer be authorized to sign and seal 2016-091-DVP to vary retaining wall height.

1110 2018-089-DVP, 14310 256 Street

Staff report dated July 2, 2019 recommending that the Corporate Officer be authorized to sign and seal 2018-089-DVP to omit the requirement to upgrade services and utilities on 256 Street.

1111 2019-210-DVP, 22768 and 22772 119 Avenue

Staff report dated July 2, 2019 recommending that the Corporate Officer be authorized to sign and seal 2019-210-DVP to vary parking from 126 stalls to 112 stalls.

1112 Award of Contract ITT-EN19-35: Dewdney Trunk Road Watermain Replacement (Edge Street to 228 Street)

Staff report dated July 2, 2019 recommending that Contract ITT-EN19-35: Dewdney Trunk Road Watermain Replacement (Edge Street to 228 Street) be awarded to Pedre Contractors Ltd., that a construction contingency be approved, that the Financial Plan be amended to increase the budget and further that the Corporate Officer be authorized to execute the contract.

Corporate Services

1131 2019 Community Grant

Staff report dated July 2, 2019 recommending that a community grant be awarded to the Jamia Riyadhul Jannah British Columbia Foundation.

Parks, Recreation & Culture

1151 Maple Ridge and Pitt Meadows Arts Council Proposed Bylaw Amendments

Staff report dated July 2, 2019 recommending that the changes to the Maple Ridge and Pitt Meadows Arts Council Society's bylaw be endorsed.

Administration (including Fire and Police)

Other Committee Issues

1200 STAFF REPORTS

1300 OTHER MATTERS DEEMED EXPEDIENT

1301 Reconsideration of Resolution No. R/2019-393 "That Zone Amending Bylaw No. 7552-2019 be given first reading; and that the applicant provide further information as described on Schedules C, D and E of the Development Procedures Bylaw No. 5879-1999" defeated at the June 25, 2019 Council Meeting.

Staff report dated June 18, 2019 recommending that Maple Ridge Zone Amending Bylaw No. 7552-2019 to rezone from RS-1 (One Family Urban Residential) to RM-1 (Townhouse Residential) to support a 8 unit residential townhouse development be given first reading and that the applicant provide further information as described on Schedules C, D and E of the Development Procedures Bylaw No. 5879-1999.

1400 *NOTICES OF MOTION AND MATTERS FOR FUTURE MEETING*

1500 *MAYOR AND COUNCILLORS' REPORTS*

1600 *ADJOURNMENT*

QUESTIONS FROM THE PUBLIC

The purpose of the Questions from the Public session is to provide the public with an opportunity to ask questions of Council on items that are of concern to them, with the exception of Public Hearing bylaws which have not yet reached conclusion.

Council will not tolerate any derogatory remarks directed at Council or staff members.

Each person will be permitted 2 minutes to ask their question (a second opportunity is permitted if no one else is sitting in the chairs in front of the podium). Questions must be directed to the Chair of the meeting and not to individual members of Council. The total session is limited to 15 minutes.

Council reserves the right to defer responding to a question in order to obtain the information required to provide a complete and accurate response.

Other opportunities are available to address Council including public hearings, delegations and community forum. The public may also make their views known to Council by writing or via email and by attending open houses, workshops and information meetings. Serving on an Advisory Committee is an excellent way to have a voice in the future of this community.

For more information on these opportunities contact:

Clerk's Department at 604-463-5221 or clerks@mapleridge.ca.
Mayor and Council at mayorandcouncil@mapleridge.ca.

Checked by: 

Date: 7/5/19

City of Maple Ridge

COUNCIL MEETING MINUTES

June 25, 2019

The Minutes of the City Council Meeting held on June 25, 2019 at 7:06 p.m. in the Council Chamber of the City Hall, 11995 Haney Place, Maple Ridge, British Columbia for the purpose of transacting regular City business.

<i>PRESENT</i>	<i>Appointed Staff</i>
<i>Elected Officials</i>	K. Swift, Acting Chief Administrative Officer
Mayor M. Morden	D. Boag, Acting General Manager Parks, Recreation & Culture
Councillor C. Meadus	D. Pollock, General Manager Engineering Services
Councillor G. Robson	C. Goddard, Director of Planning
Councillor R. Svendsen	L. Benson, Director of Corporate Administration
Councillor A. Yousef	T. Thompson, Chief Financial Officer
	C. Nolan, Corporate Controller
<i>ABSENT</i>	<i>Other Staff as Required</i>
Councillor K. Duncan	B. Elliott, Manager of Community Planning
Councillor J. Dueck	M. Orsetti, Manager Bylaw & Licencing Services
	R. MacNair, Senior Advisor, Bylaw & Licencing Services

Note: These Minutes are also posted on the City's Web Site at www.mapleridge.ca
Video of the meeting is posted at media.mapleridge.ca/Mediasite/Showcase

Note: Councillor Robson was not in attendance at the start of the meeting.

100 *CALL TO ORDER*

200 *AMENDMENTS TO THE AGENDA*

300 *APPROVAL OF THE AGENDA*

R/2019-380

It was moved and seconded

That the agenda of the Regular Council Meeting of June 25, 2019 be approved as circulated.

CARRIED

400 *ADOPTION AND RECEIPT OF MINUTES*

401 Minutes of the Regular Council Meeting of June 11, 2019 and the Special Council Meetings of June 11, 2019 and June 18, 2019

R/2019-381

It was moved and seconded

~~That the minutes of the Regular Council Meeting of June 11, 2019 and the Special Council Meetings of June 11, 2019 and June 18, 2019 be adopted as circulated.~~

CARRIED

402 Minutes of the Public Hearing of June 18, 2019

R/2019-382

It was moved and seconded

That the minutes of the Public Hearing of June 18, 2019 be adopted as circulated.

CARRIED

500 *PRESENTATIONS AT THE REQUEST OF COUNCIL*

501 Financial Reports Award Presentation

- Mayor Morden

Mayor Morden presented three awards from the Government Finance Officers' Association to staff. The three awards are:

- Canadian Award for Financial Reporting
- Distinguished Budget Presentation Award
- Popular Annual Financial Reporting Award

The Chief Financial Officer and Corporate Controller accepted the awards on behalf of staff.

600 *DELEGATIONS*

601 Public Art Steering Committee Annual Report

- Wayne Bissky, Chair (absent)
- Dr. Don Miskiman, Vice-Chair

Dr. Miskiman provided a review of the past year, highlighting the many works of art which have been placed throughout the community, those that are in progress, and those that will be coming over the next few years.

650 *QUESTIONS FROM THE PUBLIC SESSION*

Note: Councillor Robson joined the meeting at 7:25 p.m. during question period.

700 *ITEMS ON CONSENT*

701 *Minutes*

701.1 Minutes of the Development Agreements Committee Meetings of June 12 and June 18, 2019

701.2 Minutes of Meetings of Committees and Commissions of Council

- Environmental Advisory Committee – April 10, 2019

702 *Reports* – Nil

703 *Correspondence* – Nil

704 *Release of Items from Closed Council Status*

From the June 11, 2019 Closed Council Meeting

Item 04.02 Panhandling Bylaw Discussion - Resolution only

- Staff to bring back a proposed bylaw based on the Safe Streets Act.

R/2019-383

It was moved and seconded

That items on the Consent Agenda be received into the record.

CARRIED

800 *UNFINISHED BUSINESS*

Note: *Item 801 was forwarded from the June 18, 2019 Audit & Finance Committee Meeting*

801 *Business Planning Guidelines*

Staff report dated June 25, 2019 recommending that the 2020-2024 Business & Financial Planning Guidelines, attached as Appendix A be approved.

The Chief Financial Officer provided a slide presentation providing a high-level overview of the guidelines proposed.

R/2019-384

It was moved and seconded

That the Business & Financial Planning Guidelines 2020-2024, attached as Appendix A, be approved.

CARRIED

900 *CORRESPONDENCE* – Nil

1000 *BYLAWS*

Note: Items 1001 to 1004 are from the June 18, 2019 Public Hearing

Bylaws for Third Reading

1001 2017-572-RZ, 11703 Fraser Street and 11718 224 Street

1001.1 Maple Ridge Official Community Plan Amending Bylaw No. 7550-2019

To re-designate the easterly portion of subject property (11703 Fraser Street) from Ground-Oriented Multi-Family to Low-Rise Apartment.

Third reading

R/2019-385

It was moved and seconded

That Bylaw No. 7550-2019 be given third reading.

CARRIED

1001.2 Maple Ridge Zone Amending Bylaw No. 7422-2018

To rezone the easterly portion of the subject property from RM-1 (Townhouse Residential) to RM-2 (Medium Density Apartment Residential). The current application is to permit future construction of a 57 unit apartment building with underground parking.

Third reading

R/2019-386

It was moved and seconded

That Bylaw No. 7422-2018 be given third reading.

CARRIED

- 1002 **2016-031-RZ, 13227 236 Street**
 Maple Ridge Zone Amending Bylaw No. 7228-2016
 To rezone from RS-2 (One Family Suburban Residential) to RM-1 (Townhouse Residential). The current application is to permit a future development of 17 townhouse units.
 Third reading

R/2019-387

It was moved and seconded

That Bylaw No. 7228-2016 be given third reading.

CARRIED

- 1003 **2018-093-RZ, 11780 Burnett Street**
 Maple Ridge Zone Amending Bylaw No. 7485-2018
 To rezone from RS-1 (One Family Urban Residential) to R-1 (Residential District). The current application is to permit a future 2 lot subdivision.
 Third reading

R/2019-388

It was moved and seconded

That Bylaw No. 7485-2018 be given third reading.

CARRIED

- 1004 **2017-117-RZ, 11865, 11839, 11831 232 Street**
 Maple Ridge Zone Amending Bylaw No. 7351-2017
 To rezone from RS-1 (One Family Urban Residential) to RM-1 (Townhouse Residential). The current application is to permit the future development of 46 townhouse units.
 Third reading

R/2019-389

It was moved and seconded

That Bylaw No. 7351-2017 be given third reading.

CARRIED

Bylaws for Adoption

- 1005 **Maple Ridge Recreation Facility Fees Amending Bylaw No. 7553-2019**
 To reduce the dry floor rate by 10%, retroactive to April 1, 2019
 Adoption

R/2019-390

It was moved and seconded

That Bylaw No. 7553-2019 be adopted.

CARRIED

1100 *REPORTS AND RECOMMENDATIONS*

Public Works and Development Services

1101 2019-072-AL, 12225 250 Street, Application to Exclude Land from the Agricultural Land Reserve

Staff report dated June 18, 2019 providing options for consideration pertaining to Application 2019-072-AL to exclude approximately 0.987 hectares (2.4 acres) of land from the Agricultural Land Reserve.

R/2019-391

It was moved and seconded

That Application 2019-072-AL be authorized to go forward to the Agricultural Land Commission with a summary of Council's comments and the staff report.

CARRIED

1102 Proposed Cannabis Retail Store, #7-22214 Dewdney Trunk Road

Staff report dated June 18, 2019 recommending that an application for a cannabis retail store by Venti Holdings Ltd. located at #7-22214 Dewdney Trunk Road not be supported.

R/2019-392

It was moved and seconded

1. That the application for a cannabis retail store by Venti Holdings Ltd., located at #7 - 22214 Dewdney Trunk Road, Maple Ridge not be supported based on the information contained in the Council report dated June 18, 2019.
2. That a copy of the resolution be forwarded to the Liquor and Cannabis Regulation Branch in accordance with the legislative requirements.

CARRIED

1103 2019-164-RZ, 11678 Burnett Street, RS-1 to RM-1

Staff report dated June 18, 2019 recommending that Maple Ridge Zone Amending Bylaw No. 7552-2019 to rezone from RS-1 (One Family Urban Residential) to RM-1 (Townhouse Residential) to support a 8 unit residential townhouse development be given first reading and that the applicant provide further information as described on Schedules C, D and E of the Development Procedures Bylaw No. 5879-1999.

R/2019-393

It was moved and seconded

That Zone Amending Bylaw No. 7552-2019 be given first reading; and

That the applicant provide further information as described on Schedules C, D and E of the Development Procedures Bylaw No. 5879-1999.

DEFEATED

Councillor Robson, Councillor Svendsen, Councillor Yousef - Opposed

1104 2018-444-RZ, 21759 River Road, RS-1 to RS-1b

Staff report dated June 18, 2019 recommending that Maple Ridge Zone Amending Bylaw No. 7516-2018 to rezone from RS-1 (One Family Urban Residential) to RS-1b (One Family Urban [Medium Density] Residential) to permit a future subdivision of approximately two lots be given second reading and be forwarded to Public Hearing.

R/2019-394

It was moved and seconded

- 1) That Zone Amending Bylaw No. 7516-2018 be given second reading, and be forwarded to Public Hearing;
- 2) That the following terms and conditions be met prior to final reading:
 - i) Approval from the Ministry of Transportation and Infrastructure;
 - ii) Road dedication on River Road as required;
 - iii) Registration of a Restrictive Covenant for the Geotechnical Report, which addresses the suitability of the subject property for the proposed development;
 - iv) Registration of a Restrictive Covenant for Stormwater Management;
 - v) Removal of existing buildings;
 - vi) In addition to the site profile, a disclosure statement must be submitted by a Professional Engineer advising whether there is any evidence of underground fuel storage tanks on the subject property. If so, a Stage 1 Site Investigation Report is required to ensure that the subject property is not a contaminated site; and

- vii) That a voluntary contribution, in the amount of \$5,100.00 be provided in keeping with the Council Policy with regard to Community Amenity Contributions.

CARRIED

- 1105 2018-321-RZ, Electric Vehicle Charging Infrastructure

Staff report dated June 18, 2019 recommending that Off-Street Parking and Loading Amending Bylaw No. 7489-2018 to integrate 'rough-in' electric vehicle charging infrastructure requirements be given first, second and third reading.

R/2019-395

It was moved and seconded

That Bylaw No. 7489-2018 be given first, second and third reading.

CARRIED

- 1106 23154 128 Avenue – Request for Sanitary Service Connection Outside Urban Containment Boundary

Staff report dated June 18, 2019 recommending that the request to provide a sanitary service connection to 23154 128 Avenue be supported.

R/2019-396

It was moved and seconded

That the request to provide a sanitary service connection to 23154 128 Avenue be supported and forwarded to the Greater Vancouver Sewerage and Drainage District Board for consideration.

CARRIED

Corporate Services

- 1131 2018 Annual Report and 2018 Statement of Financial Information

Staff report dated June 18, 2019 recommending that the 2018 Annual Report be received and that the 2018 Statement of Financial Information be approved.

R/2019-397

It was moved and seconded

That the 2018 Annual Report be received as required by the Community Charter, and further

That the Statement of Financial Information be approved as required by the Financial Information Act.

CARRIED

Parks, Recreation & Culture

1151 Festival Grant Program Recommendations – Intake Two

Staff report dated June 18, 2019 recommending that festival support allocations for events scheduled between November 1, 2019 to April 30, 2020 be approved.

Note: Councillor Robson recused himself from the vote due to a potential conflict of interest at 8:10 p.m. He stated he may have a personal interest in one of the applications.

R/2019-398

It was moved and seconded

That festival support allocations totaling \$15,580 for events taking place between November 1, 2019 to April 30, 2020, as outlined in Attachment A of this report titled "Festival Grant Program Summary Chart - Intake Two 2019" be approved.

CARRIED

Note: Councillor Robson returned to the meeting. 8:10 p.m.

Administration (including Fire and Police) – Nil

Other Committee Issues – Nil

1200 STAFF REPORTS – Nil

1300 OTHER MATTERS DEEMED EXPEDIENT – Nil

1400 NOTICES OF MOTION AND MATTERS FOR FUTURE MEETINGS – Nil

1500 *MAYOR AND COUNCILLORS' REPORTS*

Council members provided verbal reports on events they attended and those they plan to attend in future.

1600 *ADJOURNMENT* – 8:34 p.m.

Certified Correct

M. Morden, Mayor

L. Benson, Corporate Officer

City of Maple Ridge

SPECIAL COUNCIL MEETING MINUTES

June 25, 2019

The Minutes of the City Council Meeting held on June 25, 2019 at 4:00 p.m. in the Blaney Room, 1st Floor, Maple Ridge City Hall, 11995 Haney Place, Maple Ridge, British Columbia for the purpose of transacting regular City business.

PRESENT

Elected Officials

Mayor M. Morden
Councillor J. Dueck
Councillor C. Meadus
Councillor G. Robson
Councillor R. Svendsen
Councillor A. Yousef

Appointed Staff

K. Swift, Acting Chief Administrative Officer
D. Pope, Acting General Manager Parks, Recreation & Culture
C. Carter, General Manager Planning and Development Services
D. Pollock, General Manager Engineering Services
L. Benson, Director of Corporate Administration

ABSENT

Councillor K. Duncan

Note: These Minutes are also posted on the City's Web Site at www.mapleridge.ca

1.0 **CALL TO ORDER**

2.0 **APPROVAL OF THE AGENDA**

R/2019-373

It was moved and seconded

That the agenda for the June 25, 2019 Special Council Meeting be approved as circulated.

CARRIED

3.0 **NOTICE OF CLOSED COUNCIL MEETING**

R/2019-374

It was moved and seconded

The meeting will be closed to the public pursuant to Section 90(1) and 90(2) of the *Community Charter* as the subject matter being considered relates to the following:

Section 90(1)(a) Personal information about an identifiable individual who holds or is being considered for a position as an officer, employee or agent of the municipality or another position appointed by the municipality.

Section 90(1)(i) The receipt of advice that is subject to solicitor-client privilege, including communications necessary for that purpose.

Section 90(2)(b) The consideration of information received and held in confidence relating to negotiations between the municipality and a provincial government or the federal government or both, or between a provincial government or the federal government or both and a third party.

Any other matter may be brought before the Council that meets the requirements for a meeting closed to the public pursuant to Section 90(1) and 90(2) of the Community Charter or Freedom of Information and Protection of Privacy Act.

CARRIED

4.0 *ADJOURNMENT* – 4:01 p.m.

M. Morden, Mayor

Certified Correct

L. Benson, Corporate Officer

City of Maple Ridge

SPECIAL COUNCIL MEETING MINUTES

July 2, 2019

The Minutes of the City Council Meeting held on July 2, 2019 at 12:45 p.m. in the Blaney Room, 1st Floor, Maple Ridge City Hall, 11995 Haney Place, Maple Ridge, British Columbia for the purpose of transacting regular City business.

PRESENT	Appointed Staff
Elected Officials	K. Swift, Acting Chief Administrative Officer
Mayor M. Morden	D. Boag, Acting General Manager Parks, Recreation & Culture
Councillor J. Dueck	C. Carter, General Manager Planning and Development Services
Councillor C. Meadus	D. Pollock, General Manager Engineering Services
Councillor G. Robson	L. Benson, Director of Corporate Administration
Councillor R. Svendsen	
Councillor A. Yousef	
ABSENT	
Councillor K. Duncan	

Note: These Minutes are also posted on the City's Web Site at www.mapleridge.ca

1.0 **CALL TO ORDER**

2.0 **APPROVAL OF THE AGENDA**

R/2019-399

It was moved and seconded

That the agenda for the July 2, 2019 Special Council Meeting be approved as circulated.

CARRIED

3.0 **NOTICE OF CLOSED COUNCIL MEETING**

R/2019-400

It was moved and seconded

The meeting will be closed to the public pursuant to Section 90(1) and 90(2) of the *Community Charter* as the subject matter being considered relates to the following:

Section 90(1)(c) Labour relations or employee negotiations.

Section 90(1)(e) The acquisition and disposition of land if the council considers that disclosure might reasonably be expected to harm the interests of the municipality.

Any other matter may be brought before the Council that meets the requirements for a meeting closed to the public pursuant to Section 90(1) and 90(2) of the Community Charter or Freedom of Information and Protection of Privacy Act.

CARRIED

4.0 *ADJOURNMENT* – 12:46 p.m.

M. Morden, Mayor

Certified Correct

L. Benson, Corporate Officer

701.1 Development Agreements Committee

**CITY OF MAPLE RIDGE
DEVELOPMENT AGREEMENTS COMMITTEE**

June 19, 2019
Mayor's Office

CIRCULATED TO:

Michael Morden, Mayor
Chair

Kelly Swift, Acting Chief Administrative Officer
Member

Catherine Schmidt, Recording Secretary

1. 16-130581 BG

LEGAL: Strata Lot 35 Section 11 Township 12 New Westminster District
Strata Plan EPS234
PID: 028-284-241
LOCATION: 25442 Godwin Drive
OWNER: Joel and Raquel Logan
REQUIRED AGREEMENTS: Secondary Suite Covenant

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 16-130581 BG.

CARRIED

2. 18-117470 BG

LEGAL: Lot 18 Section 10 Township 12 New Westminster District Plan
EPP70566
PID: 030-108-772
LOCATION: 11091 241A Street
OWNER: Davinder and Kamaljeet Sekhon
REQUIRED AGREEMENTS: Secondary Suite Covenant

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 18-117470 BG.

CARRIED

3. 19-104735 BG

LEGAL: Lot 1 Except: Parcel "C" (Statutory Right of Way Plan 5240); Section
25 Township 9 New Westminster District Plan 3662
PID: 010-993-142

LOCATION: 13540 Neaves Road

OWNER: Manjit and Charan Chatha

REQUIRED AGREEMENTS: Geotechnical Covenant
Floodplain Covenant

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENTS AS THEY RELATE TO 19-104735 BG.

CARRIED

4. 19-105831 BG

LEGAL: Lot 44 District Lot 247 Group 1 New Westminster District Plan 27006
PID: 008-956-987

LOCATION: 21528 River Road

OWNER: Robert and Emily Schlagintweit

REQUIRED AGREEMENTS: Fraser River Escarpment Covenant

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 19-105831 BG.

CARRIED

5. 2015-297-RZ

LEGAL: Lots B, C and E, District Lots 402 and 403 Group 1 New Westminster
District Plan EPP79514
PID: 030-627-770 (Lot B); 030-627-788 (Lot C); 030-627-800 (Lot E)

LOCATION: 23061 Lougheed Highway and 11295 Pazarena Place, and 11280
Pazarena Place

OWNER: Polygon Provincance Homes Ltd.

REQUIRED AGREEMENTS: Statutory Right of Way and Covenant - Trail Agreement

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 2015-297-RZ.

CARRIED

6. 2015-297-RZ

LEGAL: Lot E District Lots 402 and 403 Group 1 New Westminster District
Plan EPP79514
PID: 030-627-800 (Lot E)
LOCATION: 11280 Pazarena Place
OWNER: Polygon Provinance Homes Ltd.
REQUIRED AGREEMENTS: Visitor Parking Covenant

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 2015-297-RZ.

CARRIED

7. 2015-297-RZ

LEGAL: Lot B District Lots 402 and 403 Group 1 New Westminster District
Plan EPP79514
PID: 030-627-770
LOCATION: 23061 Lougheed Highway and 11295 Pazarena Place
OWNER: Polygon Provinance Homes Ltd.
REQUIRED AGREEMENTS: Statutory Right of Way for Sanitary Sewer
Stormwater Management Covenant
Visitor Parking Covenant

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENTS AS THEY RELATE TO 2015-297-RZ.

CARRIED

8. 2015-297-RZ

LEGAL: Lots B and E, District Lots 402 and 403 Group 1 New Westminster
District Plan EPP79514
PID: 030-627-770 (Lot B); 030-627-800 (Lot E)
LOCATION: 23061 Lougheed Highway and 11295 Pazarena Place and; 11280
Pazarena Place
OWNER: Polygon Provinance Homes Ltd.
REQUIRED AGREEMENTS: Cross Access Agreement

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 2015-297-RZ.

CARRIED

9. 2015-297-RZ

LEGAL: Lot C District Lots 402 and 403 Group 1 New Westminster District
Plan EPP79514

PID: 030-627-788

LOCATION: 11300 Pazarena Place

OWNER: Polygon Provinance Homes Ltd.


REQUIRED AGREEMENTS: Visitor Parking Covenant
No Build Covenant (Environmental Sensitive Area)
Housing Agreement and Covenant – Rental and Adaptive
Units

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENTS AS THEY RELATE TO 2015-297-RZ.


CARRIED




Michael Morden, Mayor
Chair



Kelly Swift, Acting Chief Administrative Officer
Member



Scale: 1:1,500



25442 GODWIN



FILE: Untitled
 DATE: Jun 17, 2019

BY: C1

112 AVE.

2

11195

11187

11181

11175

11169

11163

11157

11151

11145

11139

11133

11127

11121

11115

11109

11103

11097

11091

241A ST.

24212

24250

SUBJECT PARCEL

11126

11120

11114

11108

11102

11096

11090

11091 241A ST


ENGINEERING DEPARTMENT




MAPLE RIDGE

British Columbia

mapleridge.ca




Scale: 1:1,500




FILE: Untitled
DATE: Jun 17, 2019

BY: C1




SUBJECT PROPERTY
13540 NEAVES RD

The City of Maple Ridge makes no guarantee regarding the accuracy or present status of the information shown on this map.



Scale: 1:3,000



GEOTECHNICAL & FLOODPLAIN COVENANT

LICENCES, PERMITS & BYLAWS DEPT.



mapleridge.ca

FILE: Untitled
DATE: Jun 18, 2019

BY: TG

RIVER RD.

21564

21554

21544

21536

21528

21520


21512

21508


21500

SUBJECT PROPERTY
21528 RIVER ROAD

The City of Maple Ridge makes no guarantee regarding the accuracy or present status of the information shown on this map.



Scale: 1:800



FRASER RIVER ESCARPMENT COVENANT

LICENCES, PERMITS & BYLAWS DEPT.




MAPLE RIDGE

British Columbia


mapleridge.ca

FILE: Untitled
DATE: Jun 18, 2019

BY: TG



**23061 Lougheed Highway and
11295 Pazarena Place, and 11280
Pazarena Place**




Remaining legal documents related to 2015-297-RZ and related files on one or more lots rezoned.



FILE: 2015-297-RZ
DATE: Jun 17, 2019

BY: MC


Scale: 1:5,000



11280 Pazarena Place



Scale: 1:5,000



Remaining legal documents related to 2015-297-RZ and related files on one or more lots rezoned.




FILE: 2015-297-RZ
DATE: Jun 17, 2019

BY: MC



**23061 Lougheed Highway and
11295 Pazarena Place**

Scale: 1:5,000



Remaining legal documents related to 2015-297-RZ and related files on one or more lots rezoned.


PLANNING DEPARTMENT

mapleridge.ca

FILE: 2015-297-RZ
DATE: Jun 17, 2019
BY: MC



**23061 Lougheed Highway and
11295 Pazarena Place;
11280 Pazarena Place**



Remaining legal documents related to 2015-297-RZ and related files on one or more lots rezoned.




FILE: 2015-297-RZ
DATE: Jun 17, 2019
BY: MC



11300 Pazarena Place



Scale: 1:5,000



Remaining legal documents related to 2015-297-RZ and related files on one or more lots rezoned.



FILE: 2015-297-RZ
DATE: Jun 17, 2019

BY: MC

**CITY OF MAPLE RIDGE
DEVELOPMENT AGREEMENTS COMMITTEE**

June 26, 2019
Mayor's Office

CIRCULATED TO:

Michael Morden, Mayor
Chair

Kelly Swift, Acting Chief Administrative Officer
Member

Catherine Schmidt, Recording Secretary

1. 19-109925 BG

LEGAL: Lot 10 District Lot 280 Group 1 New Westminster District Plan 75819
PID: 008-818-606

LOCATION: 20282 116B Avenue

OWNER: Audrey and Tyson McLellan

REQUIRED AGREEMENTS: Discharge of Covenant (CA7241509)

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 19-109925 BG.

CARRIED

2. 18-122501 BG

LEGAL: Lot 28 Section 29 Township 12 New Westminster District Plan
EPP32166

PID: 029-339-316

LOCATION: 13580 Nelson Peak Drive

OWNER: Dustin and Sarah Clayton

REQUIRED AGREEMENTS: Temporary Residential Use Covenant

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 18-122501 BG.

CARRIED

3. 18-116754 BG

LEGAL: Lot 7 District Lot 396 Group 1 New Westminster District Plan 15728
PID: 010-122-761

LOCATION: 22153 123 Avenue

OWNER: Parmala McIntyre


REQUIRED AGREEMENTS: Sump Pump Covenant

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 18-116754 BG.


CARRIED



Michael Morden, Mayor
Chair




Kelly Swift, Acting Chief Administrative Officer
Member



SUBJECT PROPERTY



Scale: 1:1,000



20282 116B AVE



ENGINEERING DEPARTMENT



mapleridge.ca

FILE: Untitled
DATE: Jun 24, 2019

BY: C1



22153 123 AVE

ENGINEERING DEPARTMENT

mapleridge.ca

FILE: Untitled
DATE: Jun 24, 2019
BY: C1

**CITY OF MAPLE RIDGE
DEVELOPMENT AGREEMENTS COMMITTEE**

July 4, 2019
Mayor's Office

CIRCULATED TO:

Michael Morden, Mayor
Chair

Kelly Swift, Acting Chief Administrative Officer
Member

Catherine Schmidt, Recording Secretary

1. 17-122484 BG

LEGAL: Strata Lot 41 Section 11 Township 12 New Westminster District
Strata Plan EPS234
PID: 028-284-305
LOCATION: 25518 Godwin Drive
OWNER: Amardeep, Jasmin and Jasvir Dhaliwal
REQUIRED AGREEMENTS: Secondary Suite Covenant

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 17-122484 BG.

CARRIED

2. 19-104730 BG

LEGAL: Lot 2 District Lot 279 Group 1 New Westminster District Plan
EPP81369
PID: 030-540-127
LOCATION: 20448 Chigwell Street
OWNER: Derek Sousa and Faithe Pogany
REQUIRED AGREEMENTS: Flood Protection Covenant
Release of Covenant (CA6999835 and CA6999836)

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENTS AS THEY RELATE TO 19-104730 BG.

CARRIED

3. 18-110129

LEGAL: Lot 11 Section 19 Township 12 New Westminster District Plan
BCP48758
PID: 028-626-559
LOCATION: 26465 121 Avenue
OWNER: Horacio and Katherine Rojas
REQUIRED AGREEMENTS: Sanitary Sump Pump Covenant

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 18-110129.

CARRIED

4. 18-106274 BG

LEGAL: Lot K Section 10 Township 12 New Westminster District Plan
NWP19820
PID: 010-588-931
LOCATION: # 1 - 24705 108 Avenue
OWNER: Andres and Brigitta Schneider
REQUIRED AGREEMENTS: Detached Garden Suite Covenant
Detached Garden Suite Parking Covenant

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENTS AS THEY RELATE TO 18-106274 BG.

CARRIED

5. 18-111600 BG

LEGAL: Lot 23 Section 32 Township 12 New Westminster District Plan 13709
PID: 009-850-643
LOCATION: 13726 224 Street
OWNER: Jing Lu and Zhen Liu
REQUIRED AGREEMENTS: Flood Protection Covenant

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 18-111600 BG.

CARRIED

6. 19-105881 BG

LEGAL: Lot 42 District 405 Group 1 New Westminster District Plan
EPP56457
PID: 029-775-159
LOCATION: 10308 238A Street
OWNER: Tammy and Ryan Pavan
REQUIRED AGREEMENTS: Temporary Residential Use Covenant

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 19-105881 BG.

CARRIED

7. 2015-297-RZ

LEGAL: Lot 3 District Lot 402 and 403 Group 1 New Westminster District
Plan EPP71200
PID:
LOCATION: No Address Assigned
OWNER: Polygon Provenance Homes Ltd.
REQUIRED AGREEMENTS: Property Transfer Tax Form

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 2015-297-RZ.

CARRIED

8. 18-111353 BG

LEGAL: Lot 9 Section 29 Township 12 New Westminster District Plan
EPP60285
PID: 030-229-286
LOCATION: 23046 135 Avenue
OWNER: 1132743 B.C. Ltd. (Jharmal Dhaliwal)
REQUIRED AGREEMENTS: Secondary Suite Covenant

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 18-111353 BG.

CARRIED

9. 2016-176-RZ


LEGAL: Lot 4 Section 28 Township 12 New Westminster District Plan
EPP73927
PID: 030-395-178
LOCATION: 23710 133 Avenue
OWNER: Hillside Ventures Ltd. / City of Maple Ridge
REQUIRED AGREEMENTS: Release of Covenants (CA6670960 Geotechnical,
CA6670962 Stormwater, CA6670971 No Build)

THAT THE MAYOR AND CORPORATE OFFICER BE AUTHORIZED TO SIGN AND SEAL THE PRECEDING DOCUMENT AS IT RELATES TO 2016-176-RZ.


CARRIED




Michael Morden, Mayor
Chair



Kelly Swift, Acting Chief Administrative Officer
Member



Scale: 1:1,500



25518 Godwin Drive

ENGINEERING DEPARTMENT




MAPLE RIDGE

British Columbia

mapleridge.ca

FILE: Untitled
DATE: Jun 27, 2019


BY: C1



The City of Maple Ridge makes no guarantee regarding the accuracy or present status of the information shown on this map.



Scale: 1:2,800



20448 Chigwell St.
Section 219 Flood Protection,
Release of former flood covenant


LICENCES, PERMITS & BYLAWS DEPT.



mapleridge.ca


FILE: Untitled
 DATE: Jun 28, 2019

BY: ML



Subject Parcel

The City of Maple Ridge makes no guarantee regarding the accuracy or present status of the information shown on this map.



26465 121 Ave.
Section 219 Sanitary Sump /Pump Covenant

LICENCES, PERMITS & BYLAWS DEPT.




MAPLE RIDGE
British Columbia

mapleridge.ca

FILE: Untitled
 DATE: Jun 28, 2019
 BY: ML



SUBJECT PROPERTY



Scale: 1:2,000

24705 108 Ave


ENGINEERING DEPARTMENT

MAPLE RIDGE


British Columbia

mapleridge.ca

FILE: Untitled
DATE: Jun 28, 2019
BY: C1



Scale: 1:2,000




**13726-224 STREET
FLOOD PLAIN COVENANT**


LICENCES, PERMITS & BYLAWS DEPT.

mapleridge.ca

FILE: Untitled
DATE: Jun 28, 2019
BY: JP



Scale: 1:1,000





10308 238A ST

ENGINEERING DEPARTMENT

mapleridge.ca

FILE: Untitled
DATE: Jun 28, 2019

BY: C1



**Lot 3 District Lot 402 and 403
Group 1 NWD Plan EPP71200**

PLANNING DEPARTMENT





MAPLE RIDGE
British Columbia

mapleridge.ca


Scale: 1:2,500

DATE: Jul 2, 2019

BY: DT



Scale: 1:2,000



23046 135 Ave

ENGINEERING DEPARTMENT



MAPLE RIDGE


British Columbia

mapleridge.ca

FILE: Subject_Map10.4.1

DATE: Jul 2, 2019

BY: MC



Scale: 1:2,000

Legend

-  Stream
-  Ditch Centreline
-  Indefinite Creek
-  Active Applications (RZ/SD/DP/VP)

23710 133 AVENUE

PLANNING DEPARTMENT



MAPLE RIDGE
British Columbia

mapleridge.ca

FILE: 2016-176-RZ
DATE: Jul 10, 2018

BY: LP

701.2 Minutes of Meetings of Committees and Commissions of Council

City of Maple Ridge
ACTIVE TRANSPORTATION ADVISORY COMMITTEE
REGULAR MEETING

The Minutes of the Regular Meeting of the Active Transportation Advisory Committee, held in the Blaney Room, at Maple Ridge City Hall on May 29, 2019 at 7:01 pm.

COMMITTEE MEMBERS PRESENT

Councillor Ahmed Yousef	Council Liaison
Vijay Soparkar, Chair	Member at Large
Colette Trudeau	School Trustee
Gary Hare, Vice Chair	Seniors Community Representative
Jennifer Wright	Member at Large - Cycling Representative
Kim McLennan	Municipal Advisory Committee on Accessibility and Inclusiveness Representative

STAFF MEMBERS PRESENT

Purvez Irani	Manager of Transportation / Staff Liaison
Amanda Allen	Committee Clerk

GUESTS

Councillor Meadus	Council Liaison – alternate
Pascale Shaw	School Trustee – alternate

ABSENT

Cpl. Steven Martin	Ridge Meadows RCMP – Traffic Services
Ineke Boekhorst	Downtown Maple Ridge Business Improvement Association

Note: Councillor Yousef chaired the meeting as the presiding member

Note: Jennifer Wright participated via GoToMeeting

1. **CALL TO ORDER**
2. **APPROVAL OF THE AGENDA**

R/2019-004

It was moved and seconded

That the agenda for the May 29, 2019 Active Transportation Advisory Committee be approved as circulated.

CARRIED

3. **ADOPTION OF THE MINUTES**

R/2019-005

It was moved and seconded

That the minutes of the Maple Ridge Active Transportation Advisory Committee meeting dated September 26, 2018 and April 24, 2019 be adopted.

CARRIED

4. *DELEGATION* - Nil

5. *QUESTION PERIOD* - Nil

6. *NEW AND UNFINISHED BUSINESS*

6.1. 2019 Chair and Vice Chair Elections

The staff liaison opened the floor to nominations for a Chair.

R/2019-006

It was moved and seconded

That Vijay Soparkar be elected Chair of the Active Transportation Advisory Committee for 2019.

CARRIED

The staff liaison opened the floor to nominations for a Vice Chair.

R/2019-007

It was moved and seconded

That Gary Hare be elected Vice Chair of the Active Transportation Advisory Committee for 2019.

CARRIED

Note: Vijay Soparkar assumed the Chair.

6.2. Seniors Issues Affecting Active Transportation in Maple Ridge

Gary Hare gave a PowerPoint presentation '*Think Senior*' highlighting the importance of safety and senior friendly infrastructure that enables seniors to participate in modes of active transportation. There was discussion on the separation of walk and bikeways from traffic, multi-use pathways and the 'complete street' concept. The staff liaison reviewed the phased plan of the TransLink B Line project.

6.3. Topics for future meetings

There was discussion on potential topics and the following items and concepts were identified:

- Active neighbourhoods;
- Walkability of downtown corridor (224 Street from 124 Avenue to 117 Avenue) for all ages and abilities;
- Safe and secure bicycle parking;
- Identify barriers/challenges for children walking/cycling to school;
- Utilize mapping technology to identify and educate active transportation opportunities for families in proximity to local schools;

- Partnered education campaigns around behaviours in school zones;
- Walk 30 challenge between communities / schools;

There was discussion on programs that teach children road and cycling safety and the staff liaison will look into City of Maple Ridge participation into such programs and report back at a future meeting.

7. *CORRESPONDENCE* - Nil

8. *ROUNDTABLE*

Members received verbal reports on relevant activities and active transportation topics.

Kim McLennan will bring information on school planning through best practices learned in other communities to a future meeting.

Jennifer Wright will bring information about the in-school HUB program to a future meeting.

It was also noted that that 3 positions were vacant: 2 Members at Large and 1 Youth Representative.

9. *ADJOURNMENT* – 8:23 pm.

“Original signed by Vijay Soparkar”
Vijay Soparkar, Chair

/aa

City of Maple Ridge
AGRICULTURAL ADVISORY COMMITTEE
MEETING MINUTES

The Minutes of the Regular Meeting of the Agricultural Advisory Committee, held in the Blaney Room,
at Maple Ridge Municipal Hall on May 23, 2019 at 7:05 pm.

COMMITTEE MEMBERS PRESENT

Councillor Gordy Robson	City of Maple Ridge
Councillor Ryan Svendsen	City of Maple Ridge
Bill Hardy, Chair	Member at Large
Al Kozak, Vice Chair	Agricultural Sector
Andrew Pozsar	Member at Large
Carla Schiller	Agricultural Sector
Ian Brooks	Member at Large
Michelle Franklin	Member at Large
Pascale Shaw	Agricultural Sector
Ryan Murphy	Agricultural Sector

STAFF MEMBERS PRESENT

Amanda Grochowich	Staff Liaison / Planning Department
Amanda Allen	Committee Clerk

ABSENT

Candace Gordon	Haney Farmers Market Society
Chris Zabek	Regional Agrologist, Ministry of Agriculture
Lorraine Bates	Agricultural Fair Board

1. **CALL TO ORDER**
2. **APPROVAL OF THE AGENDA**

R/2019-021

It was moved and seconded

That the May 23, 2019 Agricultural Advisory Committee agenda be approved as circulated.

CARRIED

3. **ADOPTION OF THE MINUTES**

R/2019-022

It was moved and seconded

That the minutes of the Maple Ridge Agricultural Advisory Committee meeting dated April 25,
2019 be adopted.

CARRIED

4. **DELEGATIONS – Nil**

5. **QUESTION PERIOD**

Mary Robson provided information on the Friends In Need Food Bank perishable food recovery program. Ms. Robson advised that operations in the downtown facility should be completed by 2:00pm daily and discussion is underway with Vancouver Farmers Markets Direct for possible afternoon use of the facility. Ms. Robson answered questions from the committee.

Note: Councillor Robson left the meeting at 7:17 pm and did not return.

6. **NEW AND UNFINISHED BUSINESS**

6.1. **Farm Stand Directional Signage**

There was discussion on advertising farm food sales and how Booth in a Box could help map farm stands. The Chair and Ryan Murphy will meet with staff to further discuss next steps on communicating AAC support for a farm stand directional signage program.

6.2. **Golden Harvest**

The staff liaison advised that Golden Harvest 2019 has been cancelled and the subcommittee is working to reimagine the program for 2020. Members were invited to join the subcommittee discussions on the new Golden Harvest format.

6.3. **Prioritization of Agricultural Plan Action Items**

The Chair reported Booth in the Box work is underway and results of Metro Vancouver Agriculture Awareness grant application should be forthcoming.

The Chair has identified a resource that could easily be adapted to fit a Maple Ridge Community Garden tool kit.

6.4. **Backyard Chickens**

The staff liaison provided a high level overview of the program direction and advised a report will proceed to Council in June. There was discussion on the setbacks, lot size, and programs and models in other municipalities.

R/2019-023

It was moved and seconded

That the Agricultural Advisory Committee support the proposed direction of the backyard hen program for residential areas in Maple Ridge, ideally incorporating a smaller lot size similar to the City of North Vancouver and City of Surrey.

CARRIED

7. *SUBCOMMITTEE REPORTS*

7.1. *Food Garden Contest*

The staff liaison reported several applications have been submitted and that the entry deadline is June 30, 2019. Members were encouraged to spread news of the contest and there was discussion to include community gardens as part of the 2020 Food Garden contest.

8. *CORRESPONDENCE* - Nil

9. *ROUNDTABLE*

Members received verbal reports on local agricultural topics and activities and expressed interest in participating in a Farm Tour.

10. *ADJOURNMENT* - 8:31 pm.

"Original signed by B. Hardy"

Bill Hardy, Chair

/aa

TO: His Worship Mayor Michael Morden
and Members of Council

FROM: Chief Administrative Officer

SUBJECT: Albion Community Centre Background Information for the Expression of Interest (EOI) Process

MEETING DATE: July 9, 2019

FILE NO: 2247162

MEETING: Council Meeting

EXECUTIVE SUMMARY:

At the May 28, 2019 Council Meeting, staff presented an update on the Albion Community Centre (ACC) construction project process. At that time, Council directed staff to bring background information on the previously proposed Expression of Interest process for a facility operator to a subsequent meeting. This report responds to this Council direction.

RECOMMENDATION:

No resolution required. For Information only.

DISCUSSION:

a) Background Context:

In the early stage of the Parks, Recreation & Culture (PRC) Infrastructure Concepts discussion, Council expressed interest in a third party operator, with the YMCA of Greater Vancouver (YMCA) suggested as an organization for a potential partnership. In July 2017, Council directed staff to meet with the YMCA to discuss opportunities for partnerships in Maple Ridge, including the ACC, and following that, to facilitate a conversation with School District No. 42 (SD42) and the YMCA to explore the feasibility of a tri-party agreement for the operation of the ACC on this joint park/school site. Initial discussions between the parties were held, and in June 2018 Council directed staff to conduct a call for Expressions of Interest (EOI) for the operation and program servicing of the ACC and to form a Task Group composed of City and SD42 staff to develop a recommendation regarding a tri-party agreement.

Through this conversation, key considerations were identified in the feasibility of such an agreement, including ensuring that a competitive procurement process for the operation of the ACC is followed, that the operating model selected reflects the programming needs identified through community consultation processes and is consistent with SD42's policies and procedures, and the requirement to obtain Board of Education approval.

The Task Group and EOI development process is timed to be completed later this year, with the intent to release the EOI in January 2020.

Community Consultation & Building Design

The City performs community consultation processes when designing new facilities to ensure stakeholders have input in services and programs available to them. Feedback received from several consultations undertaken through 2016, 2017 and 2018 have informed the design of this project including a joint community consultation by SD42 and the City, broader City-led community consultation focused on the Centre's program and design including online surveys and stakeholder meetings including performing arts groups, daycare providers, Ridge Meadows Seniors Society, the Seniors Network and Community Network. The consultations were open to both the immediate neighbourhood and broader community through the conceptual and detailed design phases.

Staff retained an Architectural design team to complete the ACC's detailed design based on this community feedback. The YMCA attended and participated in the 2018 process as one of many stakeholder groups who provided input into the design of the facility.

Operating Model

The City of Maple Ridge uses a number of operating models at its facilities such as direct service (City Staff), partnership agreements and contract services. The City engages contract services when it is deemed to be beneficial to citizens and may include reasons such as expertise in the field (Arts Council, RG Properties), financial sustainability, and operating efficiencies. In this particular case, Council directed staff to investigate a potential partnership with the YMCA. The YMCA conducted a feasibility study and has identified Maple Ridge, specifically the Albion area, as an attractive location for its model. The YMCA feels they could build on existing relationships between the School District and the City and further engage as a strategic and complementary partner in the provision of services to the community.

Procurement Process

The procurement process includes an open call for Expressions of Interest (EOI) for facility operations and program delivery and a subsequent Request for Proposals (RFP) from the pre-qualified proponents. The EOI is under development and will be further informed during the Task Group discussions with SD42 to be completed later this year. While phase one site works are currently underway, the tendering for the construction of the building itself was delayed to qualify for a Recreation Infrastructure Grant which is anticipated to be announced by the end of 2019. Tendering for the building construction is anticipated for January 2020 and building completion by the end of 2020. The EOI is proposed to launch no sooner than a year in advance of the building construction completion and with this in mind, the EOI release would be targeted for January 2020.

b) Desired Outcome:

The desired outcome is to ensure that the most effective and efficient operating model is in place at the ACC, reflecting programming needs identified in the community consultation processes, so that the neighbourhood and community are well-served.

c) Strategic Alignment:

This project aligns with the 2010 City of Maple Ridge Parks, Recreation & Culture Master Plan, the 2015 SD42 Board of Education Strategic Facilities Plan, and with the 2017 Master Agreement on Cooperation for the Joint Use of Public Facilities and Coordination of Services. The project is also consistent with the City's Official Community Plan for the Albion Area.

d) Business Plan/Financial Implications:

At the concept development stage, an annual operating budget was projected for financial planning purposes based on a City-operated facility. The financial details for an operating

agreement with external parties will need to be negotiated and brought back to Council at the appropriate time.

e) Alternatives:


If Council does not wish to pursue a third party operator for the ACC at this time, staff could continue to work with SD42 on a joint operating model for the ACC that maximizes community access to Cæsçenele Elementary School and the Neighbourhood Learning Centre while garnering operational efficiencies, and could then explore other potential partnership opportunities with the YMCA and others to continue to strengthen these relationships over time.

CONCLUSION:

As the ACC is anticipated to be completed at the end of 2020, there remains time for Council to consider the operational needs to align with the community's input and the most efficient and effective delivery method for this. SD42 is a significant partner in the operation of the joint school/community site that will continue to be closely involved in the development of the EOI. Should Council choose to pursue a contract services provider, a tri-party joint use agreement would be required to move forward with endorsement by City Council and the Board of Education.


Prepared by: **Don Cramb**
Senior Recreation Manager


Reviewed by: **Valoree Richmond**
Acting Director of Parks & Facilities


Approved by: **David Boag**
Acting General Manager Parks, Recreation & Culture


Concurrence: **Kelly Swift, MBA**
Acting Chief Administrative Officer

TO: His Worship Mayor Michael Morden
and Members of Council
FROM: Chief Administrative Officer
SUBJECT: Final Reading:
Official Community Plan Amending Bylaw No. 7172-2015
Zone Amending Bylaw No. 7173-2015
23702 132 Avenue

MEETING DATE: July 9, 2019
FILE NO: 2015-155-RZ
MEETING: COUNCIL

EXECUTIVE SUMMARY:

Bylaw(s) 7172-2015 and 7173-2015 has/have been considered by Council and at Public Hearing and subsequently were granted Third Reading. The applicant has requested that Final Reading be granted. The purpose of the rezoning is to permit the subdivision into 16 lots not less than 557 m².

Council granted first reading for Zone Amending Bylaw No. 7173-2015 on April 26, 2016. Council granted first and second reading for Official Community Plan Amending Bylaw No. 7172-2015 on November 14, 2017, and second reading for Zone Amending Bylaw No. 7173-2015 on November 14, 2017. This application was presented at Public Hearing on December 5, 2017, and Council granted third reading on December 5, 2017. A six month extension was granted on May 5, 2019.

RECOMMENDATION:

That Official Community Plan Amending Bylaw No. 7172-2015 be adopted; and

That Zone Amending Bylaw No. 7173-2015 be adopted.

DISCUSSION:

a) Background Context:

Council considered this rezoning application at a Public Hearing held on December 05, 2017. On December 05, 2017 Council granted Third Reading to Official Community Plan Amending Bylaw No. 7172-2015 and Zone Amending Bylaw No. 7173-2015 with the stipulation that the following conditions be addressed:

Subsequent to the Public Hearing, Council gave third reading to the subject bylaws on December 5, 2017 and further resolved that prior to any reconsideration of the said bylaws the following conditions must be satisfied:

Subsequent to the Public Hearing, Council gave third reading to the subject bylaws on December 5, 2017 and further resolved that prior to any reconsideration of the said bylaws the following conditions must be satisfied:

- a. **Registration of a Rezoning Servicing Agreement as a Restrictive Covenant and receipt of the deposit of a security, as outlined in the Agreement;**

This requirement has been shifted as a requirement of subdivision, to be met with a subdivision servicing agreement, and deposit of security.

- b. **Amendment to Official Community Plan Schedule “A”, Chapter 10.3, Part VI, A – Silver Valley, Figure 2 - Land Use Plan, and Figure 3C - River Hamlet, Figure 4 - Trails / Open Space,**

This requirement will be met with final reading.

- c. **Registration of a Restrictive Covenant for the Geotechnical Report which addresses the suitability of the subject property for the proposed development;**

This requirement has been shifted as a requirement of subdivision.

- d. **Registration of a No Build / No Disturb Restrictive Covenant for the protection of the Environmentally Sensitive areas on the subject property;**

This requirement has been shifted as a requirement of subdivision.

- e. **Registration of a Statutory Right-of-Way plan and agreement for servicing easement;**

This requirement has been shifted as a requirement of subdivision.

- f. **Registration of a Restrictive Covenant for Stormwater Management;**

This requirement has been shifted as a requirement of subdivision.

- g. **Notification to the Department of Fisheries and Oceans and the Ministry of Environment for in-stream works on the site; and**

This requirement has been met.

- h. **That a voluntary contribution, in the amount of \$81,600.00 (\$5100.00/lot) be provided in keeping with the Council Policy with regard to Community Amenity Contributions.**


This requirement has been met.

CONCLUSION:

As the applicant has met Council's conditions, it is recommended that Final Reading be given to Official Community Plan Amending Bylaw No. 7172-2015 and Zone Amending Bylaw No. 7173-2015.




Prepared by: **Diana Hall, M.A, MCIP, RPP**
Planner 2



Reviewed by: **Charles R. Goddard, BA, MA**
Director of Planning



Approved by: **Christine Carter, M.PL, MCIP, RPP**
GM Planning & Development Services




Concurrence: **Kelly Swift, MBA**
Acting Chief Administrative Officer

The following appendices are attached hereto:

- Appendix A – Subject Map
- Appendix B – Zoning Bylaw No. 7173-2015.
- Appendix C – OCP Bylaw No. 7172-2015
- Appendix D – (Subdivision Plan)

APPENDIX A



SUBJECT PROPERTY



Scale: 1:2,500

Legend

- Wetlands
- GPS Creek Centrelines
- Streams & Rivers (Topographic)**
- Feature Type**
- Indefinite Creek Centreline
- Ditch Centreline
- River Centreline
- Rivers & Lakes (Topographic)**
- Feature Type**
- Lake/Reservoir

23702 132 AVENUE



CITY OF MAPLE RIDGE
PLANNING DEPARTMENT

DATE: Jun 1, 2015 FILE: 2015-155-RZ BY: PC

1100 *Committee Reports and Recommendations*

Items in Section 1100 *Committee Reports and Recommendations* that refer to a staff report earlier than this agenda date were presented at a Committee of the Whole Meeting typically a week prior, on the date of the staff report, to provide Council with an opportunity to ask staff detailed questions. The items are now before regular Council Meeting for debate and vote. Both meetings are open to the public. The reports are not reprinted again in hard copy; however they can be found in the electronic agenda or in the Committee of the Whole agenda package dated accordingly.



mapleridge.ca

City of Maple Ridge

TO: His Worship Mayor Michael Morden
and Members of Council

FROM: Chief Administrative Officer

MEETING DATE: July 2, 2019
FILE NO: 2019-183-AL
MEETING: C o W

SUBJECT: Application to Exclude Land from the Agricultural Land Reserve
12176 237 Street

EXECUTIVE SUMMARY:

An application has been received under Section 30 (1) of the Agricultural Land Commission Act to exclude approximately 1.12 hectares (2.8 acres) of land from the Agricultural Land Reserve. The applicant's submission conforms with the notice of application requirements of the Agricultural Land Commission. If this application is successful, it would be converted to urban residential uses.

This property is designated Agricultural in the Official Community Plan and in the Regional Growth Strategy of Metro Vancouver. Redevelopment of this property for urban uses would be contrary to these long range plans and would require approval from municipal, regional, and provincial agencies. On this basis, this application could be considered not supportable.

The recommendation of this report has been provided in accordance with Council direction for applications for exclusion from the Agricultural Land Reserve. However, other options for Council's consideration are presented in the Alternatives section of this report.

RECOMMENDATION:

In accordance with Council direction for applications for exclusions from the Agricultural Land Reserve, the following resolutions are provided for Council's consideration:

- a) That the application not be authorized to go forward to the Agricultural Land Commission;
- b) That the application be authorized to go forward to the Agricultural Land Commission with a summary of Council's comments and the staff report.

DISCUSSION:

a) Background Context:

Applicant: R C B Enterprises Limited

Legal Description: Lot: 2, Section: 21, Township: 12, Plan: NWP72342

OCP :
Existing: AGR (Agricultural)

Zoning:
Existing: RS-3 (One Family Rural Residential)

1101

Surrounding Uses

North:	Use:	Rural Residential
	Zone:	A-2 Upland Agriculture
	Designation:	Agriculture
South:	Use:	Rural Residential
	Zone:	RS-3 One Family Rural Residential
	Designation:	Agricultural
East:	Use:	3 properties, urban residential
	Zone:	RS-1b One Family Urban Medium Density Residential
	Designation:	Urban Residential
West:	Use:	Townhouse Residential
	Zone:	RM-1 Townhouse Residential
	Designation:	Urban Residential
Existing Use of Property:		vacant
Proposed Use of Property:		urban residential
Site Area:		1.12 hectares (2.8 acres)
Access:		237 th Street
Servicing:		On-site sewer and water

b) Project Description:

This application is to exclude the subject property from the Agricultural Land Reserve. The applicant intends to develop the property for residential uses to an urban standard. If excluded from the ALR, this property would require an amendment to Metro Vancouver's Regional Growth Strategy prior to urban redevelopment.

c) Planning Analysis:

On July 19, 2004, a report for processing exclusion applications was received by Council outlining legal implications and the local government's role in processing applications for exclusion from the Agricultural Land Reserve. Council resolved to consider the following options for referring applications to the Agricultural Land Commission:

- The application be authorized to go forward to the Agricultural Land Commission with no comment.
- The application be authorized to go forward to the Agricultural Land Commission with comments.
- The application be authorized to go forward to the Agricultural Land Commission with a recommendation to exclude the property with or without comments.
- The application be authorized to go forward to the Agricultural Land Commission with a recommendation to not exclude the property with or without comments.
- The application not be authorized to go forward to the Agricultural Land Commission.

The process for decision making on applications for exclusion from the Agricultural Land Reserve was further refined by Council at their February 14, 2005 Workshop. At that time, Council resolved that the process for referring applications for exclusion to the Agricultural Land Commission include the following options:

- a) *That the application not be authorized to go forward to the Agricultural Land Commission;*
- b) *That the application be authorized to go forward to the Agricultural Land Commission with a summary of Council's comments and the staff report.*

The above resolution forms the recommendations presented in this staff report. To assist Council in the decision of allowing this application to proceed further, this development proposal will be reviewed in light of the policies of the Official Community Plan and the Agricultural Plan.

OFFICIAL COMMUNITY PLAN

The Official Community Plan, adopted by Council on November 14, 2006, provides a policy context that has relevance to this application, and the agricultural future of the subject property. The following outlines some of the relevant sections from the Official Community Plan.

Official Community Plan Agricultural Policies

The Maple Ridge Official Community Plan emphasizes the value of agriculture in contributing to the local economy and to the rural character of the community. It is noted that Maple Ridge agriculture faces considerable challenges, but there is consistent community support for local farming. Policy 6-12 of the Official Community Plan states:

Maple Ridge will protect the productivity of its agricultural land by:

- a) *Adopting a guiding principal of "positive benefit to agriculture" when making land use decisions that could affect the agricultural land base, with favourable recognition of initiatives including but not limited to supportive non-farm uses, infrastructure improvements for farmland, or the inclusion of land elsewhere in the Agricultural Land Reserve;*
- b) *requiring agricultural impact assessments (AIAs) and Groundwater Impact Assessment of non-farm development and infrastructure projects and identifying measures to off-set impacts on agricultural capability;*
- c) *preserving larger farm units and areas by using appropriate buffers such as roads, topographic features, watercourses, ditching, fencing, or gradually reduced residential densities on properties adjacent to agricultural land;*
- d) *discouraging the subdivision of agricultural land into smaller parcels, except where positive benefits to agriculture can be demonstrated;*
- e) *reinforcing the concept that the Agricultural Land Reserve is intended for agricultural use by increasing the minimum lot size for ALR properties that are zoned Rural Residential;*
- f) *encouraging the amalgamation of smaller parcels of farmland into larger, more cohesive parcels.*

Section 6.2 of the Official Community Plan, which pertains to Agricultural opportunities. states that the value of agriculture is consistently recognized and supported within the community, as follows:

Agricultural land is a key component of the Metro Vancouver Regional Growth Strategy and provides many benefits of local and regional significance. As an economic generator it contributes to a more complete community.

Official Community Plan - Growth Management Policies

Section 2.1 of the Official Community Plan states that in Maple Ridge the majority of the growth in population, jobs and housing will be accommodated within the Urban Area Boundary where services are readily available or infrastructure is already in place. The subject property forms the legal boundary of the Agricultural Land Reserve at this location. The Official Community Plan emphasized that adjustments to the Urban Area Boundary, if required, must follow a specified process.

Although additional adjustments may occur in the future, this process was generally concluded, thereby clarifying the location of the Urban Area Boundary, through the completion of the Maple Ridge Agricultural Plan in 2009 and the adoption of the Metro Vancouver Regional Growth Strategy in 2011.

The 2 parcels to the south of the subject property have both been excluded (12146 237th & 12102 237th Street) from the Agricultural Land Reserve since the 2006 adoption of the Official Community Plan. They were included in an amendment to Metro Vancouver's Livable Region Strategic Plan from Agriculture to an Urban Designation, and subsequently, they were both designated urban in the Regional Growth Strategy. This amendment process was lengthy, and involved collaboration between the agencies involved (Metro Vancouver and member municipalities, and the ALC). The subject property was not part of this amendment process, and for this reason, the urban development of the subject property is not supportable.

AGRICULTURAL PLAN

The Maple Ridge Agricultural Plan, adopted by Council on December 15, 2009, provided additional direction for advancing agricultural opportunities in Maple Ridge. Although adopted, specific actions related to the implementation of the Plan are currently being prioritized by Council. Pertinent excerpts of the Plan are included below.

Issue 1 in the Agricultural Plan notes the difficulty faced by farmers in gaining access to underutilized agricultural land. Specific issues included the following:

- *Absentee landlords*
- *Agricultural land held in idle state*
- *Landless operators unable to find land to farm*
- *High land cost restricts access.*

The Plan indicates that an appropriate means to address these issues would be to encourage non-farming land owners to make idle land available to farmers or to start farming it themselves. The Plan notes the need to re-emphasize the role of agriculture in the Agricultural Land Reserve and to address the perception that the Agricultural Land Reserve is a land reserve for eventual non-agricultural development in Maple Ridge.

Issue 5 of the Agricultural Plan discusses the loss of the agricultural land base and notes the following specific issues:

- *Many small parcels*
- *High level of rural residential incursion into Agricultural Land Reserve*
- *Non-farmed areas of the Agricultural Land Reserve tend to be smaller parcels*
- *Limited availability of irrigation water*
- *Continued conversion pressure from the District of Maple Ridge's urban growth*
- *Financial pressure on farming*

The Agricultural Plan recognizes that there may be situations in the future where exclusions may be required to meet community needs, for example employment generating lands. In instances where land conversion is unavoidable, levies or other means may be established by the City in order to compensate for the loss of agricultural land.

Goal 6 of the Plan discusses the issue of the conversion of agricultural land as follows:

The primary goal with respect to larger established farming operations in Maple Ridge is to plan for their retention as farms, rather than watch them languish and deteriorate, so that the community can optimize the rewards and advantages of having agriculture in its midst.

Limited to highly specific situations, the secondary goal (if the primary goal is not feasible) is to explore establishing a policy of compensation from development that enables funds to be generated and expended so that the net agricultural capability of the District is enhanced by investment elsewhere.

INTERGOVERNMENTAL AGENCIES

Agricultural Land Commission

The Commission has established guidelines for local governments regarding the timing of application processing. These guidelines are provided by the Commission in their document, the *Agricultural Land Reserve Use, Subdivision And Procedure Regulation*. The local government is normally required to address the application within 60 days of its receipt under Section 21.1 of this Regulation, but has an option to hold a public meeting which would extend the application processing time to 90 days.

Metro Vancouver

The subject property is designated for Agricultural use in the Official Community Plan. If the property was excluded from the Agricultural Land Reserve, its Agricultural designation would remain in the Official Community Plan. Any change in permitted uses would require an amendment to the Official Community Plan, which in turn would require the approval of Metro Vancouver to amend the Regional Growth Strategy. This type of amendment would be considered by Metro Vancouver to be a Type 2 Minor Amendment. The bylaw amendment process would include a regional public hearing and a two-thirds weighted vote of the Metro Vancouver Board. In this instance, the municipal government would apply for the amendment to Metro Vancouver.

d) Alternatives:

The report recommendations follow Council direction as noted earlier in this report. The property has not been identified for exclusion from the Agricultural Land Reserve, and is not considered available for urban development in the Regional Growth Strategy. On this basis, this application could be considered not supportable.

CONCLUSION:

This application for exclusion from the Agricultural Land Reserve has been considered in the context of the policies of the Official Community Plan, and the Agricultural Plan. On review of this context, this application is found to be not supportable. However, the report recommendation has been prepared in accordance with previous Council direction for applications for exclusion from the Agricultural Land Reserve.

"Original Signed by Diana Hall"

Prepared by: **Diana Hall, MA (Planning), MCIP
Planner II**

"Original signed by Chuck Goddard"

Reviewed by: **Charles R. Goddard, BA, MA
Director of Planning**

"Original signed by Chuck Goddard" for

Approved by: **Christine Carter, M.PL, MCIP, RPP
GM Planning & Development Services**

"Original signed by Kelly Swift"

Concurrence: **Kelly Swift, MBA
Acting Chief Administrative Officer**

The following appendices are attached hereto:
Appendix A – Subject Map
Appendix B – Ortho Map



SUBJECT PROPERTY



Scale: 1:3,000

Legend

-  Stream
-  Ditch Centreline
-  Indefinite Creek
-  Lake or Reservoir

12176 237 STREET
PID: 004-588-347

PLANNING DEPARTMENT



MAPLE RIDGE

British Columbia

mapleridge.ca

FILE: 2019-183-AL
DATE: May 23, 2019

BY: PC

APPENDIX B




SUBJECT PROPERTY

Aerial Imagery from the Spring of 2018



Scale: 1:3,000



12176 237 STREET
PID: 004-588-347

PLANNING DEPARTMENT



MAPLE RIDGE
British Columbia

mapleridge.ca

FILE: 2019-183-AL
DATE: May 23, 2019

BY: PC



mapleridge.ca

City of Maple Ridge

TO: His Worship Mayor Michael Morden
and Members of Council

FROM: Chief Administrative Officer

MEETING DATE: July 2, 2019
FILE NO: 2019-126-AL
MEETING: C o W

SUBJECT: Application for non-adhering residential uses in the Agricultural Land Reserve
12392 248 Street

EXECUTIVE SUMMARY:

This application is for residential development within the Agricultural Land Reserve (ALR). The applicant cannot proceed with this development proposal unless it is approved by the Agricultural Land Commission (ALC).

The applicant had been working on the development proposal in compliance with Farm Home Plate regulations and met with municipal staff to review the development plans. The ALC regulations for residential development were changed prior to an application for a building permit being made. This proposal generally complied with existing regulations when it was initiated and therefore is found to be supportable. However, a variance may be required to approve the attached garage structure due to its size.

RECOMMENDATION:

That Application 2019-126-AL respecting property located at 12392 248 Street, be forwarded to the Agricultural Land Commission

DISCUSSION:

a) Background Context:

Applicant: Ronnie Bhala

Legal Description: Section: 23, Township: 12

OCP :
Existing: AGR (Agricultural)

Zoning:
Existing: RS-3 (One Family Rural Residential)

Surrounding Uses

North:	Use:	Vacant
	Zone:	RS-3 One Family Rural Residential
	Designation	Agricultural
South:	Use:	Rural Residential
	Zone:	RS-3 One Family Rural Residential
	Designation	Agricultural

East:	Use:	Rural Residential
	Zone:	RS-3 One Family Rural Residential
	Designation	Agricultural
West:	Use:	Rural Residential
	Zone:	RS-3 One Family Rural Residential & RS-1 One Family Urban Residential
	Designation	Agricultural
Existing Use of Property:		Vacant
Proposed Use of Property:		Rural residential
Site Area:		2.023 ha (5 acres)
Access:		248 th Street
Servicing:		Municipal water, septic

b) Project Description:

This application is for a principal dwelling with a total floor area of 650 square metres (6,996 square feet). Prior to making a building permit, the applicant was working on a development plan that met the regulations for the Farm Home Plate in Maple Ridge.

However, the building permit application was not made prior to the changed ALC regulations, which imposed greater restrictions on house size. For this reason, the applicant is seeking ALC approval to realize this development plan, which was underway prior to the changed regulations.

Generally, this proposal complies with the regulations of the Farm Home Plate. However, the size of the attached garage structures exceeds the maximum specified in the Zoning Bylaw. If the ALC approves this application, the applicant will have the option of revising the plan or seeking a variance prior to issuance of a building permit.

c) Planning Analysis:

Agricultural Land Commission: The provincial government introduced Bill 52 on Nov. 5, 2018 and the changes officially took effect on Feb. 22, 2019. A key change includes reducing the size of homes built on ALR land. Primary residences are now restricted to less than 500 square metres (5,400 square feet) under the new regulations. In addition, only one detached dwelling is permitted, although it can also have a secondary suite. Other residential uses that were previously permitted conditionally such as temporary residential uses, detached garden suites, or farm help housing now require approval through the ALC prior to issuance of a building permit.

With this change, the ALC has also placed further restrictions on the amount of fill that can be brought on site. For residential uses, the maximum area of landscape alteration is now 1000 m², (10,764 square feet) significantly less than the previous threshold of 2000 m² (21,528 square feet)

Zoning Bylaw:

All properties will be required to meet both municipal zoning regulations (farm home plate) and ALC regulations prior to issuance of a building permit. The table below compares the 2 sets of regulations.

Use	ALC Bill 52	Zoning Bylaw (Farm Home Plate)
Detached garden suite	Non adhering residential use application required	Permitted conditionally
Temporary Residential Use	Non adhering residential use application required	Conditional use, manufactured home, restrictive covenant required
Employee Residential Use	Non adhering residential use application required	279 m ² (3,003 square feet) maximum footprint, need farm status, restrictive covenant, Council resolution requiring ALC approval
Principal Dwelling	500 m ² (5,400 square feet) maximum, below ground basements and attached garages up to 42 m ² (452 square feet).	650 m ² (6,996 square feet), includes attached garages
Residential Footprint	Maximum landscape disturbance of 1000 m ² , (10,764 square feet) including foundations and driveways, located anywhere on the lot.	2000 m ² , (21,528 square feet) to be located within 60 m (197 feet) of fronting street

Development proposals would need to resolve conflicts with these regulations through a variance and / or through an application to the ALC, depending on the nature of the conflict.

This application is one of the first under these new regulations. In this case, it is clear that the applicant intended to develop the property in compliance with Zoning Bylaw regulations but did not complete the application process before ALC regulations changed. For this reason, this application is supportable.

d) Intergovernmental Issues:

The initiatives of the ALC and the City to limit residential development in the ALR have emerged out of a commitment to retain agricultural land for agricultural purposes. The municipal farm home plate regulations were completed earlier, and it may make sense in the future to amend the Zoning Bylaw to more closely align these two sets of regulations.

e) Citizen/Customer Implications:

The measures taken to limit residential development in the ALR are intended to assist the agricultural community by reducing the competition for agricultural land by those interested in estate residential development.

Those interested in estate residential development will continue to have options in properties that are designated Rural Residential and Estate Suburban.

Alternatives:

As with all applications, Council has the option to deny. The recommended approach is to forward the application. It is understood that the recent changes to ALC regulations may lead to more ALC applications in the near future to address conflicts faced by recent development proposals that previously complied with ALC regulations. It is not clear at this point if additional action at the municipal level is necessary, such as amending bylaws to more closely align with ALC regulations, but over time, greater clarity will occur.

CONCLUSION:

As the applicant intended to develop the property in compliance with the municipal and provincial regulations as they existed at the time, it is recommended that this application be forwarded to the ALC for their decision on this non-adhering residential application.

“Original signed by Diana Hall”

Prepared by: **Diana Hall, M.A, MCIP, RPP**
Planner

“Original signed by Chuck Goddard”

Reviewed by: **Charles R. Goddard, BA, MA**
Director of Planning

“Original signed by Chuck Goddard” for


Approved by: **Christine Carter, M.PL, MCIP, RPP**
GM Planning & Development Services

“Original signed by Kelly Swift”

Concurrence: **Kelly Swift, MBA**
Acting Chief Administrative Officer

The following appendices are attached hereto:

- Appendix A – Subject Map
- Appendix B – Ortho Photo
- Appendix C – Site Plan and house details provided by the applicant.



Scale: 1:3,000

Legend

-  Stream
-  Ditch Centreline

12392 248 STREET


PLANNING DEPARTMENT




mapleridge.ca

FILE: 2019-126-AL
DATE: Apr 8, 2019

BY: PC



Scale: 1:3,000



12392 248 STREET


PLANNING DEPARTMENT




mapleridge.ca

FILE: 2019-126-AL
DATE: Apr 8, 2019


BY: PC




FRONT ELEVATION



SIDE ELEVATION



REAR ELEVATION



BACK ELEVATION

SUBJECT PROPERTY
1892, 248 ST.

DIAGRAM TO SCALE

156' = 32'


PROPERTY 165' x 1312' = 214,560 SQ.FT.

MAIN FLOOR PLAN

- MAIN FLOOR = 4370 SQ.FT.
- 2 CAR ATTACHED GARAGE = 514.8 SQ.FT.
- FRONT COVERED PORCH =
- COVERED PORTICO =
- REAR COVERED DECKS =
- 2 CAR GARAGE = 570 SQ.FT.
- 4 CAR GARAGE = 1348 SQ.FT.
- TOTAL GARAGE AREA = 1918 SQ.FT.

MAIN FLOOR = 4370 SQ.FT.
UPPER FLOOR = 2622 SQ.FT.
TOTAL HOUSE = 6992.0 SQ.FT.

MAX. HOUSE SQ.FT. = 4006.54 SQ.FT. (450 SQ.M)



TO SCALE
SUBJECT HOUSE SITING ON
PROPERTY



mapleridge.ca

City of Maple Ridge

TO: His Worship Mayor Michael Morden
and Members of Council

FROM: Chief Administrative Officer

MEETING DATE: July 2, 2019

FILE NO: 2019-200-AL

MEETING: C o W

SUBJECT: Application for non-adhering residential uses in the Agricultural Land Reserve
13055 210 Street

EXECUTIVE SUMMARY:

This application is for residential development within the Agricultural Land Reserve (ALR). The applicant has been challenged due to changing regulations during the application process. The 2016 introduction of Farm Home Plate regulations in the Zoning Bylaw entailed that their development plan exceeded maximum requirements for house size and for the footprint that was to be devoted to residential uses.

To address these non-conformities, the applicant was granted Board of Variance Approval to proceed. However, as the building permit was being processed, the Agricultural Land Commission (ALC) introduced their new regulations for house size, a maximum of 500 square meters (5,400 square feet), which was considerably smaller than the maximum specified in the Zoning Bylaw.

For this reason, the applicant cannot proceed with this development proposal unless approved by the ALC. As this proposal complied with existing regulations when it was initiated, it is felt to be supportable.

RECOMMENDATION:

That Application 2019-200-AL, respecting property located at 13055 210 Street, be forwarded to the Agricultural Land Commission.

DISCUSSION:

a) Background Context:

Applicant:	Karamjeet S Gill
Legal Description:	Lot: 1, D.L.: 262, Section: 25, Township: 9, Plan: NWP3512
OCP:	
Existing:	AGR (Agricultural)
Zoning:	
Existing:	A-2 (Upland Agricultural)

Surrounding Uses

North:	Use:	Agriculture
	Zone:	A-2 Upland Agriculture
	Designation:	Agricultural
South:	Use:	Farm, Rural Residential
	Zone:	A-2 Upland Agriculture
	Designation:	Agricultural
East:	Use:	Farm, Rural Residential
	Zone:	A-2 Upland Agriculture
	Designation:	Agricultural
West:	Use:	Vacant
	Zone:	A-2 Upland Agriculture
	Designation:	Agricultural
Existing Use of Property:		Farm, Rural Residential
Proposed Use of Property:		Farm, Rural Residential
Site Area:		3.7 Ha (9.25 acres)
Access:		210 th Street
Servicing:		Municipal water, septic

b) Project Description:

This application is for a principal dwelling with a total floor area of 750 square metres (8,073 square feet). The development history of the site dates to 2016, with the applicant seeking to place a manufactured home on the property that could initially function as a principal dwelling, and then be considered a temporary residential use by a relative, once a larger house (principal dwelling) was built on the property.

The Maple Ridge Farm Home Plate regulations were adopted in late 2016, which rendered the site house plans non-conforming with respect to Zoning. A variance was granted to waive the conflicts with the Farm Home Plate regulations at the August 2, 2017 Board of Variance meeting.

The Building Permit was not issued prior to the changed ALC regulations, which imposed greater restrictions on house size. For this reason, the applicant is seeking ALC approval to realize this development plan, which has been in progress since 2016.

c) Planning Analysis:

Agricultural Land Commission: The provincial government introduced Bill 52 on Nov. 5, 2018 and the changes officially took effect on Feb. 22, 2019. A key change includes reducing the size of homes built on ALR land. Primary residences are now restricted to less than 500 square metres (5,400 square feet) under the new regulations. In addition, only one detached dwelling is permitted, although it can also have a secondary suite. Other residential uses that were previously permitted conditionally such as temporary residential uses, detached garden suites, or farm help housing now require approval through the ALC prior to issuance of a building permit.

With this change, the ALC has also placed further restrictions on the amount of fill that can be brought on site. For residential uses, the maximum area of landscape alteration is now 1000 m², (10,764 square feet) significantly less than the previous threshold of 2000 m² (21,528 square feet).

Zoning Bylaw:

All properties will be required to meet both municipal zoning regulations (farm home plate) and ALC regulations prior to issuance of a building permit. The table below compares the 2 sets of regulations.

Use	ALC Bill 52	Zoning Bylaw (Farm Home Plate)
Detached garden suite	Non adhering residential use application required	Permitted
Temporary Residential Use	Non adhering residential use application required	Conditional use, manufactured home, restrictive covenant required
Employee Residential Use	Non adhering residential use application required	279 m ² (3,003 square feet) maximum footprint, need farm status, restrictive covenant, Council resolution requiring ALC approval
Principal Dwelling	500 m ² (5,400 square feet) maximum, below ground basements and attached garages up to 42 m ² (452 square feet).	650 m ² (6,996 square feet), includes attached garages
Residential Footprint	Maximum landscape disturbance of 1000 m ² , (10,764 square feet) including foundations and driveways, located anywhere on the lot.	2000 m ² , (21,528 square feet) to be located within 60 m (197 feet) of fronting street

Development proposals would need to resolve conflicts with these regulations through a variance and / or through an application to the ALC, depending on the nature of the conflict.

This application is one of the first under these new regulations. In this case, it is clear that the applicant intended to develop the property in compliance with Zoning Bylaw regulations but did not complete the application process before ALC regulations changed. For this reason, this application is supportable.

d) Intergovernmental Issues:

The initiatives of the ALC and the City to limit residential development in the ALR have emerged out of a commitment to retain agricultural land for agricultural purposes. The municipal farm home plate regulations were completed earlier, and it may make sense in the future to amend the Zoning Bylaw to more closely align these two sets of regulations.

e) Citizen/Customer Implications:

The measures taken to limit residential development in the ALR are intended to assist the agricultural community by reducing the competition for agricultural land by those interested in estate residential development.

Those interested in larger estates will continue to have options in properties that are designated Rural Residential and Estate Suburban.

Alternatives:

As with all applications, Council has the option to deny. The recommended approach is to forward the application. It is understood that the recent changes to ALC regulations may lead to more ALC applications in the near future to address conflicts faced by recent development proposals that previously complied with ALC regulations. It is not clear at this point if additional action at the municipal level is necessary, such as amending bylaws to more closely align with ALC regulations, but over time, greater clarity will occur.

CONCLUSION:

As the applicant intended to develop the property in compliance with the municipal and provincial regulations as they existed at the time, it is recommended that this application be forwarded to the ALC for their decision on this non-adhering residential application.

“Original signed by Diana Hall”

Prepared by: **Diana Hall, M.A, MCIP, RPP
Planner**

“Original signed by Chuck Goddard”

Reviewed by: **Charles R. Goddard, BA, MA
Director of Planning**

“Original signed by Chuck Goddard” for

Approved by: **Christine Carter, M.PL, MCIP, RPP
GM Planning & Development Services**


“Original signed by Kelly Swift”

Concurrence: **Kelly Swift, MBA
Acting Chief Administrative Officer**

The following appendices are attached hereto:

- Appendix A – Subject Map
- Appendix B – Ortho Photo
- Appendix C – Site Plan and house details provided by the applicant.

APPENDIX A



Scale: 1:4,000

Legend

-  Canal Edge
-  Ditch Centreline
-  Edge of River
-  Edge of Marsh
-  Canal
-  Lake or Reservoir
-  Marsh
-  River

13055 210 St

PLANNING DEPARTMENT



MAPLE RIDGE
British Columbia

mapleridge.ca

FILE: 2019-200-AL
DATE: Jun 3, 2019


BY: MC



Aerial Imagery from the Spring of 2018



Scale: 1:4,000



13055 210 St


PLANNING DEPARTMENT



mapleridge.ca

FILE: 2019-200-AL
DATE: Jun 3, 2019

BY: MC



<p>APPROVED PLAN: 13055 210th ST, MAPLE RIDGE, BC V4R-2R9</p>		<p>DATE:</p>		<p>ON-SITE WASTEWATER DISPERSAL SYSTEM</p>	
<p>PROJECT: 13055 210th ST, MAPLE RIDGE, BC V4R-2R9</p>		<p>DATE OF PLAN: AUGUST 21, 2008</p>		<p>PROJECT NUMBER: SA</p>	
<p>CLIENT: ATYON WALSH CORP INC.</p>		<p>PROJECT NAME: ATYON WALSH</p>		<p>SECTION: SA</p>	
<p>4100 YARBROOK CENTRAL RD. VANCOUVER, BC V2B 5G1 TEL: 604-261-7001 www.atyongroup.com</p>		<p>PROJECT: ATYON WALSH</p>		<p>SECTION: SA</p>	
<p>DESIGNER: KARAMELIT & MANPREET GILL</p>		<p>DATE OF PLAN: AUGUST 21, 2008</p>		<p>PROJECT NUMBER: SA</p>	
<p>SCALE: 1/8" = 1'-0"</p>		<p>DATE OF PLAN: AUGUST 21, 2008</p>		<p>PROJECT NUMBER: SA</p>	
<p>SCALE: 1/8" = 1'-0"</p>		<p>DATE OF PLAN: AUGUST 21, 2008</p>		<p>PROJECT NUMBER: SA</p>	



mapleridge.ca

City of Maple Ridge

TO: His Worship Mayor Michael Morden
and Members of Council

FROM: Chief Administrative Officer

SUBJECT: First Reading
Zone Amending Bylaw No. 7563-2019
11907 223 Street

MEETING DATE: July 2, 2019
FILE NO: 2018-464-RZ
MEETING: C o W

EXECUTIVE SUMMARY:

An application has been received to rezone the subject property, located at 11907 223 Street, from RM-3 (High Density Apartment Residential District) to RM-2 (Medium Density Apartment Residential District) to permit the future construction of a six-storey residential apartment with approximately 51 units. The applicant is proposing an increase in base density from 1.8 floor space ratio (FSR) to 2.36 FSR; therefore, a site specific text amendment, using a density bonus, will be required to the RM-2 (Medium Density Apartment Residential District) zone. In accordance with Council's draft density bonus regulations, the proposed additional density can be achieved through a cash contribution, currently determined at \$96.88 per m² (\$9.00 per ft²). To proceed further with this application additional information is required, as outlined below.

As per Council Policy 6.31, which was updated December 12, 2017 to remove the Community Amenity Contribution (CAC) Program exemption for properties situated within the Town Centre Area Plan boundaries, a CAC charge of approximately \$158,100.00 applies to this proposed development (\$3,100 per unit for apartment dwellings).

RECOMMENDATIONS:

1. In respect of Section 475 of the *Local Government Act*, requirement for consultation during the development or amendment of an Official Community Plan (OCP), Council must consider whether consultation is required with specifically:
 - i. The Board of the Regional District in which the area covered by the plan is located, in the case of a Municipal Official Community Plan;
 - ii. The Board of any Regional District that is adjacent to the area covered by the plan;
 - iii. The Council of any municipality that is adjacent to the area covered by the plan;
 - iv. First Nations;
 - v. Boards of Education, Greater Boards and Improvements District Boards; and
 - vi. The Provincial and Federal Governments and their agencies.

and in that regard it is recommended that no additional consultation be required in respect of this matter beyond the early posting of the proposed Official Community Plan amendments on the City's website, together with an invitation to the public to comment, and;

2. That Zone Amending Bylaw No. 7563-2019 be given first reading; and

1104

3. That the applicant provide further information as described on Schedules A, C, D and E of the *Development Procedures Bylaw No. 5879-1999*.

DISCUSSION:

a) Background Context:

Applicant: Bissky Architecture and Urban Design Inc.

Legal Description: Lot 4 District Lot 398 Group 1 New Westminster District Plan 8380

OCP:
Existing: Low-Rise Apartment
Proposed: Low-Rise Apartment

Zoning:
Existing: RM-3 (High Density Apartment Residential District)
Proposed: RM-2 (Medium Density Apartment Residential District)

Surrounding Uses:

North:	Use:	Apartment
	Zone:	RM-3 (High Density Apartment Residential District)
	Designation:	Low-Rise Apartment
South:	Use:	Single Family Residential
	Zone:	RM-3 (High Density Apartment Residential District)
	Designation:	Low-Rise Apartment
East:	Use:	Commercial
	Zone:	C-3 (Town Centre Commercial)
	Designation:	Flexible Mixed-Use
West:	Use:	Apartment
	Zone:	RM-3 (High Density Apartment Residential District)
	Designation:	Low-Rise Apartment

Existing Use of Property: Vacant
Proposed Use of Property: Multi-Family Apartment
Site Area: 0.18 ha (0.43 acres)
Access: Lane north of 119 Avenue
Servicing requirement: Urban Standard

b) Site Characteristics:

The subject property, located at 11907 223 Street, is located at the southwest corner of 223 Street and 119 Avenue. The property is flat with trees located around the perimeter, along with grasses and low lying shrubs located throughout. Japanese Knotweed, an invasive species, has also been identified on the subject property and will require removal as part of development. The subject property is currently vacant (see Appendices A and B).

c) Project Description:

The current application proposes to rezone the subject property from RM-3 (High Density Apartment Residential District) to RM-2 (Medium Density Apartment Residential District) to permit the

construction of a six-storey building consisting of 51 apartment units and 60 concealed parking spaces. A portion of the second storey over the parking level below will be a rooftop amenity space. Access to the parking will be from the lane along the northern edge of the site.

The property has historical RM-3 (High Density Apartment Residential District) zoning that is intended for dense high-rise buildings. This density is based on building height for each storey built above the fifth storey, to achieve the permitted density in the RM-3 (High Density Apartment Residential District) zone (e.g. FSR = 1.2 plus 0.2 for each storey 6 to 10). Instead, the applicant is seeking to rezone and apply the RM-2 (Medium Density Apartment Residential District) zone requirements with an FSR of 2.36 within a six-storey structure. This will require a site specific text amendment, using a density bonus, for an increase of 0.56 FSR over the maximum permitted FSR of 1.8 (for the RM-2 zone). A further variance in the maximum building height, from four to six storeys, is also required to accommodate this project.

The proposed RM-2 (Medium Density Apartment Residential District) zone is consistent with the *Low-Rise Apartment* designation within Town Centre Area Plan in the Official Community Plan (OCP), thus rezoning to RM-2 (Medium Density Apartment Residential District) would bring the property into compliance with the policies of OCP and the Town Centre Area Plan.

At this time, the current application has been assessed to determine its compliance with the OCP and provide a land use assessment only. Detailed review and comments will need to be made once full application packages have been received. A more detailed analysis and a further report will be required prior to second reading. Such assessment may impact proposed lot boundaries and yields, OCP designations and Bylaw particulars, and may require application for further development permits.

d) Planning Analysis:

Official Community Plan:

The subject property is located within the Downtown West Precinct of the Town Centre Area Plan. As outlined in the Development Permit Area Guidelines of the OCP, this precinct *“is an important central downtown neighbourhood, and could grow to accommodate boutique retail, arts and culture centres, and tourism related services such as hotels and small scale conference centres, in addition to multi-family residential development.”*

The subject property is designated *Low-Rise Apartment*, and as stated in Policy 3-22: *“is intended for development in a three (3) to five (5) storey apartment form where units are accessed from an internal corridor and residential parking is provided underground.”* An OCP amendment is required to accommodate the proposed six-storey structure.

The following policies apply to this proposal:

3-1 An increase in residential and commercial density is encouraged in the Town Centre [...] Land-use should include a mix of housing types catering to various demographics, including affordable and special needs housing, within walking distance to a broad mixture of uses, including shops, services, cultural facilities, and recreation.

This project increases the residential density by introducing up to 51 units, including 11 one-bedroom units, 34 two-bedroom units, and 6 three-bedroom units. The subject property is located within walking distance to a range of shops, services, parks and the Haney Place Transit Exchange.

3-12 High density development that is four or more storeys in height may be required to include a shadow study in consideration of adjacent sites to address potential impacts on available daylight.

This project will potentially have shadow impacts on the adjacent properties to the north and east of the site. The applicant will be asked to provide a shadow study.

In addition to these policies, a range of environmentally sustainable policies in the Town Centre Area Plan would also apply to this application:

2-5 Incorporating Rainwater Management practices into on-site and off-site development will be encouraged [...]. Some examples of Rainwater Management practices include:

- *bioretention areas;*
- *rainwater gardens;*
- *bioswales;*
- *landscaped curb bulges on street right-of-ways;*
- *rainwater harvest for irrigation; and*
- *green roofs.*

2-9 The use of plant and tree species that are suited for Maple Ridge climate and that will attract local songbirds and pollinating insects species [...] will be encouraged in public and private development;

2-10 Landscaping, as described in policy 2-9 above, will be encouraged in all public and private outdoor spaces in the Town Centre. For areas with a large amount of paved surfaces, such as surface parking lots and public plazas, the installation of trees, rain gardens, raised planters, and/or living green walls, where feasible, is encouraged to provide some areas of refuge for wildlife, such as small birds, rainwater interception, cooling in summer months, reduced glare from pavement, carbon sequestration, and a more attractive urban environment.

The applicant will be required to provide some of these measures as part of the development.

Housing Action Plan:

The City's Housing Action Plan (HAP) was endorsed by Council in 2014. It seeks to increase access to "safe, affordable, and appropriate housing that meets the diverse and changing needs of the community". The HAP also speaks of the need to provide a range of non-market, affordable and special needs housing. This was reaffirmed with the endorsement of the Housing Action Plan Implementation Framework in September, 2015. The subject application does provide a mix of unit size, including one, two, and three bedroom units. Further details on unit type (accessible units, special needs housing, etc.) will be included in the second reading report.

Citywide Community Amenity Program:

The City-wide Community Amenity Contribution (CAC) Program, approved by Council on March 14, 2016 and amended on December 14, 2017, applies to this project. A voluntary contribution of \$3,100 per apartment unit, totalling \$158,100.00, is required for this project before final reading.

Zoning Bylaw:

The current application proposes to rezone the subject property from RM-3 (High Density Apartment Residential District) to RM-2 (Medium Density Apartment Residential District) (see Appenix C) to permit

the construction of a six-storey apartment building with approximately 51 units (see Appendices D and E). A site specific text amendment, using a density bonus, is required to increase the maximum allowable density within the RM-2 (Medium Density Apartment Residential District) zone from 1.8 to 2.36 FSR. Based on Council's draft density bonus regulations, additional density can be achieved in exchange for a cash contribution, currently determined at \$96.88 per m² (\$9.00 per ft²). Recent discussions with Council have also noted that there is a preference for cash-in-lieu rather than the direct provision of rental units. Any density bonus contributions received are intended to help fund the creation of future affordable housing in the community. Further details of the density bonus contribution for this application will form part of the second reading report to Council.

Reductions to all setbacks and an increase in height are also being requested and will be evaluated in the context of the Downtown West Precinct Development Permit Guidelines. Any variations from the requirements of the proposed zone will require a Development Variance Permit application, and will be subject of a future report to Council.

Development Permits:

Pursuant to Section 8.11 of the OCP, a Town Centre Development Permit (Downtown West Precinct) application is required for all multi-family residential, flexible mixed use and commercial development located in the Town Centre.

Advisory Design Panel:

A Development Permit is required and the development must be reviewed by the Advisory Design Panel prior to second reading.

Development Information Meeting:

A Development Information Meeting is required for this application. Prior to second reading the applicant is required to host a Development Information Meeting in accordance with Council Policy 6.20.

e) Interdepartmental Implications:

In order to advance the current application, after first reading, comments and input, will be sought from the various internal departments and external agencies listed below:

- a) Engineering Department;
- b) Fire Department;
- c) Building Department;
- d) Parks Department;
- e) School District;
- f) Ministry of Transportation and Infrastructure; and
- g) Canada Post.

The above list is intended to be indicative only and it may become necessary, as the application progresses, to liaise with agencies and/or departments not listed above.

This application has not been forwarded to the Engineering Department for comments at this time; therefore, an evaluation of servicing requirements has not been undertaken. We anticipate that this evaluation will take place between first and second reading.

f) Early and Ongoing Consultation:

In respect of Section 475 of the *Local Government Act* for consultation during an OCP amendment, it is recommended that no additional consultation is required beyond the early posting of the proposed OCP amendments on the City's website, together with an invitation to the public to comment.

g) Development Applications:

In order for this application to proceed the following information must be provided, as required by *Development Procedures Bylaw No. 5879-1999* as amended:

1. An OCP Amendment Application (Schedule A);
2. A complete Rezoning Application (Schedule C);
3. A Town Centre Development Permit Application (Schedule D); and
4. A Development Variance Permit Application (Schedule E).

The above list is intended to be indicative only, other applications may be necessary as the assessment of the proposal progresses.

CONCLUSION:

The development proposal is in compliance with the policies of the OCP, with the exception of the proposed height. Justification has been provided to support an OCP amendment to increase the height within the *Low-Rise Apartment* designation to 6 storeys. A site specific text amendment, using a density bonus, is required to increase the base density from 1.8 to 2.36 FSR. It is, therefore, recommended that Council grant first reading subject to additional information being provided and assessed prior to second reading.

"Original signed by Adam Rieu"

Prepared by: Adam Rieu
Senior Planning Technician

"Original signed by Chuck Goddard"

Reviewed by: Charles R. Goddard, BA, MA
Director of Planning

"Original signed by David Pollock" _____ for _____


Approved by: Christine Carter, M.PL, MCIP, RPP
GM Planning & Development Services

"Original signed by Kelly Swift"


Concurrence: Kelly Swift, MBA
Acting Chief Administrative Officer

The following appendices are attached hereto:

- Appendix A – Subject Map
- Appendix B – Ortho Map
- Appendix C – Zone Amending Bylaw No. 7563-2019
- Appendix D – Proposed Site Plan
- Appendix E – Site Rendering



Scale: 1:2,000



11907 223 St


PLANNING DEPARTMENT



mapleridge.ca

FILE: 2018-464-RZ
DATE: Nov 8, 2018

BY: LP



MAPLE RIDGE ZONE AMENDING

Bylaw No. 7563-2019
 Map No. 1803
 From: RM-3 (High Density Apartment Residential District)
 To: RM-2 (Medium Density Apartment Residential District)





① View to South East



② View Along 223rd St.
Scale: 1/8" = 1'-0"

Renderings

Sheet
A0.1

WAYNE STEPHEN BISSKY
ARCHITECTURE & URBAN DESIGN INC.
PLANNING INTERIOR DESIGN
1104 N. 22nd St.
Suite 201
Phoenix, AZ 85016
Phone: 602.955.1111
www.wsbstudio.com

Client Address: 11907-223 Street, Mesa, Arizona, AZ
Legal Address: LT CL 306, NMD, PL HWP3360
P.P. #: 015-306-031

Project Name: RM-2 Multi-Family Dev't
Project Location: 11907-223 Street, Mesa, Arizona, AZ
Project Status: Approved
Project Date: 11/15/2018
Project Owner: [Redacted]
Project Architect: Wayne Stephen Bissky
Project Designer: [Redacted]
Project Engineer: [Redacted]
Project Surveyor: [Redacted]
Project Planner: [Redacted]
Project Interior Designer: [Redacted]

REBUILT DRAWINGS
Sheet No. 015-306-031-100



mapleridge.ca

City of Maple Ridge

TO: His Worship Mayor Michael Morden
and Members of Council

FROM: Chief Administrative Officer

SUBJECT: **First Reading**
Zone Amending Bylaw No. 7559-2019
22090 Cliff Avenue

MEETING DATE: July 2, 2019
FILE NO: 2019-090-RZ
MEETING: C o W

EXECUTIVE SUMMARY:

An application has been received to rezone the subject property, located at 22090 Cliff Avenue, from RS-1 (One Family Urban Residential) to RS-1b (One Family Urban (medium density) Residential), to future subdivide the property into 2 lots. To proceed further with this application additional information is required as outlined below.

Pursuant to Council policy, this application is subject to the Community Amenity Contribution Program, where a voluntary contribution will be requested. For single family residential subdivisions proposing fewer than 3 lots, only the original is exempt, after which the CAC program applies to additional lots.

RECOMMENDATIONS:

That Zone Amending Bylaw No. 7559-2019 be given first reading; and

That the applicant provide further information as described on Schedules B, E and G of the Development Procedures Bylaw No. 5879-1999, along with the information required for a Subdivision application.

DISCUSSION:

a) Background Context:

Applicant:	True Light Building & Development Ltd
Owner:	True Light Building & Development Ltd
Legal Description:	Lot 46 except part subdivided by plan 37074, District Lot 397, Group 1, New Westminster District Plan 9218
OCP:	
Existing:	RES (Urban Residential)
Proposed:	RES (Urban Residential)
Zoning:	
Existing:	RS-1 (One Family Urban Residential)
Proposed:	RS-1b (One Family Urban (medium density) Residential)

Surrounding Uses:

North:	Use:	Residential
	Zone:	RS-1 (One Family Urban Residential)
	Designation:	Urban Residential
South:	Use:	Park
	Zone:	RS-1b (One Family Urban (medium density) Residential)
	Designation:	Conservation and Park
East:	Use:	Residential
	Zone:	RS-1 (One Family Urban Residential)
	Designation:	Urban Residential
West:	Use:	Residential
	Zone:	RS-1 (One Family Urban Residential)
	Designation:	Urban Residential

Existing Use of Property:	Residential
Proposed Use of Property:	Residential
Site Area:	0.13 HA. (0.32 acres)
Access:	Cliff Avenue
Servicing requirement:	Urban Standard

b) Site Characteristics:

The subject property, located at 22090 Cliff Avenue, is approximately 0.13 hectare (0.32 acres) in area, and is mostly flat around the existing residence, with a significantly sloped area of about 23 meters in the backyard, connected to a larger ridge. The subject property is bounded by residential properties to the north, east and west, Cliff Avenue to the north, and a park to the south. The property is located within the Fraser River Escarpment Area plan.

c) Project Description:

The current application proposes to rezone the subject property from RS-1 (One Family Urban Residential) to RS-1b (One Family Urban (medium density) Residential), to permit future subdivision into two single family lots, not less than 609m² with access off of Cliff Avenue. The existing structures will be required to be demolished prior to final reading.

At this time the current application has been assessed to determine its compliance with the Official Community Plan (OCP) and provide a land use assessment only. Detailed review and comments will need to be made once full application packages have been received. A more detailed analysis and a further report will be required prior to Second Reading. Such assessment may impact proposed lot boundaries and yields, OCP designations and Bylaw particulars, and may require application for further development permits.

d) Planning Analysis:

Official Community Plan:

The development site is located in west Maple Ridge, just outside of the Town Centre Area Plan and is currently designated *Urban Residential*. For the proposed development no OCP amendment will be required to allow the proposed RS-1b (One Family Urban (medium density) Residential) zoning.

On December 12, 2017 Council amended the City-wide Community Amenity Contribution (CAC) Program policy, which permits amenity contributions for residential development throughout Maple ridge, including the provision of affordable and special needs housing in a financially sustainable manner. Each CAC will be based on a contribution rate of \$5,100 per single family lot created. For single family residential subdivisions proposing fewer than 3 lots, only the original is exempt, after which the CAC program applies to additional lots. A voluntary contribution is anticipated to be requested for the amount of \$5,100.00.

Zoning Bylaw:

The current application proposes to rezone the property located at 22090 Cliff Avenue from RS-1 (One Family Urban Residential) to RS-1b (One Family Urban (medium density) Residential) to permit future subdivision in to two lots. The minimum lot size for the proposed zone is 557m², and the proposed lots are approximately 609 and 722m² in area.

The Zoning Bylaw requires that no lot shall be created by subdivision without specified building envelopes. For the proposed RS-1b (One Family Urban (medium density) Residential) zone, a building area should have dimensions of no less than 12.0 by 12.0 metres. The subject property's shape does not allow for such building areas, therefore a Development Variance Permit requirement is anticipated. Any variations from the requirements of the proposed zone will require a Development Variance Permit application.

Development Permits:

Pursuant to Section 8.10 of the OCP, a Natural Features Development Permit application is required for all development and subdivision activity or building permits for:

- All areas designated Conservation on Schedule “B” or all areas within 50 metres of an area designated Conservation on Schedule “B”, or on Figures 2, 3 and 4 in the Silver Valley Area Plan;
- All lands with an average natural slope of greater than 15 %;
- All floodplain areas and forest lands identified on Natural Features Schedule “C”

to ensure the preservation, protection, restoration and enhancement of the natural environment and for development that is protected from hazardous conditions.

Advisory Design Panel:

No review by the Advisory Design Panel is required prior to second reading.

Development Information Meeting:

In accordance with Council Policy 6.20 a Development Information Meeting is not required for this application.

e) Interdepartmental Implications:

In order to advance the current application, after first reading, comments and input, will be sought from the various internal departments and external agencies listed below:

- a) Engineering Department;
- b) Operations Department;
- c) Fire Department;
- d) Building Department;
- e) Parks Department;
- f) School District;
- g) Utility companies;
- h) Ministry of Transportation and Infrastructure; and
- i) Canada Post.

The above list is intended to be indicative only and it may become necessary, as the application progresses, to liaise with agencies and/or departments not listed above.

This application has not been forwarded to the Engineering Department for comments at this time; therefore, an evaluation of servicing requirements has not been undertaken. We anticipate that this evaluation will take place between first and second reading.

f) Development Applications:

In order for this application to proceed the following information must be provided, as required by Development Procedures Bylaw No. 5879-1999 as amended:

- 1. A complete Rezoning Application (Schedule B);
- 2. A Development Variance Permit (Schedule E);
- 3. A Natural Features Development Permit Application (Schedule G); and
- 4. A Subdivision Application.

The above list is intended to be indicative only, other applications may be necessary as the assessment of the proposal progresses.

CONCLUSION:

The development proposal is in compliance with the OCP, therefore, it is recommended that Council grant first reading subject to additional information being provided and assessed prior to second reading.

It is recommended that Council not require any further additional OCP consultation.

The proposed layout has not been reviewed in relation to the relevant bylaws and regulations governing subdivision applications. Any subdivision layout provided is strictly preliminary and must be approved by the City of Maple Ridge's Approving Officer.

"Original signed by Therese Melser"

Prepared by: **Therese Melser**
Planning Technician

"Original signed by Chuck Goddard"

Reviewed by: **Charles R. Goddard, BA, MA**
Director of Planning

"Original signed by Chuck Goddard" for


Approved by: **Christine Carter, M.PL, MCIP, RPP**
GM Planning & Development Services

"Original signed by Kelly Swift"

Concurrence: **Kelly Swift, MBA**
Acting Chief Administrative Officer

The following appendices are attached hereto:

- Appendix A – Subject Map
- Appendix B – Ortho Map
- Appendix C – Zone Amending Bylaw No. 7559-2019
- Appendix D – Proposed Site Plan



2017-230-VP
2017-230-RZ

2018-180-RZ

SUBJECT PROPERTY

2018-118-VP
2018-118-DP



Scale: 1:2,500

Legend

-  Stream
-  Ditch Centreline
-  Indefinite Creek
-  Active Applications (RZ/SD/DP/VP)

22090 CLIFF AVENUE
PID: 011-428-953


PLANNING DEPARTMENT



mapleridge.ca

FILE: 2019-090-RZ
DATE: Mar 15, 2019


BY: PC



Aerial imagery from the Spring of 2018



Scale: 1:2,500



District of Mission

22090 CLIFF AVENUE
PID: 011-428-953

PLANNING DEPARTMENT



MAPLE RIDGE

British Columbia

mapleridge.ca

FILE: 2019-090-RZ
DATE: Mar 15, 2019

BY: PC

City of Maple Ridge

TO: His Worship Mayor Michael Morden
and Members of Council
FROM: Chief Administrative Officer
SUBJECT: First Reading
Zone Amending Bylaw No. 7558-2019
12791 232 Street

MEETING DATE: July 2, 2019
FILE NO: 2019-119-RZ
MEETING: C o W

EXECUTIVE SUMMARY:

An application has been received to rezone the subject property from RS-2 (One Family Suburban Residential) to CS-1 (Service Commercial).

The subject property was excluded from the Agricultural Land Reserve (ALR) in 2018, but it is still designated *Agricultural* and is outside of Maple Ridge's Urban Containment Boundary and Metro Vancouver's Urban Containment Boundary. An application is required to Metro Vancouver to include the property within the Metro Vancouver Urban Containment Boundary and to be included in the Fraser Sewerage Area. The property is within the Yennadon Study Area which has been identified in the Commercial and Industrial Strategy as future potential employment lands. Council recently endorsed proceeding with a Land Use Re-Designation study and consultation process.

This is a commercial development, therefore the Community Amenity Contribution Program does not apply. To proceed further with this application additional information is required as outlined below.

RECOMMENDATIONS:

1. In respect of Section 475 of the *Local Government Act*, requirement for consultation during the development or amendment of an Official Community Plan, Council must consider whether consultation is required with specifically:
 - i. The Board of the Regional District in which the area covered by the plan is located, in the case of a Municipal Official Community Plan;
 - ii. The Board of any Regional District that is adjacent to the area covered by the plan;
 - iii. The Council of any municipality that is adjacent to the area covered by the plan;
 - iv. First Nations;
 - v. Boards of Education, Greater Boards and Improvements District Boards; and
 - vi. The Provincial and Federal Governments and their agencies.

and in that regard it is recommended that no additional consultation be required in respect of this matter beyond the early posting of the proposed Official Community Plan amendments on the City's website, together with an invitation to the public to comment, and;

2. That Zone Amending Bylaw No. 7558-2019 be given first reading; and
3. That the applicant provide further information as described on Schedules A, C, and D of the Development Procedures Bylaw No. 5879-1999.

DISCUSSION:

a) Background Context:

Applicant: K. Atwall

Legal Description: Lot 44, Section 20, Township 12, New Westminster District Plan 30199

OCP:
Existing: Agricultural
Proposed: Commercial

Zoning:
Existing: RS-2 (One Family Suburban Residential)
Proposed: CS-1 (Service Commercial)

Surrounding Uses:

North:	Use:	Single Family Residential
	Zone:	RS-2 (One Family Suburban Residential)
	Designation:	Estate Suburban Residential
South:	Use:	Single Family Residential
	Zone:	RS-2 (One Family Suburban Residential) and RS-3 (One Family Rural Residential)
	Designation:	Agricultural
East:	Use:	Single Family Residential
	Zone:	RS-2 (One Family Suburban Residential)
	Designation:	Agricultural
West:	Use:	Single Family Residential and Farm
	Zone:	RS-2 (One Family Suburban Residential) and RS-3 (One Family Rural Residential)
	Designation:	Agricultural

Existing Use of Property: Vacant
Proposed Use of Property: Commercial
Site Area: 0.4 ha (1 acre)
Access: 128 Avenue
Servicing requirement: Urban Standard

b) Project Description:

The subject property, located at 12791 232 Street, is located at the south-west corner of 232 Street and 128 Avenue. The property is flat and vacant, with several trees located along the western and southern property lines (see Appendices A and B).

The applicant is proposing to rezone the property from RS-2 (One Family Suburban Residential) to CS-1 (Service Commercial) (see Appendix C) to allow for a 2,090m² (22,500ft²) two-storey commercial development (see Appendix D).

At this time the current application has been assessed to determine its compliance with the Official Community Plan (OCP) and provide a land use assessment only. Detailed review and comments will

need to be made once full application packages have been received. A more detailed analysis and further reports will be required prior to second reading. Such assessment may impact proposed lot boundaries and yields, OCP designations and Bylaw particulars, and may require application for further development permits.

c) **Planning Analysis:**

Official Community Plan:

The subject property is designated *Agricultural* and is outside of the Urban Area Boundary. The subject property was excluded from the Agricultural Land Reserve (ALR) in 2018, as it was less than 2 acres in size and considered too small to support an agricultural operation on its own, and exclusion would not negatively impact the agricultural viability of the adjacent ALR property to the west. For the proposed development, an OCP amendment will be required to re-designate the property to *Commercial* to allow the proposed CS-1 (Service Commercial) zoning.

This property is one of 13 properties at the south-west corner of 128 Avenue and 232 Street referred to as the Yennadon Lands, a 25.4 ha (63 acre) site identified in the Commercial and Industrial Strategy for future employment land uses.

The City's Commercial and Industrial Strategy identifies the need for an additional 63 – 93 ha (170 – 230 acres) of industrial lands by 2040 to meet long-term employment demand. The Yennadon Lands are one of several sites that Council has directed additional review on to explore employment land opportunities. Albion Flats is another concurrent site identified for employment uses. Additionally, in 2017, new industrial land was created at 256 Street and 130 Avenue, east of the Albion Industrial Area, and on either side of the Kwantlen IR #5 lands along Lougheed Highway.

Through the implementation of the Commercial and Industrial Strategy, Council received a report on April 16, 2019 outlining a public consultation process for the re-designation of the Yennadon Lands for employment uses. Council passed the following resolution:

That the April 16, 2019 Council Workshop report titled "Employment Land Use Suitability Assessment: Yennadon Lands" be referred back to staff for further work".

Accordingly, staff met with the Yennadon Lands property owners on June 6, 2019 and summarized the meeting outcomes for Council at a Workshop meeting held on June 18, 2019. Eleven of the 13 properties were represented at this meeting. They discussed trends in the employment sector and how the traditional business parks are evolving to innovation districts including educational, cultural and recreational facilities. The property owners had questions around the timing, process and criteria for future land use decisions, and what the alternative to an area study would look like. There was general support to pursue an area planning process, as the property owners are hoping to gain clarity on their future land use. At this Workshop meeting, Council passed the following resolutions:

That staff be directed to undertake an employment land use re-designation process and consultation strategy for the Yennadon Lands, located generally at 128th Avenue and 232nd Street;

That new applications, or those already in-stream (unless reached third reading), be deferred until any potential OCP amendments are presented at Public Hearing and given third reading, with the exception of applications that propose future employment land uses;

The proposed CS-1 (Service Commercial) zone permits a range of commercial uses, as well as employment uses such as light industrial and research and non-medical testing laboratories. As a result, consideration of first reading is recommended to reflect Council's June 18, 2019 resolution regarding in-stream applications.

Regional Growth Strategy:

In addition to the OCP amendment, Metro Vancouver's Regional Growth Strategy (RGS) manages growth by establishing urban containment boundaries throughout the region. The subject property is located outside of the Region's Urban Containment Boundary, and partially inside the Region's Fraser Sewerage Area, which delineates properties that are able to connect to the regional sanitary system. A resolution is required by Council to forward an application by the City to Metro Vancouver to include the property within the Region's Urban Containment Boundary and include it within the Fraser Sewerage Area. This will be the subject of a future report to Council from the Engineering Department.

Zoning Bylaw:

The current application proposes to rezone the subject property from RS-2 (One Family Suburban Residential) to CS-1 (Service Commercial) to permit a two-storey commercial development.

Under the Subdivision and Development Servicing Bylaw, properties zoned CS-1 (Service Commercial) outside of the Urban Area Boundary may be exempted from the requirement to connect to municipal sanitary services. Should the applicant receive Metro Vancouver approvals for inclusion in the regional Urban Containment Boundary and the Fraser Sewerage Area prior to second reading, a more appropriate urban commercial zone could be explored. Any variations from the requirements of the proposed zone will require a Development Variance Permit application.

Development Permits:

Pursuant to Section 8.5 of the OCP, a Commercial Development Permit application is required to address the current proposal's compatibility with adjacent development, and to enhance the unique character of the community.

Advisory Design Panel:

A Commercial Development Permit is required and must be reviewed by the Advisory Design Panel prior to second reading.

Development Information Meeting:

A Development Information Meeting is required for this application. Prior to second reading the applicant is required to host a Development Information Meeting in accordance with Council Policy 6.20.

d) Interdepartmental Implications:

In order to advance the current application, after first reading, comments and input will be sought from the various internal departments and external agencies listed below:

- a) Engineering Department;
- b) Operations Department;
- c) Fire Department;
- d) Building Department;
- e) Parks Department;
- f) School District;
- g) Utility companies;
- h) Agricultural Land Commission; and
- i) Canada Post.

The above list is intended to be indicative only and it may become necessary, as the application progresses, to liaise with agencies and/or departments not listed above.

This application has not been forwarded to the Engineering Department for comments at this time; therefore, an evaluation of servicing and site access requirements have not been undertaken. We anticipate that this evaluation will take place between first and second reading.

e) Early and Ongoing Consultation:

In respect of Section 475 of the *Local Government Act* for consultation during an OCP amendment, it is recommended that no additional consultation is required beyond the early posting of the proposed OCP amendments on the City's website, together with an invitation to the public to comment.

f) Development Applications:

In order for this application to proceed the following information must be provided, as required by the *Development Procedures Bylaw No. 5879-1999*, as amended:

- 1. An OCP Application (Schedule A);
- 2. A complete Rezoning Application (Schedule C); and
- 3. A Commercial Area Development Permit Application (Schedule D);

The above list is intended to be indicative only, other applications may be necessary as the assessment of the proposal progresses.

g) Alternatives:

The subject property is located in the Yennadon Lands study area, which Council directed staff to undertake a land use re-designation planning process for on June 18, 2019. Through this planning process, new land uses and zones may be created to reflect emerging employment trends and opportunities. As an alternative to the staff recommendation, Council could defer the subject application until a land use concept plan for the Yennadon Lands is endorsed.

CONCLUSION:

The development proposal is not in compliance with the current policies of the OCP. However, through the Employment Land Use Re-Designation process and consultation strategy for the Yennadon Lands, which recently received approval from Council to proceed, justification has been provided to support an OCP amendment to allow for a commercial development at this location, as it is consistent with the intended future employment lands uses. It is, therefore, recommended that Council grant first reading, subject to additional information being provided and assessed prior to second reading.

“Original signed by Michelle Baski”

Prepared by: **Michelle Baski, ASCT, MA
Planner**

“Original signed by Chuck Goddard”

Reviewed by: **Charles R. Goddard, BA, MA
Director of Planning**

“Original signed by David Pollock” for

Approved by: **Christine Carter, M.PL, MCIP, RPP
GM Planning and Development**


“Original signed by Kelly Swift”

Concurrence: **Kelly Swift, MBA
Acting Chief Administrative Officer**

The following appendices are attached hereto:

- Appendix A – Subject Map
- Appendix B – Ortho Map
- Appendix C – Zone Amending Bylaw No. 7558-2019
- Appendix D – Proposed Site Plan

APPENDIX A



Legend

- Street Name Labels
- Stream
- Ditch Centreline
- Lake or Reservoir

Scale: 1:2,500

12791 232 St
PID 003-269-477

ENGINEERING DEPARTMENT




MAPLE RIDGE
British Columbia


mapleridge.ca

FILE: 2019-119-RZ
DATE: Apr 4, 2019

BY: MC



Scale: 1:2,500



12791 232 St
PID 003-269-477

ENGINEERING DEPARTMENT




MAPLE RIDGE

British Columbia

mapleridge.ca


FILE: 2019-119-RZ
DATE: Apr 4, 2019

BY: MC



MAPLE RIDGE ZONE AMENDING

Bylaw No. 7558-2019
 Map No. 1799
 From: RS-2 (One Family Suburban Residential)
 To: CS-1 (Service Commercial)



APPENDIX D

A3

DATE: 08/14/2018
SCALE: 1" = 30'-0"

WAYNE STEPHEN BISSKY ARCHITECTURE & URBAN DESIGN INC.
PLANNING INTERIOR DESIGN

Axonometric View #2 from S-E
Proposed C-2 Development

City Address: 12781-223rd Street, Maple Ridge, BC
Copyright © 2018 Wayne Stephen Bissky Architecture & Urban Design Inc. All rights reserved. No part of this document may be reproduced without the prior written consent of Wayne Stephen Bissky Architecture & Urban Design Inc.

REVISIONS



1 Axonometric View of Site from S-E
Scale: 1" = 30'-0"

ISSUE WHEN PRINTED ON 11x17 - TABLOID



City of Maple Ridge

TO: His Worship Mayor Michael Morden
and Members of Council

FROM: Chief Administrative Officer

SUBJECT: **Second Reading**
Zone Amending Bylaw No. 7407-2017;
11917 and 11903 Burnett Street

MEETING DATE: July 2, 2019
FILE NO: 2017-489-RZ
MEETING: C o W

EXECUTIVE SUMMARY:

An application has been received to rezone the subject properties, located at 11917 and 11903 Burnett Street, from RS-1 (One Family Urban Residential) to RM-2 (Medium Density Apartment Residential), to permit the future construction of 54 residential apartment units. (Appendix A) Council granted first reading to Zone Amending Bylaw No. 7407-2017 on January 16, 2018.

The applicant is also proposing variances to increase the storeys of the building from, 4 to 5 storeys and increase the maximum height of the building from 15 metres in height to 17.59 metres to the top of main roof parapet. In addition, the applicant is seeking variances for parking. (Appendix C)

The subject property is designated as *Low-Rise Apartment* in the Official Community Plan (OCP), and no OCP amendment is required to accommodate the proposed development. (Appendix B)

The subject proper is located within the Town Centre Area Plan boundaries and pursuant to Council policy, this application is subject to the Community Amenity Contribution Program at a rate of (\$3,100.00 per apartment dwelling unit for an estimated amount of \$167,400.

RECOMMENDATIONS:

- 1) That Zone Amending Bylaw No. 7407-2017 as amended in the staff report dated July 2, 2019 be given second reading, and forwarded to Public Hearing;
- 2) That the following terms and conditions be met prior to final reading:
 - i) Registration of a Rezoning Servicing Agreement as a Restrictive Covenant and receipt of the deposit of a security, as outlined in the Agreement;
 - ii) Road dedication on Burnett Street as required;
 - iii) Consolidation of the subject properties;
 - iv) Registration of a Restrictive Covenant for the Geotechnical Report, which addresses the suitability of the subject properties for the proposed development;

- v) Registration of a Restrictive Covenant for protecting the Visitor Parking; Tree Protection, Stormwater Management;
- vi) Removal of existing buildings;
- vii) In addition to the site profile, a disclosure statement must be submitted by a Professional Engineer advising whether there is any evidence of underground fuel storage tanks on the subject properties. If so, a Stage 1 Site Investigation Report is required to ensure that the subject property is not a contaminated site; and
- viii) That a voluntary contribution, in the amount of \$167,000 (\$3,100 units) be provided in keeping with the Council Policy with regard to Community Amenity Contributions.

DISCUSSION:

1) Background Context:

Applicant:	Krahn Engineering Ltd, Wayne Venebles
Legal Description:	Lot 6 and 7, Section 17, Township 12, NWP22046
OCP:	
Existing:	Low-Rise Apartment
Proposed:	No change
Zoning:	
Existing:	RS-1 (One Family Urban Residential)
Proposed:	RM-2 (Medium Density Apartment Residential)
Surrounding Uses:	
North:	Use: Apartments Zone: RM-2 (Medium Density Apartment Residential) Designation: Low-Rise Apartment
South:	Use: Apartments Zone: RM-2 Designation: Low-Rise Apartment
East:	Use: Single-family residential Zone: RS-1 (One Family Urban Residential) Designation: Urban Residential
West:	Use: Apartments and vacant Zone: RM-2 and RM-6 (Regional Town Centre High Density Apartment Residential) Designation: Low-Rise Apartment, and Medium and High-Rise Apartment
Existing Use of Property:	Single-family residential
Proposed Use of Property:	Apartments
Site Area:	0.267 ha (0.661 acres)
Access:	Burnett Street
Servicing requirement:	Urban Standard

2) Project Description:

The applicant has applied to rezone the subject property from RS-1 (One Family Urban Residential) to RM-2 (Medium Density Apartment Residential). The proposed development will consist of approximately 54 residential units with a density of 1.61 FSR with the front of the building facing onto Burnett Street. The parking will be accommodated in an underground parkade. (Appendix D)

The proposal is subject to the Maple Ridge Town Centre Development Permit Guidelines. Details of the design will be proceed in a report to Council at the Development Permit Stage.

3) Planning Analysis:

i) Official Community Plan:

The development site is located within the Downtown East Precinct of the Town Centre Area Plan. The Downtown East Precinct serves as the eastern interface and gateway to the Town Centre. More urban and pedestrian oriented development is desired in the Downtown East Precinct, which can include medium to high density residential high-rise towers. This project, a mid-rise residential building, conforms with the intent of the precinct guidelines of the Town Centre Area Plan. The Low-Rise Apartment designation is intended for development in a three (3) to five (5) storey apartment form where units are accessed from an internal corridor and residential parking is provided underground. The proposed development parking will be located within an underground parkade. (see Appendix B)

The development site is currently designated *Low-Rise Apartment* and an OCP amendment is not required to support the development and rezoning.

The following Town Centre Area Plan policies apply to this proposal:

3-1 An increase in residential and commercial density is encouraged in the Town Centre, particularly within the Central Business District... Land-use should include a mix of housing types catering to various demographics, including affordable and special needs housing, within walking distance to a broad mixture of uses, including shops, services, cultural facilities, and recreation.

This project will increase the number of condominium units within walking distance to a range of shops, services, and transit in and around the Central Business District.

3-12 High density development that is four or more storeys in height may be required to include a shadow study in consideration of adjacent sites to address potential impacts on available daylight. Consideration should also be given to the privacy of residents in existing buildings.

This project will be five storeys in height, but situated among four storey low rise apartments to its north, west and south and a row of single family homes across Burnett Street to its east. Bases on policy 3-12 above the applicant will be asked to provide a shadow study at the development permit review stage.

3-15 Concealed parking structures are encouraged in all commercial, mixed-use, multi-family uses... in the Town Centre. Below grade parking structures are particularly encouraged for Low-Rise, Medium, and High-Rise Apartment...buildings.

This project includes an underground parking garage in compliance with this policy.

3-22 All Low-Rise Apartment developments should be a minimum of three (3) storeys and a maximum of five (5) storeys in height.

This project complies with the height range envisioned by the policy.

In addition to these policies, a range of environmentally sustainable policies in the Town Centre Area Plan would also apply to this application:

2-5 Incorporating Rainwater Management practices into on-site and off-site development will be encouraged [...]. Some examples of Rainwater Management practices include:

- *bioretention areas;*
- *rainwater gardens;*
- *bioswales;*
- *landscaped curb bulges on street right-of-ways;*
- *rainwater harvest for irrigation; and*
- *green roofs.*

2-9 The use of plant and tree species that are suited for Maple Ridge climate and that will attract local songbirds and pollinating insects species [...] will be encouraged in public and private development;

2-10 Landscaping, as described in policy 2-9 above, will be encouraged in all public and private outdoor spaces in the Town Centre. For areas with a large amount of paved surfaces, such as surface parking lots and public plazas, the installation of trees, rain gardens, raised planters, and/or living green walls, where feasible, is encouraged to provide some areas of refuge for wildlife, such as small birds, rainwater interception, cooling in summer months, reduced glare from pavement, carbon sequestration, and a more attractive urban environment.

The applicant will be required to provide some of these measures as part of the development.

In summary, this project increases the residential density within the Downtown East Precinct, and provides for more one and two bedroom condominium units in close proximity to the shops and services of the Central Business District. The project's five storey buildings conform with the intent of the OCP's *Low-Rise Apartment* designation, and would be similar in scale to existing apartment buildings to its north, south and west.

ii) **Zoning Bylaw:**

The zoning application for RM-2 (Medium Density Apartment Residential) zoning would permit the proposed 54 units 5 storey apartment building with underground parking. (Appendix E and F)

iii) **Off-Street Parking And Loading Bylaw:**

The subject properties are located within the Central Business District area of the Parking Bylaw therefore the number of parking stalls required are of a reduced number than other parts of the City.

Town Centre Parking Standards Central Business District	Required	Proposed
One Bedroom = 1 parking space per unit Each additional bedroom = 0.1 parking space per unit	36 units X 1 Space = 36 18 units X 1.1 Spaces = 20 Total Required parking spaces 56	55 Plus one small car 56
Visitor Spaces = 0.10 space per unit where on-street supply available	54 units X 0.10 space = 6	5
Disabled Space	1	1
Bicycle Parking Requirements Long-Term Parking 1 per 4 units Short-Term Parking 6 per 20 units	54 units /4 X 1 Space= 14 spaces 54 units/20 X 6 Spaces = 17 spaces	22 17

As indicated in the chart above the project is deficient in parking for visitors by one space; therefore a variance is required to the *Off-Street Parking Bylaw 4350 – 1990*.

iv) **Proposed Variances:**

A Development Variance Permit application has been received for this project to request the following relaxations to *Maple Ridge Zoning Bylaw No. 3510 -1985 and Maple Ridge Off-Street Parking and Loading Bylaw No. 4350-1990*:

Detail	Required	Proposed
Maximum building height	15 m	17.59
Maximum Storeys	4	5
Front (East) Deck Wall	7.5 m	6.0 m
Rear (West) Building Wall Face Deck Wall	7.5 m 7.5 m	6.68 m 5.3 m
Side (North) Deck Wall	7.5 m	5.8 m
Parking Visitor	6 Spaces	5 Spaces

The requested variances to the RM-2 (Medium Density Apartment Residential) zone and the parking bylaw will be the subject of a future Council report.

v) **Development Permits:**

Pursuant to Section 8.11 of the OCP, a Town Centre Development Permit application is required for all multi-family residential, flexible mixed use and commercial development located in the Town Centre.

vi) **Advisory Design Panel:**

The Advisory Design Panel (ADP) reviewed the application at a meeting held on January 16, 2019 and their comments and the applicants responses can be seen in Appendix G.

The ADP concerns have been addressed and are reflected in the current plans. A detailed description of how these items were incorporated into the final design will be included in a future development permit report to Council.

vii) **Development Information Meeting:**

A Development Information Meeting was held at Maple Ridge Secondary School at 21911-122 Avenue on February 28, 2019. Five people attended the meeting. A summary of the main comments and discussions with the attendees was provided by the applicant and include the following main points:

- HUB would like a multi-use pathway.
- Parking along the street is a concern.

4) **Interdepartmental Implications:**

i) **Engineering Department:**

The applicant's civil engineer is working with the Engineering Department with respect to the capacity and condition of the existing sanitary and sewer fronting the subject property. Any upgrades to these systems will be at the applicant's expense.

There will be upgrades to the curb, gutter, sidewalks and widening of the road. There is road dedication required along Burnett Street.

ii) **Fire Department:**

The applicant will have to address all Fire requirements at the time of building permit application.

CONCLUSION:

As this application conforms to the OCP and will strengthen the Town Centre character, therefore it is recommended that second reading be given to Zone Amending Bylaw No. 7407-2017 as amended, and that application 2017-489-RZ be forwarded to Public Hearing.

"Original signed by Wendy Cooper"

Prepared by: **Wendy Cooper, MCIP, RPP
Planner I**

"Original signed by Chuck Goddard"

Reviewed by: **Charles R. Goddard, BA, MA
Director of Planning**

"Original signed by David Pollock" for

Approved by: **Christine Carter, M.PL, MCIP, RPP
GM Planning & Development Services**


"Original signed by Kelly Swift"

Concurrence: **Kelly Swift, MBA
Acting Chief Administrative Officer**

The following appendices are attached hereto:

- Appendix A – Subject Map
- Appendix B – Ortho Map
- Appendix C – Zone Amending Bylaw No. 7407-2017
- Appendix D – Site Plan
- Appendix E – Building Elevation Plans
- Appendix F – Landscape Plan
- Appendix G – ADP comments

APPENDIX A



Scale: 1:2,500

Legend

-  Ditch Centreline
-  Active Applications (RZ/SD/DP/VP)

11903 Burnett St
PID 009-150-587

PLANNING DEPARTMENT



mapleridge.ca

FILE: 2017-489-RZ
DATE: Jun 20, 2019

BY: MC



Aerial Imagery from the Spring of 2016



Scale: 1:2,000

Legend

-  Stream
-  Indefinite Creek
-  River
-  Major Rivers & Lakes

11903 & 11917 Burnett St


PLANNING DEPARTMENT



mapleridge.ca

2017-489-SD
DATE: Oct 26, 2017

BY: JV



MAPLE RIDGE ZONE AMENDING

Bylaw No. 7407-2017

Map No. 1740

From: RS-1 (One Family Urban Residential)

To: RM-2 (Medium Density Apartment Residential)





PROJECT NORTH

11803 & 11917 BURNETT STREET, MAPLE RIDGE, BC
 LEGAL ADDRESS: LOT 6 & 7 PLANSUBDIVISION SOUTH OF SECTION 17 TOWNSHIP 12
 ZONING: R18-AM (RESIDENTIAL)
 1. DRAINAGE: 11803 & 11917 BURNETT ST. & 11803 & 11917 BURNETT ST.
 2. LOT AREA: 28,179.33 S.F. (2.57 AC.)
 3. DENSITY: 1 UNIT PER 1,000 S.F. (1 UNIT PER 1,000 S.F.)
 4. DENSITY: 1 UNIT PER 1,000 S.F. (1 UNIT PER 1,000 S.F.)
 5. DENSITY: 1 UNIT PER 1,000 S.F. (1 UNIT PER 1,000 S.F.)

PROPOSED 5 STOREY CONDOMINIUM

11803 & 11917 BURNETT STREET, MAPLE RIDGE, BC
 LEGAL ADDRESS: LOT 6 & 7 PLANSUBDIVISION SOUTH OF SECTION 17 TOWNSHIP 12
 ZONING: R18-AM (RESIDENTIAL)
 1. DRAINAGE: 11803 & 11917 BURNETT ST. & 11803 & 11917 BURNETT ST.
 2. LOT AREA: 28,179.33 S.F. (2.57 AC.)
 3. DENSITY: 1 UNIT PER 1,000 S.F. (1 UNIT PER 1,000 S.F.)
 4. DENSITY: 1 UNIT PER 1,000 S.F. (1 UNIT PER 1,000 S.F.)
 5. DENSITY: 1 UNIT PER 1,000 S.F. (1 UNIT PER 1,000 S.F.)

UNIT SUMMARY

UNIT TYPE	UNIT NUMBER	UNIT AREA (SQ. FT.)	UNIT PRICE (USD)
1-BED	101-102	700	210,000
2-BED	103-104	900	270,000
3-BED	105-106	1100	330,000
TOTAL	3 UNITS	2700 SQ. FT.	810,000 USD

PROPOSED LOT COVERAGE

RESIDENT REQUIRED	100%
PROVIDED	100%
REQUIREMENT	100%

PROPOSED PARKING

PROVIDED	45
REQUIREMENT	45
REQUIREMENT	45

PROPOSED BIKE PARKING

PROVIDED	5
REQUIREMENT	5
REQUIREMENT	5

PROPOSED STAIRS


PROVIDED	2
REQUIREMENT	2
REQUIREMENT	2

PROPOSED AMENITY SPACE

PROVIDED	100
REQUIREMENT	100
REQUIREMENT	100

PROPOSED OUTDOOR AMENITY AREA

PROVIDED	100
REQUIREMENT	100
REQUIREMENT	100



APPENDIX D

A1.1

11803 & 11917 BURNETT STREET, MAPLE RIDGE, BC
 LEGAL ADDRESS: LOT 6 & 7 PLANSUBDIVISION SOUTH OF SECTION 17 TOWNSHIP 12
 ZONING: R18-AM (RESIDENTIAL)
 1. DRAINAGE: 11803 & 11917 BURNETT ST. & 11803 & 11917 BURNETT ST.
 2. LOT AREA: 28,179.33 S.F. (2.57 AC.)
 3. DENSITY: 1 UNIT PER 1,000 S.F. (1 UNIT PER 1,000 S.F.)
 4. DENSITY: 1 UNIT PER 1,000 S.F. (1 UNIT PER 1,000 S.F.)
 5. DENSITY: 1 UNIT PER 1,000 S.F. (1 UNIT PER 1,000 S.F.)

PROPOSED 5 STOREY CONDOMINIUM

UNIT SUMMARY

UNIT TYPE	UNIT NUMBER	UNIT AREA (SQ. FT.)	UNIT PRICE (USD)
1-BED	101-102	700	210,000
2-BED	103-104	900	270,000
3-BED	105-106	1100	330,000
TOTAL	3 UNITS	2700 SQ. FT.	810,000 USD

PROPOSED LOT COVERAGE

RESIDENT REQUIRED	100%
PROVIDED	100%
REQUIREMENT	100%

PROPOSED PARKING

PROVIDED	45
REQUIREMENT	45
REQUIREMENT	45

PROPOSED BIKE PARKING

PROVIDED	5
REQUIREMENT	5
REQUIREMENT	5

PROPOSED STAIRS

PROVIDED	2
REQUIREMENT	2
REQUIREMENT	2

PROPOSED AMENITY SPACE

PROVIDED	100
REQUIREMENT	100
REQUIREMENT	100

PROPOSED OUTDOOR AMENITY AREA

PROVIDED	100
REQUIREMENT	100
REQUIREMENT	100



1 | NORTH ELEVATION
SCALE 1/8" = 1'-0"



PROPOSED 5 STOREY
CONDOMINIUM

11808 & 11817 BURNETT STREET,
MAPLE RIDGE BC

ELEVATIONS

PROJECT NO. 17004

DATE: 03/20/18

A4.1

11000 151ST STREET, SUITE 100
VANCOUVER, BC V3R 1K1
TEL: 604.273.8888
WWW.KRAHNARCHITECT.COM

APPENDIX E



2 | EAST ELEVATION
SCALE 1/8" = 1'-0"

- C1 CINDIAN STONE LEDGESTONE STERLING
- C2 HAZEL PANEL SMOOTH IRON GRAY
- C3 HAZEL PANEL SMOOTH AUTUMN TAN
- C4 HAZEL PANEL SMOOTH COBBLE STONE

PROJECT COLOURS

SCALE 1/8" = 1'-0"

ELEVATION FINISH LEGEND

- A STONE NUMBER LEDGESTONE, STERLING - C1
- B HAZEL PANEL, SMOOTH, IRON GRAY COLOUR - C2
- C HAZEL PANEL, SMOOTH, AUTUMN TAN COLOUR - C3
- D HAZEL PANEL, SMOOTH, COBBLE STONE COLOUR - C4
- E METAL SLABING, PAINTED TO MATCH HALL COLOURS BELOW
- F BLACK ALUMINUM/ALSO PAINTED BLACK
- G WINDOWS & DOORS, EXTRUDED PVC - ALL WEATHER, DOUBLE LOW GLAZING OR EQUAL, WHITE SPANDREL PANEL
- H STEEL MAIN DOOR - PAINTED IRON GRAY COLOUR
- I ARCHITECTURAL CONCRETE

City of Maple Ridge ADVISORY DESIGN PANEL

Excerpt of the Minutes of the Regular Meeting of the Maple Ridge Advisory Design Panel held in the Blaney Room at Maple Ridge Municipal Hall, 11995 Haney Place, Maple Ridge, British Columbia, on Wednesday, January 16, 2019 at 4:08 pm.

The staff liaison provided an overview of the five storey, 54 unit strata apartment project. The project team gave a presentation of the project application and plans. There was discussion on CPTED issues around the stepping stones and Panel members noted an interest in a potential RCMP assessment of the topic respecting safety and security.

R/2019-006

It was moved and seconded

The File No. 2017-489-DP be supported and the following concerns be addressed as the design develops and submitted to Planning staff for follow-up:

Landscape Comments:

1. Improving the pedestrian environment, safety and privacy:

- Consider improving design and functionality of amenity space on ground floor for both CPTED (in part due to dead end pedestrian path) and usability of space to improve visibility and circulation.
- Confirm that surface parking stalls have adequate maneuvering space without conflicting with the ramp.
- Incorporate a path to the north of ramp area.
- Provide a water source and tool storage near community garden plots.
- Where benches are adjacent to guardrails, ensure railing height is code compliant.
- Coordinate the openings to the private patios with architecture.

2. Landscaping enhancements

- Check for adequate soil depth in all planters.
- Consider incorporating additional planting to wildflower seed mix area in rooftop area.
- If stepping stones are required, consider replacing trees with a columnar solid hedge.

Architectural Comments:

1. Form and Character enhancement and additional details.

- Reconsider proportions of stone relative to street scale.
- Review and ensure all material returns on all elevations are consistent. Consider softening the entryway soffit material and improve lighting.
- Review the proportions on all exterior box frames.
- Be consistent in materials for patio guardrails.

2. Pedestrian environment and safety

- Reconfigure the ground level visitor parking and circulation to soften the entry.
- Provide a curb and elevation change between parking stalls and pedestrian walkway to better protect pedestrian at the entry; provide a curb letdown for more convenient access to the accessible stall.

3. Coordination of plans

- Coordinate between architect and landscape architect disciplines and their depiction in plans ie: landscape furniture.

TO: His Worship Mayor Michael Morden
and Members of Council
FROM: Chief Administrative Officer
SUBJECT: **Second Reading**
Zone Amending Bylaw No. 7420-2018;
11575, 11587 223 Street and 22300 River Road (PID 011-537-141)

MEETING DATE: July 2, 2019
FILE NO: 2017-573-RZ
MEETING: CoW

EXECUTIVE SUMMARY:

An application has been received to rezone the subject properties, located at 11575 and 11587 223 Street and 22300 River Road, from RS-1 (One Family Urban Residential) to RM-2 (Medium Density Apartment Residential District), to permit the future construction of approximately 36 apartment units. The applicant is proposing an increase in base density from 1.8 floor space ratio (FSR) to 2.2 FSR. In accordance with Council's draft density bonus regulations, the proposed additional density can be achieved through a cash contribution, currently determined at \$96.88 per m² (\$9.00 per ft²). Council granted first reading to Zone Amending Bylaw No. 7420-2018 on March 13, 2018.

Pursuant to Council policy, this application is subject to the Community Amenity Contribution Program at a rate of \$3,100.00 per apartment dwelling unit for an estimated amount of \$111,600.00. The cash contribution total for the additional density, from 1.8 to 2.2 FSR (742.88 m²), would be approximately \$71,967.63.

RECOMMENDATIONS:

- 1) That Zone Amending Bylaw No. 7420-2018 be given second reading, and be forwarded to Public Hearing;
- 2) That the following terms and conditions be met prior to final reading:
 - i) Registration of a Rezoning Servicing Agreement as a Restrictive Covenant and receipt of the deposit of a security, as outlined in the Agreement;
 - ii) Approval from the Ministry of Transportation and Infrastructure;
 - iii) Road dedication as required;
 - iv) Purchase of 22300 River Road (PID 011-537-141) and consolidation of the subject properties;
 - v) Registration of a Restrictive Covenant for the Geotechnical Report, which addresses the suitability of the subject properties for the proposed development;
 - vi) Registration of a Restrictive Covenant for protecting the Visitor Parking;
 - vii) Registration of a Restrictive Covenant for Stormwater Management;

- viii) Removal of existing buildings;
- ix) Notification to the Department of Fisheries and Oceans and the Ministry of Environment for in-stream works on the site;
- x) Submission of a disclosure statement, prepared by a Professional Engineer advising whether there is any evidence of underground fuel storage tanks on the subject properties. If so, a Stage 1 Site Investigation Report is required to ensure that the subject property is not a contaminated site; and
- xi) Provision of a voluntary contribution, in the amount of \$111,600.00, which is in keeping with the Council Policy with regard to Community Amenity Contributions.

DISCUSSION:

1) Background Context:

Applicant:	Sunnyville Project 223rd Ltd.
Legal Description:	Lot 7 Block 1 District Lot 398 Group 1 New Westminster District Plan 155; Lot 14 Block 1 District Lot 398 Group 1 New Westminster District Plan 155; Lot 15 Block 1 District Lot 398 Group 1 New Westminster District Plan 155
OCP:	
Existing:	Low-Rise Apartment
Proposed:	Low-Rise Apartment
Zoning:	
Existing:	RS-1 (One Family Urban Residential)
Proposed:	RM-2 (Medium Density Apartment Residential District)
Surrounding Uses:	
North:	Use: Duplex and St. Andrew's Heritage Church Zone: RT-1 (Two Family Urban Residential) and H-1 (Heritage Commercial)
South:	Designation: Port Haney Heritage Adaptive Use Use: Railway and Port Haney West Coast Express Station Zone: RS-3 (One Family Rural Residential), RS-1 (One Family Urban Residential) and M-2 (General Industrial)
East:	Designation: Park Use: Apartment Zone: CRM (Commercial/Residential)
West:	Designation: Port Haney Multi-Family, Commercial & Mixed-Use Use: Multi-Family (Townhouse) Zone: RM-1 (Townhouse Residential) Designation: Low-Rise Apartment
Existing Use of Property:	Vacant
Proposed Use of Property:	Multi-Family Residential
Site Area:	2,262 m ² (0.56 acres)
Access:	223 Street
Servicing requirement:	Urban Standard

2) Project Description:

The subject properties, located at 11575 and 11587 223 Street and 22300 River Road, are located south of 116 Avenue, west of 223 Street and north of River Road. Consolidation of the subject properties will be a condition of rezoning and once combined, the three lots have a total area of 2,262 m² (0.56 acres). All three properties are currently vacant. The development site's elevation descends from north to south towards the Fraser River; however, most of the transition occurs on slopes on the northern and southern sections of the site. The central section of the development site is relatively flat. There are trees located around the perimeter of the subject site, as well as lawn and shrubs located throughout the remainder of the subject property. There are a row of three heritage properties, listed on the 'Heritage Inventory' (Masonic Hall, St. Andrew's Heritage Church and St. Andrew's Manse), adjacent to the subject property on the north side of 116 Avenue, and the Port Haney West Coast Express Station is located across the street on the south side of River Road.

The current application proposes to rezone the subject properties from RS-1 (One Family Urban Residential) to RM-2 (Medium Density Apartment Residential District) to permit the construction of a five storey apartment building consisting of 36 units. The proposed building will consist of a concrete base and wood frame construction with a mix of one, two and three bedroom units. Residential parking will be located underground and will be accessed from 223 Street with visitor parking located in the underground parking. The main pedestrian entrance, loading area and some on-street parking is also proposed along the 223 Street frontage. Due to grade changes sloping north to south, the building will appear to be a four storey apartment from 116 Avenue and a five storey apartment from River Road. The top floor will be recessed to provide a visual break in the massing, further allowing for larger open space and patio areas for top floor units. Materials will consist of brick at the base, cement paneling and wood cladding. Extensive landscaping has been proposed on the southern portions of the development and along the retaining walls, including a public art piece and seating features at the corner of River Road and 223 Street (see Appendix F).

The property located at 22300 River Road is currently owned by the City; however, the developer will purchase the City property to be included as part of the development prior to final reading. The City property is 677 m² in size and on its own has little development potential, due to its steep slopes and the amount of dedication required to achieve current road standards. Council will be consulted on the appraisal of the City-owned property and will be required to authorize the sale.

Some details of the current design are still to be determined and will be the subject of a future report to Council, through Development Permit application 2017-573-DP.

3) Planning Analysis:

i) Official Community Plan:

The development site is located within the Port Haney and Waterfront Precinct of the Town Centre Area Plan. This precinct is an important transportation link between the Central Business District, the Fraser River Waterfront, the West Coast Express Station and east Maple Ridge via the Haney Bypass. Port Haney's historic roots, heritage character, waterfront access, green space, and river and mountain views are a treasured part of the precinct that should be enhanced through any new development.

The subject property is designated as *Low-Rise Apartment*, and stated in Policy 3-22: "*is intended for developmet in a three (3) to five (5) storey apartment form where units are accessed from an internal corridor and residential parking is provided underground.*" An OCP amendment is not required to support the proposed project.

The following policies apply to this proposal:

Town Centre Area Plan

3-1 An increase in residential and commercial density is encouraged in the Town Centre [...] Land-use should include a mix of housing types catering to various demographics, including affordable and special needs housing, within walking distance to a broad mixture of uses, including shops, services, cultural facilities, and recreation.

- This project increases the residential density by introducing up to thirty-six (36) units, including one, one-bedroom unit; 20 two-bedroom units and 15 three-bedroom units. The subject site is located within walking distance to a range of shops, services, the Westcoast Express and the Fraser River Waterfront.

3-11 Viewscape studies may be required for proposed buildings greater than three (3) storeys in height, where views may be impacted [...] to the Fraser River to the south. Important views have been identified along 224 Street, within Port Haney, and the south slopes of the Town Centre on 116th and on 227th. In locations where it is deemed that key views will be impacted, an increase in density, or the proposed form, may not be supported.

- This project's five storey height, in addition to the development site's moderate slope and location will provide excellent views towards the Fraser River. There is little likelihood that any existing views will be blocked.

3-12 High density development that is four or more storeys in height may be required to include a shadow study in consideration of adjacent sites to address potential impacts on available daylight.

- The applicant has provided a shadow study to show impacts to adjacent properties. Shadowing during the winter months has the largest impact to those surrounding properties, most notably to the north. However, given these properties are heritage properties, their likelihood of redevelopment is minimal.

2-9 The use of plant and tree species that are suited for Maple Ridge climate and that will attract local songbirds and pollinating insects species [...] will be encouraged in public and private development;

2-10 Landscaping, as described in policy 2-9 above, will be encouraged in all public and private outdoor spaces in the Town Centre. For areas with a large amount of paved surfaces, such as surface parking lots and public plazas, the installation of trees, rain gardens, raised planters, and/or living green walls, where feasible, is encouraged to provide some areas of refuge for wildlife, such as small birds, rainwater interception, cooling in summer months, reduced glare from pavement, carbon sequestration, and a more attractive urban environment.

- Extensive landscaping with a variety of plant and tree species is proposed around the subject property, with a strong focus along the southern portions of the site and along the new retaining walls. The applicant is proposing an accessible pedestrian feature, at the corner of River Road and 223 Street, to help reduce the impact of the retaining walls. This southern section will also provide a seating area and public art feature that is reflective of the Fraser River and complimentary to the West Coast Express station (see Appendix G).

Housing Action Plan:

The City's Housing Action Plan (HAP) was endorsed by Council in 2014. It seeks to increase access to "safe, affordable, and appropriate housing that meets the diverse and changing needs of the community". The HAP also speaks of the need to provide a range of non-market, affordable and special needs housing. This was reaffirmed with the endorsement of the Housing Action Plan Implementation Framework in September, 2015. The subject application does provide a mix of unit size including one, two, and three bedroom units; however, the applicant has indicated they are not interested in providing any dedicated rental, affordable, or special needs housing.

Citywide Community Amenity Program:

The City-wide Community Amenity (CAC) Program approved by Council on March 14, 2016 and amended on December 14, 2017, applies to this project. A voluntary contribution of \$3,100 per apartment unit, totaling \$111,600, is required for this project before final reading.

ii) Zoning Bylaw:

The current application proposes to rezone the subject properties from RS-1 (One Family Urban Residential) to RM-2 (Medium Density Apartment Residential District) to permit the construction of a five storey apartment building. The maximum allowable density within the RM-2 (Medium Density Apartment Residential District) zone has an FSR of 1.8 times the net lot area. This development is proposing an FSR of 2.2, which exceeds the maximum allowable density by 0.4 FSR or 742.88m² (7,997 ft²). Based on Council's draft density bonus regulations for RM-2 (Medium Density Apartment Residential District) zoned properties, additional density can be achieved in exchange for a cash contribution currently set at \$96.88 per m² (\$9.00 per ft²). There is ongoing discussion regarding the density bonus contribution rates; however, the dollar value listed above (\$96.88 per m²) is the most current framework and may be subject to change for future applications. Recent discussions with Council have also noted a preference for cash-in-lieu rather than the direct provision of rental units. Any density bonus contribution received are intended to help fund the creation of future affordable housing in the community.

A preliminary review of the plans indicate that the proposal generally complies with the *Zoning Bylaw* and the *Subdivision and Development Services Bylaw*; however, variances will be requested, as discussed below.

iii) Off-Street Parking And Loading Bylaw:

The *Off-Street Parking and Loading Bylaw* requires 1.5 parking spaces plus 0.2 spaces for visitor parking per dwelling unit in the RM-2 (Medium Density Apartment Residential District) zone, requiring 62 spaces in total for the proposed 36 unit development. The applicant is proposing 45 resident parking spaces and six visitor parking spaces, for a total of 51 parking spaces; therefore, a variance will be required. The applicant is also requesting a variance to increase the percentage of allowable small car spaces from 10% to 13.7%. As per Schedule "C" in the *Off-Street Parking and Loading Bylaw*, the applicant may choose the 'Payment-In-Lieu' Fees for residential parking off-site. The fee for 'Payment-In-Lieu' is \$8,000.00 per stall (multiplied by 11 spaces), for a total of \$88,000.00. Two of the parking spaces are designated accessible parking and three spaces are designed as level 2 charging stations for electric vehicles. Some limited on-street parking will be available on all three street frontages.

iv) Proposed Variances:

A preliminary review of the plans indicate that the proposal generally complies with the *Zoning Bylaw, Subdivision and Development Services Bylaw and Off-Street Parking and Loading Bylaw*; however, variances will be requested through a Variance Permit application. The following proposed relaxations are outlined below:

Zoning Bylaw:

- Reduce eastern property setback (223 Street) from 7.5m to 1.24m.
- Increase maximum height from 15m (4 storey's) to 18.2m (5 storey's).
- Increase in retaining wall height.

Off-Street Parking and Loading Bylaw:

- Reduce parking requirement from 51 stalls to 40 stalls (reduction of 11 stalls).
- Increase percentage of small car stalls from 10% to 13.7%.

The requested variances to the RM-2 zone (Medium Density Apartment Residential District) will be the subject of a future Council report.

v) Development Permits:

Pursuant to Section 8.11 of the OCP, a Town Centre Development Permit application is required for all multifamily residential, flexible mixed use and commercial development located in the Town Centre.

Pursuant to Section 8.9 of the OCP, a Watercourse Protection Development Permit application is required for all developments and building permits within 50m of the top of bank of all watercourses and wetlands. The purpose of the Watercourse Protection Development Permit is to ensure the preservation, protection, restoration and enhancement of watercourse and riparian areas.

vi) Advisory Design Panel:

The application was reviewed by the ADP on January 16, 2019 and their comments and the applicants responses can be seen in Appendix H. The details of the project's form and character will be outlined to Council in a future Development Permit report.

vii) Development Information Meeting:

A Development Information Meeting was held at Fraserview Community Hall on June 10, 2019. Six people attended the meeting. A summary of the main comments and discussions with the attendees was provided by the applicant and include the following main points:

- Concern regarding noise and vibrations from the trains.
- Concern from neighbours to the west regarding slope stability and impacts the proposed development may have on the existing building (west).
- Comments regarding the proposed landscaping to ensure appropriate planting choices that reflect climate change. As well, comments seem very positive on the landscape area renderings and a hope that the completed project appears as illustrated.
- General questions regarding building details including: electric vehicle charging stations; location of recycling and garbage access; unit size and cost; and project timing.

The following are provided in response to the issues raised by the public:

- Developer will consider acoustic buffering, and suggested that they will be using soundproof construction materials to mitigate the noise.
- Geotechnical report has been provided and is in support of the development.
- Developer will consider using drought resistant plantings. Landscape plans were prepared by a Landscape Architect, as well, plans have been supported by the Advisory Design Panel.

4) Environmental Implications:

An Environmental Assessment, Arborist Report and Geotechnical Report were provided as part of the development application. The development site's elevation descends from north to south towards the Fraser River; however, most of the transition occurs on slopes on the northern and southern sections of the site. The central section of the development site is relatively flat. Vegetation on the subject properties consist of ornamental shrubs, grasses and mature trees. A watercourse (roadside ditch) is located along the southern property boundary, north of River Road. As part of the servicing requirements, this roadside ditch will be removed and a storm sewer will be implemented. This southern-most portion of the property is currently vegetated with invasive species, including Himalayan Blackberry, which will be removed as part of development. Assessment of the roadside ditch, provided by the Environmental Consultant, concludes it is non-fish bearing.

5) Traffic Impact:

As the subject properties are located within 800m of the Lougheed Highway, a referral has been sent to the Ministry of Transportation and Infrastructure. Ministry approval of the Zone Amending Bylaw will be required as a condition of final reading. At this time, the Ministry has granted preliminary approval of the development application.

6) Interdepartmental Implications:

i) Engineering Department:

To fulfill requirements with the Subdivision and Development Servicing Bylaw, the Engineering Department has requested the following:

- Concrete curb, gutter and sidewalk required along 223 Street, 116 Avenue and River Road frontages.
- A concrete bulb to be constructed at 223 Street and River Road intersection.
- Existing roadside ditch along River Road to be eliminated and replaced with a new storm sewer connection.
- 223 Street property frontage to be upgraded to a collector standard, as well as upgrades to River Road.
- A parking lane to be provided along River Road up to the existing sidewalk.
- Street lighting required on all property frontages and street trees required across 223 Street and 116 Avenue frontages.

- Existing watermains and service connections to be replaced; new sanitary sewer connections and capacity analysis required; new storm sewer and storm service connection required along River Road and extended up 223 Street.
- Road dedication required along River Road.

ii) **License, Permits and Bylaws Department:**

The Building Department has reviewed the proposal and comments have been provided to the applicant.

iii) **Fire Department:**

The Fire Department has reviewed the proposal and comments have been provided to the applicant.

7) **School District No. 42 Comments:**

The proposed application would affect the student population for the catchment areas currently served by Maple Ridge Elementary and Maple Ridge Secondary School. Maple Ridge Elementary has an operating capacity of 480 students. Actual numbers for 2016 student enrolment at Maple Ridge Elementary was 381 students (82% utilization). Maple Ridge Secondary School has an operating capacity of 1300 students. Actual numbers for 2016 student enrolment at Maple Ridge Secondary School was 1,317 students (101% utilization).

8) **Citizen/Customer Implications:**

A Development Information Meeting was held on June 10, 2019. The results of the concerns expressed at that meeting are discussed above in Section 3) vii). The Public Hearing will provide an additional opportunity for citizens to express their concern or support of the development.

CONCLUSION:

The development proposal is in compliance with the policies of the OCP as the RM-2 (Medium Density Apartment Residential District) zone aligns with the *Low Rise* designation. The applicant is proposing to increase the density for this development from 1.8 to 2.2 FSR. The current density bonus contribution rate of \$96.88 per m² is proposed for the subject application; however, this dollar value may change for future applications.

It is recommended that second reading be given to zone amending bylaw no. 7420 - 2018 and that application 2017-573-RZ be forwarded to Public Hearing.

"Original signed by Adam Rieu"

Prepared by: **Adam Rieu**
Senior Planning Technician

"Original signed by Chuck Goddard"

Reviewed by: **Charles R. Goddard, BA, MA**
Director of Planning

"Original signed by David Pollock" for

Approved by: **Christine Carter, M.PL, MCIP, RPP**
GM Public Works & Development Services

"Original signed by Kelly Swift"

Concurrence: **Kelly Swift, MBA**
Acting Chief Administrative Officer

The following appendices are attached hereto:

- Appendix A – Subject Map
- Appendix B – Ortho Map
- Appendix C – Zone Amending Bylaw No. 7420-2018
- Appendix D – Site Plan
- Appendix E – Building Elevation Plans
- Appendix F – Landscape Plan
- Appendix G – Project Rendering
- Appendix H – Advisory Design Panel Comments

APPENDIX A



Scale: 1:2,000

Legend

-  Stream
-  Ditch Centreline
-  Edge of River
-  Indefinite Creek
-  River
-  Major Rivers & Lakes

P.I.D. 011-537-141,
11575/87 223 STREET

PLANNING DEPARTMENT



mapleridge.ca

FILE: 2017-573-RZ
DATE: Feb 19, 2018


BY: PC



Aerial Imagery from the Spring of 2016



Scale: 1:2,000



P.I.D. 011-537-141,
11575/87 223 STREET


PLANNING DEPARTMENT



mapleridge.ca

FILE: 2017-573-RZ
DATE: Feb 19, 2018

BY: PC



MAPLE RIDGE ZONE AMENDING

Bylaw No. 7420-2018

Map No. 1743

From: RS-1 (One Family Urban Residential)

To: RM-2 (Medium Density Apartment Residential)




SCALE 1:2,500

© Copyright 2018
 All Rights Reserved
 THIS DRAWING IS THE PROPERTY OF INSPIRED ARCHITECTURE, INC. NO PART OF THIS DRAWING IS TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF INSPIRED ARCHITECTURE, INC. ANY REPRODUCTION OR TRANSMISSION OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION OF INSPIRED ARCHITECTURE, INC. IS STRICTLY PROHIBITED.

NO.	DATE	DESCRIPTION
1	01.15.18	ISSUED FOR PERMITS
2	02.15.18	ISSUED FOR PERMITS
3	03.15.18	ISSUED FOR PERMITS
4	04.15.18	ISSUED FOR PERMITS
5	05.15.18	ISSUED FOR PERMITS
6	06.15.18	ISSUED FOR PERMITS
7	07.15.18	ISSUED FOR PERMITS
8	08.15.18	ISSUED FOR PERMITS
9	09.15.18	ISSUED FOR PERMITS
10	10.15.18	ISSUED FOR PERMITS
11	11.15.18	ISSUED FOR PERMITS
12	12.15.18	ISSUED FOR PERMITS
13	01.15.19	ISSUED FOR PERMITS
14	02.15.19	ISSUED FOR PERMITS
15	03.15.19	ISSUED FOR PERMITS
16	04.15.19	ISSUED FOR PERMITS
17	05.15.19	ISSUED FOR PERMITS
18	06.15.19	ISSUED FOR PERMITS
19	07.15.19	ISSUED FOR PERMITS
20	08.15.19	ISSUED FOR PERMITS
21	09.15.19	ISSUED FOR PERMITS
22	10.15.19	ISSUED FOR PERMITS
23	11.15.19	ISSUED FOR PERMITS
24	12.15.19	ISSUED FOR PERMITS
25	01.15.20	ISSUED FOR PERMITS
26	02.15.20	ISSUED FOR PERMITS
27	03.15.20	ISSUED FOR PERMITS
28	04.15.20	ISSUED FOR PERMITS
29	05.15.20	ISSUED FOR PERMITS
30	06.15.20	ISSUED FOR PERMITS
31	07.15.20	ISSUED FOR PERMITS
32	08.15.20	ISSUED FOR PERMITS
33	09.15.20	ISSUED FOR PERMITS
34	10.15.20	ISSUED FOR PERMITS
35	11.15.20	ISSUED FOR PERMITS
36	12.15.20	ISSUED FOR PERMITS
37	01.15.21	ISSUED FOR PERMITS
38	02.15.21	ISSUED FOR PERMITS
39	03.15.21	ISSUED FOR PERMITS
40	04.15.21	ISSUED FOR PERMITS
41	05.15.21	ISSUED FOR PERMITS
42	06.15.21	ISSUED FOR PERMITS
43	07.15.21	ISSUED FOR PERMITS
44	08.15.21	ISSUED FOR PERMITS
45	09.15.21	ISSUED FOR PERMITS
46	10.15.21	ISSUED FOR PERMITS
47	11.15.21	ISSUED FOR PERMITS
48	12.15.21	ISSUED FOR PERMITS
49	01.15.22	ISSUED FOR PERMITS
50	02.15.22	ISSUED FOR PERMITS
51	03.15.22	ISSUED FOR PERMITS
52	04.15.22	ISSUED FOR PERMITS
53	05.15.22	ISSUED FOR PERMITS
54	06.15.22	ISSUED FOR PERMITS
55	07.15.22	ISSUED FOR PERMITS
56	08.15.22	ISSUED FOR PERMITS
57	09.15.22	ISSUED FOR PERMITS
58	10.15.22	ISSUED FOR PERMITS
59	11.15.22	ISSUED FOR PERMITS
60	12.15.22	ISSUED FOR PERMITS
61	01.15.23	ISSUED FOR PERMITS
62	02.15.23	ISSUED FOR PERMITS
63	03.15.23	ISSUED FOR PERMITS
64	04.15.23	ISSUED FOR PERMITS
65	05.15.23	ISSUED FOR PERMITS
66	06.15.23	ISSUED FOR PERMITS
67	07.15.23	ISSUED FOR PERMITS
68	08.15.23	ISSUED FOR PERMITS
69	09.15.23	ISSUED FOR PERMITS
70	10.15.23	ISSUED FOR PERMITS
71	11.15.23	ISSUED FOR PERMITS
72	12.15.23	ISSUED FOR PERMITS
73	01.15.24	ISSUED FOR PERMITS
74	02.15.24	ISSUED FOR PERMITS
75	03.15.24	ISSUED FOR PERMITS
76	04.15.24	ISSUED FOR PERMITS
77	05.15.24	ISSUED FOR PERMITS
78	06.15.24	ISSUED FOR PERMITS
79	07.15.24	ISSUED FOR PERMITS
80	08.15.24	ISSUED FOR PERMITS
81	09.15.24	ISSUED FOR PERMITS
82	10.15.24	ISSUED FOR PERMITS
83	11.15.24	ISSUED FOR PERMITS
84	12.15.24	ISSUED FOR PERMITS
85	01.15.25	ISSUED FOR PERMITS
86	02.15.25	ISSUED FOR PERMITS
87	03.15.25	ISSUED FOR PERMITS
88	04.15.25	ISSUED FOR PERMITS
89	05.15.25	ISSUED FOR PERMITS
90	06.15.25	ISSUED FOR PERMITS
91	07.15.25	ISSUED FOR PERMITS
92	08.15.25	ISSUED FOR PERMITS
93	09.15.25	ISSUED FOR PERMITS
94	10.15.25	ISSUED FOR PERMITS
95	11.15.25	ISSUED FOR PERMITS
96	12.15.25	ISSUED FOR PERMITS
97	01.15.26	ISSUED FOR PERMITS
98	02.15.26	ISSUED FOR PERMITS
99	03.15.26	ISSUED FOR PERMITS
100	04.15.26	ISSUED FOR PERMITS
101	05.15.26	ISSUED FOR PERMITS
102	06.15.26	ISSUED FOR PERMITS
103	07.15.26	ISSUED FOR PERMITS
104	08.15.26	ISSUED FOR PERMITS
105	09.15.26	ISSUED FOR PERMITS
106	10.15.26	ISSUED FOR PERMITS
107	11.15.26	ISSUED FOR PERMITS
108	12.15.26	ISSUED FOR PERMITS
109	01.15.27	ISSUED FOR PERMITS
110	02.15.27	ISSUED FOR PERMITS
111	03.15.27	ISSUED FOR PERMITS
112	04.15.27	ISSUED FOR PERMITS
113	05.15.27	ISSUED FOR PERMITS
114	06.15.27	ISSUED FOR PERMITS
115	07.15.27	ISSUED FOR PERMITS
116	08.15.27	ISSUED FOR PERMITS
117	09.15.27	ISSUED FOR PERMITS
118	10.15.27	ISSUED FOR PERMITS
119	11.15.27	ISSUED FOR PERMITS
120	12.15.27	ISSUED FOR PERMITS
121	01.15.28	ISSUED FOR PERMITS
122	02.15.28	ISSUED FOR PERMITS
123	03.15.28	ISSUED FOR PERMITS
124	04.15.28	ISSUED FOR PERMITS
125	05.15.28	ISSUED FOR PERMITS
126	06.15.28	ISSUED FOR PERMITS
127	07.15.28	ISSUED FOR PERMITS
128	08.15.28	ISSUED FOR PERMITS
129	09.15.28	ISSUED FOR PERMITS
130	10.15.28	ISSUED FOR PERMITS
131	11.15.28	ISSUED FOR PERMITS
132	12.15.28	ISSUED FOR PERMITS
133	01.15.29	ISSUED FOR PERMITS
134	02.15.29	ISSUED FOR PERMITS
135	03.15.29	ISSUED FOR PERMITS
136	04.15.29	ISSUED FOR PERMITS
137	05.15.29	ISSUED FOR PERMITS
138	06.15.29	ISSUED FOR PERMITS
139	07.15.29	ISSUED FOR PERMITS
140	08.15.29	ISSUED FOR PERMITS
141	09.15.29	ISSUED FOR PERMITS
142	10.15.29	ISSUED FOR PERMITS
143	11.15.29	ISSUED FOR PERMITS
144	12.15.29	ISSUED FOR PERMITS
145	01.15.30	ISSUED FOR PERMITS
146	02.15.30	ISSUED FOR PERMITS
147	03.15.30	ISSUED FOR PERMITS
148	04.15.30	ISSUED FOR PERMITS
149	05.15.30	ISSUED FOR PERMITS
150	06.15.30	ISSUED FOR PERMITS
151	07.15.30	ISSUED FOR PERMITS
152	08.15.30	ISSUED FOR PERMITS
153	09.15.30	ISSUED FOR PERMITS
154	10.15.30	ISSUED FOR PERMITS
155	11.15.30	ISSUED FOR PERMITS
156	12.15.30	ISSUED FOR PERMITS
157	01.15.31	ISSUED FOR PERMITS
158	02.15.31	ISSUED FOR PERMITS
159	03.15.31	ISSUED FOR PERMITS
160	04.15.31	ISSUED FOR PERMITS
161	05.15.31	ISSUED FOR PERMITS
162	06.15.31	ISSUED FOR PERMITS
163	07.15.31	ISSUED FOR PERMITS
164	08.15.31	ISSUED FOR PERMITS
165	09.15.31	ISSUED FOR PERMITS
166	10.15.31	ISSUED FOR PERMITS
167	11.15.31	ISSUED FOR PERMITS
168	12.15.31	ISSUED FOR PERMITS
169	01.15.32	ISSUED FOR PERMITS
170	02.15.32	ISSUED FOR PERMITS
171	03.15.32	ISSUED FOR PERMITS
172	04.15.32	ISSUED FOR PERMITS
173	05.15.32	ISSUED FOR PERMITS
174	06.15.32	ISSUED FOR PERMITS
175	07.15.32	ISSUED FOR PERMITS
176	08.15.32	ISSUED FOR PERMITS
177	09.15.32	ISSUED FOR PERMITS
178	10.15.32	ISSUED FOR PERMITS
179	11.15.32	ISSUED FOR PERMITS
180	12.15.32	ISSUED FOR PERMITS
181	01.15.33	ISSUED FOR PERMITS
182	02.15.33	ISSUED FOR PERMITS
183	03.15.33	ISSUED FOR PERMITS
184	04.15.33	ISSUED FOR PERMITS
185	05.15.33	ISSUED FOR PERMITS
186	06.15.33	ISSUED FOR PERMITS
187	07.15.33	ISSUED FOR PERMITS
188	08.15.33	ISSUED FOR PERMITS
189	09.15.33	ISSUED FOR PERMITS
190	10.15.33	ISSUED FOR PERMITS
191	11.15.33	ISSUED FOR PERMITS
192	12.15.33	ISSUED FOR PERMITS
193	01.15.34	ISSUED FOR PERMITS
194	02.15.34	ISSUED FOR PERMITS
195	03.15.34	ISSUED FOR PERMITS
196	04.15.34	ISSUED FOR PERMITS
197	05.15.34	ISSUED FOR PERMITS
198	06.15.34	ISSUED FOR PERMITS
199	07.15.34	ISSUED FOR PERMITS
200	08.15.34	ISSUED FOR PERMITS
201	09.15.34	ISSUED FOR PERMITS
202	10.15.34	ISSUED FOR PERMITS
203	11.15.34	ISSUED FOR PERMITS
204	12.15.34	ISSUED FOR PERMITS
205	01.15.35	ISSUED FOR PERMITS
206	02.15.35	ISSUED FOR PERMITS
207	03.15.35	ISSUED FOR PERMITS
208	04.15.35	ISSUED FOR PERMITS
209	05.15.35	ISSUED FOR PERMITS
210	06.15.35	ISSUED FOR PERMITS
211	07.15.35	ISSUED FOR PERMITS
212	08.15.35	ISSUED FOR PERMITS
213	09.15.35	ISSUED FOR PERMITS
214	10.15.35	ISSUED FOR PERMITS
215	11.15.35	ISSUED FOR PERMITS
216	12.15.35	ISSUED FOR PERMITS
217	01.15.36	ISSUED FOR PERMITS
218	02.15.36	ISSUED FOR PERMITS
219	03.15.36	ISSUED FOR PERMITS
220	04.15.36	ISSUED FOR PERMITS
221	05.15.36	ISSUED FOR PERMITS
222	06.15.36	ISSUED FOR PERMITS
223	07.15.36	ISSUED FOR PERMITS
224	08.15.36	ISSUED FOR PERMITS
225	09.15.36	ISSUED FOR PERMITS
226	10.15.36	ISSUED FOR PERMITS
227	11.15.36	ISSUED FOR PERMITS
228	12.15.36	ISSUED FOR PERMITS
229	01.15.37	ISSUED FOR PERMITS
230	02.15.37	ISSUED FOR PERMITS
231	03.15.37	ISSUED FOR PERMITS
232	04.15.37	ISSUED FOR PERMITS
233	05.15.37	ISSUED FOR PERMITS
234	06.15.37	ISSUED FOR PERMITS
235	07.15.37	ISSUED FOR PERMITS
236	08.15.37	ISSUED FOR PERMITS
237	09.15.37	ISSUED FOR PERMITS
238	10.15.37	ISSUED FOR PERMITS
239	11.15.37	ISSUED FOR PERMITS
240	12.15.37	ISSUED FOR PERMITS
241	01.15.38	ISSUED FOR PERMITS
242	02.15.38	ISSUED FOR PERMITS
243	03.15.38	ISSUED FOR PERMITS
244	04.15.38	ISSUED FOR PERMITS
245	05.15.38	ISSUED FOR PERMITS
246	06.15.38	ISSUED FOR PERMITS
247	07.15.38	ISSUED FOR PERMITS
248	08.15.38	ISSUED FOR PERMITS
249	09.15.38	ISSUED FOR PERMITS
250	10.15.38	ISSUED FOR PERMITS
251	11.15.38	ISSUED FOR PERMITS
252	12.15.38	ISSUED FOR PERMITS
253	01.15.39	ISSUED FOR PERMITS
254	02.15.39	ISSUED FOR PERMITS
255	03.15.39	ISSUED FOR PERMITS
256	04.15.39	ISSUED FOR PERMITS
257	05.15.39	ISSUED FOR PERMITS
258	06.15.39	ISSUED FOR PERMITS
259	07.15.39	ISSUED FOR PERMITS
260	08.15.39	ISSUED FOR PERMITS
261	09.15.39	ISSUED FOR PERMITS
262	10.15.39	ISSUED FOR PERMITS
263	11.15.39	ISSUED FOR PERMITS
264	12.15.39	ISSUED FOR PERMITS
265	01.15.40	ISSUED FOR PERMITS
266	02.15.40	ISSUED FOR PERMITS
267	03.15.40	ISSUED FOR PERMITS
268	04.15.40	ISSUED FOR PERMITS
269	05.15.40	ISSUED FOR PERMITS
270	06.15.40	ISSUED FOR PERMITS
271	07.15.40	ISSUED FOR PERMITS
272	08.15.40	ISSUED FOR PERMITS
273	09.15.40	ISSUED FOR PERMITS
274	10.15.40	ISSUED FOR PERMITS
275	11.15.40	ISSUED FOR PERMITS
276	12.15.40	ISSUED FOR PERMITS
277	01.15.41	ISSUED FOR PERMITS
278	02.15.41	ISSUED FOR PERMITS
279	03.15.41	ISSUED FOR PERMITS
280	04.15.41	ISSUED FOR PERMITS
281	05.15.41	ISSUED FOR PERMITS
282	06.15.41	ISSUED FOR PERMITS
283	07.15.41	ISSUED FOR PERMITS
284	08.15.41	ISSUED FOR PERMITS
285	09.15.41	ISSUED FOR PERMITS
286	10.15.41	ISSUED FOR PERMITS
287	11.15.41	ISSUED FOR PERMITS
288	12.15.41	ISSUED FOR PERMITS
289	01.15.42	ISSUED FOR PERMITS
290	02.15.42	ISSUED FOR PERMITS
291	03.15.42	ISSUED FOR PERMITS
292	04.15.42	ISSUED FOR PERMITS
293	05.15.42	ISSUED FOR PERMITS
294	06.15.42	ISSUED FOR PERMITS
295	07.15.42	ISSUED FOR PERMITS
296	08.15.42	ISSUED FOR PERMITS
297	09.15.42	ISSUED FOR PERMITS
298	10.15.42	ISSUED FOR PERMITS
299	11.15.42	ISSUED FOR PERMITS
300	12.15.42	ISSUED FOR PERMITS

APPENDIX D

- SITE PLAN LINE TYPES**
- PROPERTY LINE
 - SETBACK LINE
 - PARKING OUTLINE
 - LEVEL 1 OUTLINE
 - LEVEL 2-4 OUTLINE
 - LEVEL 5 OUTLINE



3 SV SITE PLAN-200
 SCALE 1/8"=1'-0"



REISSUED FOR SECOND HEARING

PROJECT NO.	17180	PLOT DATE	MAY. 17, 2018	DRAWN	MGR
DATE		DATE		REVISION	AF
ISSUED NO.	A-0101	AS INDICATED		SECTION	6



© Copyright Inspired Architecture, 2019.
 All rights reserved.
 THIS DRAWING IS THE PROPERTY OF INSPIRED ARCHITECTURE. THE
 INFORMATION CONTAINED HEREIN IS UNCLASSIFIED AND NOT FOR
 CONTROLLED BY THE CANADIAN SECURITY INFORMATION ACT.
 THIS DRAWING IS THE PROPERTY OF INSPIRED ARCHITECTURE. THE
 INFORMATION CONTAINED HEREIN IS UNCLASSIFIED AND NOT FOR
 CONTROLLED BY THE CANADIAN SECURITY INFORMATION ACT.
 ANY REPRODUCTION OR TRANSMISSION OF THIS DRAWING
 WITHOUT THE WRITTEN PERMISSION OF INSPIRED ARCHITECTURE IS
 STRICTLY PROHIBITED.

ITEM	MATERIAL	FINISH / COLOUR
01	CAST-IN-PLACE CONCRETE	ARCHITECTURAL FINISH GRAY
02	5.589 X14.589 BRICK	STACK
03	HARDY PANE PANEL, CW REVEAL	SMOOTH COBBLE STONE
04	WOODGRAN METAL CLADDING	CHARCOAL
05	WOODGRAN METAL CLADDING	CHARCOAL
06	ALUMINUM WINDOW MULLION	ANODIZED CHARCOAL
07	DOUBLE GLAZE GLASS PANEL	CLEAR
08	ALUMINUM GUARD FRAME	CHARCOAL
09	HEAVY GLAZING	STAINED CLEAR
10	HEAVY GLAZING	STAINED CLEAR
11	HEAVY GLAZING	STAINED CLEAR
12	HEAVY GLAZING	STAINED CLEAR
13	HEAVY GLAZING	STAINED CLEAR
14	SPANDREL	CULTURED STONE SCULPTED GRAY
15	PRECAST CONCRETE LINTEL	ARCHITECTURAL FINISH GRAY
16	PRECAST CONCRETE COPING	ARCHITECTURAL FINISH GRAY
17	WOOD BRACKET	STAINED



NO.	DESCRIPTION	DATE
01	ISSUED FOR PERMIT	2019.05.17
02	ISSUED FOR PERMIT	2019.05.17
03	ISSUED FOR PERMIT	2019.05.17
04	ISSUED FOR PERMIT	2019.05.17
05	ISSUED FOR PERMIT	2019.05.17
06	ISSUED FOR PERMIT	2019.05.17
07	ISSUED FOR PERMIT	2019.05.17
08	ISSUED FOR PERMIT	2019.05.17
09	ISSUED FOR PERMIT	2019.05.17
10	ISSUED FOR PERMIT	2019.05.17
11	ISSUED FOR PERMIT	2019.05.17
12	ISSUED FOR PERMIT	2019.05.17
13	ISSUED FOR PERMIT	2019.05.17
14	ISSUED FOR PERMIT	2019.05.17
15	ISSUED FOR PERMIT	2019.05.17
16	ISSUED FOR PERMIT	2019.05.17
17	ISSUED FOR PERMIT	2019.05.17

PROJECT
 223rd STREET
 1515 8, 1187 22nd St, Maple Ridge, BC
 DRAWING TITLE
 WEST & EAST ELEVATIONS
 REISSUED FOR SECOND HEARING
 PROJECT NO. 17180
 DATE MAY 17, 2019
 DRAWN BY MGH
 CHECKED BY MGH
 SCALE 1:100
 SHEET NO. A-0402
 TOTAL SHEETS 6

Copyright reserved. This drawing and design is the property of pmg and is not to be reproduced or used for other projects without pmg's permission.

pmg
LANDSCAPE ARCHITECTS
Suite C100 - 4185 5th Street
Vancouver, BC V6J 1K1
P: 604.266.0111 F: 604.266.0222

SEAL:

NO.	DATE	REVISION DESCRIPTION	DR.
1	2014.08.01	ISSUED FOR PERMIT	DR
2	2014.08.01	ISSUED FOR PERMIT	DR
3	2014.08.01	ISSUED FOR PERMIT	DR
4	2014.08.01	ISSUED FOR PERMIT	DR
5	2014.08.01	ISSUED FOR PERMIT	DR
6	2014.08.01	ISSUED FOR PERMIT	DR
7	2014.08.01	ISSUED FOR PERMIT	DR
8	2014.08.01	ISSUED FOR PERMIT	DR
9	2014.08.01	ISSUED FOR PERMIT	DR
10	2014.08.01	ISSUED FOR PERMIT	DR
11	2014.08.01	ISSUED FOR PERMIT	DR
12	2014.08.01	ISSUED FOR PERMIT	DR
13	2014.08.01	ISSUED FOR PERMIT	DR
14	2014.08.01	ISSUED FOR PERMIT	DR
15	2014.08.01	ISSUED FOR PERMIT	DR
16	2014.08.01	ISSUED FOR PERMIT	DR
17	2014.08.01	ISSUED FOR PERMIT	DR
18	2014.08.01	ISSUED FOR PERMIT	DR
19	2014.08.01	ISSUED FOR PERMIT	DR
20	2014.08.01	ISSUED FOR PERMIT	DR
21	2014.08.01	ISSUED FOR PERMIT	DR
22	2014.08.01	ISSUED FOR PERMIT	DR
23	2014.08.01	ISSUED FOR PERMIT	DR
24	2014.08.01	ISSUED FOR PERMIT	DR
25	2014.08.01	ISSUED FOR PERMIT	DR
26	2014.08.01	ISSUED FOR PERMIT	DR
27	2014.08.01	ISSUED FOR PERMIT	DR
28	2014.08.01	ISSUED FOR PERMIT	DR
29	2014.08.01	ISSUED FOR PERMIT	DR
30	2014.08.01	ISSUED FOR PERMIT	DR
31	2014.08.01	ISSUED FOR PERMIT	DR
32	2014.08.01	ISSUED FOR PERMIT	DR
33	2014.08.01	ISSUED FOR PERMIT	DR
34	2014.08.01	ISSUED FOR PERMIT	DR
35	2014.08.01	ISSUED FOR PERMIT	DR
36	2014.08.01	ISSUED FOR PERMIT	DR
37	2014.08.01	ISSUED FOR PERMIT	DR
38	2014.08.01	ISSUED FOR PERMIT	DR
39	2014.08.01	ISSUED FOR PERMIT	DR
40	2014.08.01	ISSUED FOR PERMIT	DR
41	2014.08.01	ISSUED FOR PERMIT	DR
42	2014.08.01	ISSUED FOR PERMIT	DR
43	2014.08.01	ISSUED FOR PERMIT	DR
44	2014.08.01	ISSUED FOR PERMIT	DR
45	2014.08.01	ISSUED FOR PERMIT	DR
46	2014.08.01	ISSUED FOR PERMIT	DR
47	2014.08.01	ISSUED FOR PERMIT	DR
48	2014.08.01	ISSUED FOR PERMIT	DR
49	2014.08.01	ISSUED FOR PERMIT	DR
50	2014.08.01	ISSUED FOR PERMIT	DR

PROJECT:


WATER'S EDGE
11575 & 11587 223RD STREET
MAPLE RIDGE, BC

DRAWING TITLE
SHRUB PLAN

DATE: 18.04.2014
SCALE: 1:100
DRAWN: [Name]
DESIGN: [Name]
CHECKED: [Name]

L2
OF 3

PAC PROJECT NUMBER: 18-049



1804-23

©Copyright reserved. This drawing and design is the property of PMG Landscape Architects and may not be reproduced or used for other projects without their permission.

pmg
LANDSCAPE ARCHITECTS
Suite C100 - 4185 Oak Creek Drive
Vancouver, British Columbia
V6M 4K2
Tel: 604-244-9001 | Fax: 604-244-9022

SCALE:

SITE FURNISHINGS



BENCH A ENTRY & TERRACE:
METAL: BRONZE MATTE FINETEX FINISH
ALL FURNISHINGS TO BE SURFACE MOUNTED TO CONCRETE HOUSEKEEPING PAD. LOCATIONS AND SIZE TO BE COORDINATED WITH ARCHITECT, STRUCTURAL ENGINEER.



WASTE RECEPTACLE:
METAL: BRONZE MATTE FINETEX FINISH



BENCH B INTERIOR SEATING AREA:
METAL: BRONZE MATTE FINETEX FINISH



BENCH C KITCHEN/PAVING:
METAL: BRONZE MATTE FINETEX FINISH



BENCH D ENTRY & TERRACE:
METAL: BRONZE MATTE FINETEX FINISH



BENCH E ENTRY & TERRACE:
METAL: BRONZE MATTE FINETEX FINISH



BENCH F ENTRY & TERRACE:
METAL: BRONZE MATTE FINETEX FINISH



BENCH G ENTRY & TERRACE:
METAL: BRONZE MATTE FINETEX FINISH



ALUMINUM PLANTERS (30" DIA):
METAL: BRONZE MATTE FINISH
SPUN SERIES, SIZE LARGE 33" DIA



ALUMINUM PLANTERS (30" DIA):
METAL: BRONZE MATTE FINISH
SPUN SERIES, SIZE LARGE 33" DIA




ART INSTALLATION:
METAL: BRONZE MATTE FINISH
SITE SCULPTURE EMBEDDED IN PLANTERS



ART INSTALLATION:
METAL: BRONZE MATTE FINISH
SITE SCULPTURE EMBEDDED IN PLANTERS



ART INSTALLATION:
METAL: BRONZE MATTE FINISH
SITE SCULPTURE EMBEDDED IN PLANTERS



ART INSTALLATION:
METAL: BRONZE MATTE FINISH
SITE SCULPTURE EMBEDDED IN PLANTERS



ART INSTALLATION:
METAL: BRONZE MATTE FINISH
SITE SCULPTURE EMBEDDED IN PLANTERS

PAVING KEY

DECORATIVE PAVING LEVEL ONE:
HYDRAPRESSED CONCRETE SLAB
PAVERS, EG.
ABBOTSFORD NEW YORK SERIES
FULL AND HALF SIZES

DECORATIVE PAVING AT ENTRY:
PORCELAN SLAB PAVERS
TO MATCH LOBBY (SIZE,
PATTERN, COLOUR TBD), MORTARED
IN PLACE

DECORATIVE PAVING LEVEL ONE:
HYDRAPRESSED CONCRETE SLAB
PAVERS, EG.
ABBOTSFORD NEW YORK SERIES
FULL SIZE

B.E. CONCRETE
SEE ARCH. FOR FINISH DETAILS

COMPOSITE DECKING:
TREX 'ENHANCE'
COLOUR TBD

NOTE: INSTALL PER MANUFACTURER'S SPECIFICATIONS
AND ALIGNED AS SHOWN.


PROPOSED TREES



AMELANCHIER



PICIA GAUICA 'PENDULA'



CHAMAECYPARIS NOOTIC 'VAN DEN AXER'



LIQUIDAMBER S 'SLENDER SILHOUETTE'



ACER GRIEUM



PICIA OMORICA



ACER PALMATUM 'BLODDGODD'



ACER PALMATUM 'SERRA'



STYRAX JAPONICA



PINUS DENSIFORMIS 'UMBRAFLUEBA'



PINUS DENSIFORMIS 'UMBRAFLUEBA'



PINUS DENSIFORMIS 'UMBRAFLUEBA'



PINUS DENSIFORMIS 'UMBRAFLUEBA'

NO.	DATE	REVISION DESCRIPTION	DK
1	11.15.22	REVISED DRAWING	DK
2	11.15.22	REVISED DRAWING	DK
3	11.15.22	REVISED DRAWING	DK
4	11.15.22	REVISED DRAWING	DK
5	11.15.22	REVISED DRAWING	DK
6	11.15.22	REVISED DRAWING	DK
7	11.15.22	REVISED DRAWING	DK
8	11.15.22	REVISED DRAWING	DK
9	11.15.22	REVISED DRAWING	DK
10	11.15.22	REVISED DRAWING	DK

PROJECT:

WATER'S EDGE
11575 & 11587 238RD STREET
MAPLE RIDGE, BC

DRAWING TITLE:
**LANDSCAPE
DETAILS**


DATE: 14.10.22
SCALE: 1/8" = 1'-0"
DRAWN: [Name]
DESIGN: [Name]
CHECK: [Name]

DRAWING NUMBER:
L3
OF 3

PMO PROJECT NUMBER:
18-049

18049-2P

© Inspire Architecture Inc.
 ALL RIGHTS RESERVED
 THIS DRAWING IS THE PROPERTY OF INSPIRED ARCHITECTURE INC. NO PART OF THIS DRAWING IS TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF INSPIRED ARCHITECTURE INC.



NO.	DESCRIPTION	DATE	BY
1	ISSUED FOR PERMIT	01/15/18	AF
2	ISSUED FOR PERMIT	01/15/18	AF
3	ISSUED FOR PERMIT	01/15/18	AF
4	ISSUED FOR PERMIT	01/15/18	AF
5	ISSUED FOR PERMIT	01/15/18	AF
6	ISSUED FOR PERMIT	01/15/18	AF
7	ISSUED FOR PERMIT	01/15/18	AF
8	ISSUED FOR PERMIT	01/15/18	AF
9	ISSUED FOR PERMIT	01/15/18	AF
10	ISSUED FOR PERMIT	01/15/18	AF
11	ISSUED FOR PERMIT	01/15/18	AF
12	ISSUED FOR PERMIT	01/15/18	AF
13	ISSUED FOR PERMIT	01/15/18	AF
14	ISSUED FOR PERMIT	01/15/18	AF
15	ISSUED FOR PERMIT	01/15/18	AF
16	ISSUED FOR PERMIT	01/15/18	AF
17	ISSUED FOR PERMIT	01/15/18	AF
18	ISSUED FOR PERMIT	01/15/18	AF
19	ISSUED FOR PERMIT	01/15/18	AF
20	ISSUED FOR PERMIT	01/15/18	AF
21	ISSUED FOR PERMIT	01/15/18	AF
22	ISSUED FOR PERMIT	01/15/18	AF
23	ISSUED FOR PERMIT	01/15/18	AF
24	ISSUED FOR PERMIT	01/15/18	AF
25	ISSUED FOR PERMIT	01/15/18	AF
26	ISSUED FOR PERMIT	01/15/18	AF
27	ISSUED FOR PERMIT	01/15/18	AF
28	ISSUED FOR PERMIT	01/15/18	AF
29	ISSUED FOR PERMIT	01/15/18	AF
30	ISSUED FOR PERMIT	01/15/18	AF
31	ISSUED FOR PERMIT	01/15/18	AF
32	ISSUED FOR PERMIT	01/15/18	AF
33	ISSUED FOR PERMIT	01/15/18	AF
34	ISSUED FOR PERMIT	01/15/18	AF
35	ISSUED FOR PERMIT	01/15/18	AF
36	ISSUED FOR PERMIT	01/15/18	AF
37	ISSUED FOR PERMIT	01/15/18	AF
38	ISSUED FOR PERMIT	01/15/18	AF
39	ISSUED FOR PERMIT	01/15/18	AF
40	ISSUED FOR PERMIT	01/15/18	AF
41	ISSUED FOR PERMIT	01/15/18	AF
42	ISSUED FOR PERMIT	01/15/18	AF
43	ISSUED FOR PERMIT	01/15/18	AF
44	ISSUED FOR PERMIT	01/15/18	AF
45	ISSUED FOR PERMIT	01/15/18	AF
46	ISSUED FOR PERMIT	01/15/18	AF
47	ISSUED FOR PERMIT	01/15/18	AF
48	ISSUED FOR PERMIT	01/15/18	AF
49	ISSUED FOR PERMIT	01/15/18	AF
50	ISSUED FOR PERMIT	01/15/18	AF

PROJECT: 223rd STREET
 14575 & 11587 223rd ST, MAPLE RIDGE, BC
 DRAWING TITLE: 3D RENDERINGS

REISSUED FOR SECOND HEARING

PROJECT NO:	177180	PROJECT DATE:	MAY - 17, 2018	DRAWN BY:	MOD
SCALE:		DATE:	NOVEMBER	CHECKED BY:	AF
DRAWING NO:	A-0006	REVISION:		DATE:	
					6

Advisory Design Panel Comments:

The Advisory Design Panel (ADP) reviewed the form and character of the proposed development and the landscaping plans at a meeting held on January 16, 2019. After presentations by the project Architect and Landscape Architect, the ADP made the following resolution:

That the following concerns be addressed regarding File No. 2017-573-DP and digital versions of revised drawings & memo be submitted to Planning staff; and further that Planning staff forward this on to the Advisory Design Panel for comment:

General Comments:

Greater attention is needed from both the landscaping and architectural perspective in achieving the OCP Key Guideline Concepts of the Port Haney and Waterfront Area, for this high profile and iconic Port Haney site, adjacent to the historical village, the Fraser River and commuter transportation.

Landscape Comments:

Pedestrian environment, urban design and safety enhancements:

- Redesign the corner and River Road frontage to create a stepped accessible pedestrian feature that reduces the impact of the stepped retaining wall and allows for introduction of public art and seating complementary to the public area of the West Coast Express station.
- Explore a relaxation in the wall heights/planters restriction facing River Road to allow for at grade programming including lighting, public art, and seating; higher retaining walls in location may be supportable as a means of improving the pedestrian environment and CPTED concerns.
- A CPTED report would be desirable to ensure corner is suitably designed.
- Add locking gate at bottom of walkway and provide lighting, possibly motion sensor activated.
- Provide a curb bump out at the right-in to the parkade entry.
- Check width of sidewalk to eliminate pinch points.

Enhancing pedestrian environment, amenities and capitalize on views:

- Consider incorporating the one bedroom unit north of the interior amenity space into an outdoor amenity space and including programming for all age use.
- Design and program the roof top area.
- Provide a gate to the patio of the 2 bedroom unit on the West side.

Integrate the landscape design with stormwater management strategy consistent with the escarpment policy.

Architectural Comments:

River Road Street front and corner significance:

- Given the strategic location of this site, incorporate suitable elements for public art or similar features that help to achieve the Key Guideline Concepts of the Port Haney and Waterfront precinct.
- Place a public art piece fronting River Road that connects the location with the Fraser River, and history of the Port Haney area.

Form and Character enhancement and additional details:

- Be consistent in accent colours in all elevations.
- Provide more prominent building corner designs.
- Redesign blank walls at corners.

- Provide updated entry design i.e.: between trellis entry and butterfly roof.
- Ensure material shown on material board and on architectural plans are consistent.
- Provide a longitudinal section through building at the location of the detention tank including the retaining walls.
- Be consistent in projections of roofs and patios, including soffit widths.
- Remove roof pilasters that overhang the soffit.
- Be consistent in projections of roofs and patios, including soffit widths.
- Remove roof pilasters that overhang the soffit.
- Provide a longitudinal section through building at the location of the detention tank including the retaining walls.
-

Sustainability and related matters:

- Consider offering some adaptable units.
- Consider offering sustainable features in the building design and implementation.
- Consider providing Electrical Vehicle Charging stations.

The ADP concerns have been addressed and are reflected in the current plans. A detailed description of how these items were incorporated into the final design will be included in a future development permit report to Council.



mapleridge.ca

City of Maple Ridge

TO: His Worship Mayor Michael Morden
and Members of Council

FROM: Chief Administrative Officer

MEETING DATE: July 2, 2019

FILE NO: 2016-091-DVP

MEETING: C o W

SUBJECT: Development Variance Permit
14155 Marc Road

EXECUTIVE SUMMARY:

Development Variance Permit application (2016-091-VP) has been received in conjunction with a rezoning and subdivision application to create a single family urban development of 109 lots in the Silver Valley Area. The requested variance is to:

1. Vary retaining wall height from 1.2 metres to 12.3 metres.

A total of 5 over height retaining walls are proposed for this development, with different maximum heights of 5.2, 5.6, 6.5, 9.2, and 12.3 metres. These height variances will only pertain to a portion of the wall, as each wall tapers down at its edges in response to the grade. In all cases, the vertical length of the wall is softened by tiers and landscaping, thereby reducing the visual impact.

These walls are needed in order to realize the applicant's development plan and lot yield. This plan has been revised over time through an iterative process in response to community concerns. Given the resulting extent of these variance requests, it was felt that that Council should be given the opportunity to consider this variance request earlier in the rezoning and subdivision approval process. The usual process is to consider a variance application concurrently with final reading of a rezoning application. Should Council have concerns with the wall proposal and not support the variance, the proposed lot yield may be affected.

Council will be considering final reading for rezoning application 2016-091-RZ at a later date.

Council considered rezoning application 2016-091-RZ and granted first reading for Zone Amending Bylaw No. 7254-2016 on June 14, 2016. Council granted first and second reading for Official Community Plan Amending Bylaw No. 7416-2017 on January 16, 2018, and second reading for Zone Amending Bylaw No. 7254-2016 on January 16, 2018. This application was presented at Public Hearing on February 20, 2018, and Council granted third reading on February 27, 2018. The date for final approval of the rezoning application is to be determined.

RECOMMENDATION:

That the Corporate Officer be authorized to sign and seal 2016-091-DVP respecting property located at 14155 Marc Road.

DISCUSSION:

a) Background Context

Applicant: Morningstar Homes Ltd.

Legal Description: Lot: 3, Section: 32, Township: 12, Plan: LMP14126

OCP:
 Existing: ECO (Eco Clusters), Conservation, Rural Residential
 Proposed: Eco Clusters, Conservation

Zoning:
 Existing: A-2 (Upland Agricultural)
 Proposed: R-1 (Residential District), R-2 (Urban Residential District)

Surrounding Uses:

OCP:

North: Use: Vacant
 Zone: A-2 (Upland Agricultural)
 Designation: Rural Residential & Agricultural

South: Use: Single Family Residential
 Zone: R-1 (Residential District)
 Designation: Eco Clusters

East: Use: Single Family Residential
 Zone: RS-3 (One Family Rural Residential)
 Designation: Eco Clusters and Conservation

West: Use: Blaney Bog
 Zone: A-5 (Agriculture Only)
 Designation: Park within the ALR and Rural Residential

Existing Use of Property: Vacant
 Proposed Use of Property: Urban Residential
 Site Area: 30.079 Ha. (74.32 acres)
 Access: Marc Road
 Servicing requirement: Urban Standard

b) Project Description:

This development variance application is to support a rezoning and subdivision application for 109 single family houses in the Silver Valley Area. The site is characterized by complex topography, with steep slopes and watercourses.

Since first reading was granted, significant revisions have been made resulting in a more compact development site with less disturbance into pristine portions of the site. As a consequence of these revisions, however, significant lot grading of the development site is proposed, with retaining walls that significantly exceed the maximum permissible in the Zoning Bylaw.

The retaining walls will be to stabilize either cutting or filling into the natural grade. For this project, the cuts will be stabilized with a process of soil nails and shotcrete walls. A series of landscaped tiers will break up the height of each wall. The visual effect of this type of tiered wall will be a granite-like rock face with plantings.

The placement of fill in the natural grade will be stabilized through sierra walls, which are built using mesh blocks filled with rock. These walls are combined with growing medium to support plants. The visual effect of this type of wall is a steep green slope which can blend into the natural landscape.

c) Variance Analysis:

The Zoning Bylaw establishes general minimum and maximum regulations for single family development. A Development Variance Permit allows Council some flexibility in the approval process.

The requested variances and rationale for support are described below:

1. *Maple Ridge Zoning Bylaw No 3510 -1985, Part 4, Section 403, (8): To vary maximum retaining wall height from 1.2 metres (4 ft) to 12.3 metres (40.3 feet).*

This proposal has evolved with a number of concerns that have been raised, discussed and addressed. The areas that it touches on include the policies of the Official Community Plan, potential liability, seismic stability, public safety and the integration of public infrastructure. These are discussed as follows below:

Official Community Plan - Hillside Policies. Policies 5-21 and 5-22 are pertinent to this application, as follows:

5.21 Patterns of density should be encouraged to achieve a mosaic of development sensitive to the natural contours of the land, with retention of mid-slope forested areas and density increased towards upland flat or valley bottom areas, the natural crest of a hill should be respected and development should be set back sufficiently to maintain the slope of the crest and the vegetation along it. Denser forms of horizontal development should be permitted along hillsides only where they can be off-set by sufficiently large open areas and where building modules can be broken into smaller units and carefully sited.

It should be noted that roughly 80% of the site (24 hectares or 59 acres) will be dedicated as park, and these dedicated areas will be enhanced and retained in their natural state. This retention of conservation lands was accomplished by concentrating development in the southern portion of the site.

5-22 Landscape disturbance should be minimized by retaining trees and natural vegetation as much as possible and requiring replanting or enhanced planting as a condition for development; providing a minimum of cuts and fills and limiting their depths, minimizing terracing and earth grading, blending graded areas with natural slope, and minimizing the amount of exposed raw earth by phased development and on-site controls.

The extent of the cuts and fills on the site are restricted to the compact development site, occupying roughly 20% of the site. As noted, these are significant, reflecting the challenges of attaining sufficient density to enable the project. The tradeoff for the City is the environmental protection that can be achieved with this extensive regrading and filling. An estimated 80% of the site will be dedicated and preserved as parkland which will be accessible to the public through a proposed trails system. This trails system will be integrated with the Regional Parks network of Metro Vancouver, and the UBC Forest.

Official Community Plan – Visual Character

Policy 5-27 states the following:

The protection of views should be encouraged by sensitive site design that maximizes views beyond and between buildings on the site.

The visual impact of the landscape alterations will not be apparent at locations close to the development site, but there will likely be viewscape changes from a distance. As these walls will be decorative, planted and tiered, the combination of park dedication and planted walls will continue to appear as significant green space. The applicant has provided a rendering to demonstrate how the developed site will appear from a distance, included in Appendix D. Very few homes exist west of the site in Pitt Meadows or Blaney Bog that would be affected by this change.

Legal protection to ensure the walls are planted and maintained appropriately will be attained through a number of restrictive covenants and easements that will be required through the rezoning and subdivision process. These legal documents include: restrictive covenants (no-build) for retaining wall and GeoGrid Protection areas; easements to provide access to planting areas, and easements for retaining wall maintenance,

Potential Liability:

All of the retaining walls will be on private property and will not be the responsibility of the municipality for repair or maintenance. At the request of the Engineering Department and the Approving Officer, the applicants engaged a second engineering firm to peer review the design of the walls. A few recommendations were made and committed to with this peer review. The Maple Ridge Engineering Department has reviewed this work along with the peer review and is satisfied with this scope of work. These walls have been designed for seismic stability with a minimum lifespan of 70 years. A no disturb covenant will be placed on each lot to ensure these walls are not altered or removed by future homeowners.

Public Safety.

Protective fencing at the top of each lot's wall will provide fall protection for pedestrians although this area of the site does not contain pedestrian paths.

Integration of Infrastructure.

Storm and sewer have been located outside of the wall stabilization areas, thereby facilitating access to reduce the costs of repair and replacement of these utilities, if required in the future by the City.

d) Citizen/Customer Implications:

In accordance with the *Development Procedures Bylaw No. 5879-1999*, notice of Council consideration of a resolution to issue a Development Variance Permit was mailed to all owners or tenants in occupation of all parcels, any parts of which are adjacent to the property that is subject to the permit.

Although this development plan has also evolved through community input with the applicant making a clear effort to address the concerns of local residents, this application is the first public notice of the extent of the overheight walls.

e) Alternatives:

This application follows an unusual process in that this formal request for a variance occurs in advance of final reading or the release of the Preliminary Review letter that outlines subdivision requirements. The decision to bring this before Council at this time is due to the extent of the variance request, as it is integral to the proposed subdivision. At the staff level, there has been some reluctance and concern over the extent of the walls necessary to accommodate this proposal. It is, however a result of the clustering of development and the developer's desire to achieve a certain density and lot yield. However, this variance request is supportable based on the extent of dialogue and revisions the applicant has committed to in addressing concerns. If this application is denied, the applicant will need to revise the development plan in order to reduce the height of retaining walls. This application is timed to provide guidance to the Approving Officer and fairness to both Council to the applicant.

It should be noted that the second reading report included graphic examples of retaining walls, although specific heights were not included. At the time of second reading, Council would have had some understanding that retaining walls would be required in order for development to proceed.

Should the extent of this variance request exceed Council's comfort, Council may wish to use this opportunity to express a lesser measure and method such as the use of more backfilled slopes for some lots which would reduce the length and height of some proposed walls, that they would be willing to support through a variance request.

With this alternative, a second variance application would be required if Council denies this application. However, with this assurance of support from Council, the applications could be revised and proceed with the second variance request brought forward concurrently with final reading.

CONCLUSION:

The proposed variance is supported because the overall site plan is compact, maximizes the extent of park dedication, and has been revised to address municipal concerns. Although a number of concerns have been noted in the report, this application and this variance request is a reasonable compromise for a difficult site.

It is therefore recommended that this application be favourably considered and the Corporate Officer be authorized to sign and seal Development Variance Permit 2016-091-DVP.

"Original signed by Diana Hall"

Prepared by: **Diana Hall, M.A, MCIP, RPP
Planner 2**

"Original signed by Chuck Goddard"

Reviewed by: **Charles R. Goddard, BA, MA
Director of Planning**

"Original signed by David Pollock" for

Approved by: **Christine Carter, M.PL, MCIP, RPP
GM Planning & Development Services**

"Original signed by Kelly Swift"

Concurrence: **Kelly Swift, MBA
Acting Chief Administrative Officer**

The following appendices are attached hereto:


Appendix A – Subject Map

Appendix B – Ortho Map

Appendix C – Site Plan showing locations of over height walls

Appendix D – Information provided by applicant.

Appendix F – OCP Amending Map Showing extent of Conservation areas



SUBJECT PROPERTY



Scale: 1:4,500

Legend

-  Stream
-  Ditch Centreline
-  Edge of Marsh
-  Indefinite Creek
-  Lake or Reservoir
-  Marsh

14155 MARC ROAD
PID: 018-620-850

PLANNING DEPARTMENT



MAPLE RIDGE


British Columbia

mapleridge.ca


FILE: 2016-091-VP

DATE: Jun 4, 2019

BY: MC



Scale: 1:4,500




14155 MARC ROAD
PID: 018-620-850



FILE: 2016-091-VP
DATE: Jun 4, 2019

BY: MC



LEGEND

EX. WATER	— W —
EX. SANITARY SEWER	— S —
EX. STORM SEWER	— D —
PROP. WATER	— W —
PROP. SANITARY SEWER	— S —
PROP. STORM SEWER	— D —
PROP. SIDEWALK	— / / —
PROP. FIRE HYDRANT	⊙
PROP. CATCH BASIN	⊞
PROP. STREETLIGHT	⊙

Maximum wall height
5.2 m for lots 1-9

Maximum wall height
12.3 m for lots 10-28

Maximum wall height
6.5 m for lots 32-36

Maximum wall height
5.6 m for lots 72-79

Maximum wall height
9.2 m for lots 83-98

SEE GEOTECHNICAL REPORT (DATED JULY 18, 2018) FOR APPROXIMATE PEAT LOCATION. IF PEAT IS ENCOUNTERED, EXCAVATION IS REQUIRED. ALL EXCAVATION TO BE WITHIN DEVELOPMENT BOUNDARIES. NO ENCROACHMENT INTO SPEA WILL OCCUR.

CHECK BEFORE YOU DIG
INFORMATION ON EXISTING UTILITIES MAY NOT BE COMPLETE OR ACCURATE. PRIOR TO CONSTRUCTION CONTRACTOR SHALL VERIFY LOCATIONS OF ALL EXISTING UTILITIES AND ADVISE THE ENGINEER OF POTENTIAL CONFLICTS. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS FOR UTILITIES, SERVICE LOCATIONS, AND DETAILS. THE EXACT LOCATION OF THESE UTILITIES SHALL BE DETERMINED ON SITE.

REV'D	DATE(Y/M/D)	DR'N	CHK'D	DESCRIPTION
2	2019/04/03	BC	CN	REVISED PER CITY COMMENTS
1	2018/11/13	BC	CN	REVISED PER CITY COMMENTS
0	2018/05/18	BC	CN	FIRST SUBMISSION

CITY OF MAPLE RIDGE Engineering Department

BRIDLE RIDGE SUBDIVISION

KEY PLAN OVERALL

14155 MARC ROAD, MAPLE RIDGE, BC

DESIGNED — BC
DRAWN — BC
METRIC SCALE — 1:1000
APPROVED — CN
DATE — APR. 3, 2019

FILE # 5245-20-2016-091
CONSULTANTS DWG No- 1800
CITY DOC. No-
SHEET 2 OF 87



2nd Floor, 946 Brunette Avenue
Coquitlam, BC V3K 1C9
Head Office: 604-521-0038
Fax: 604-521-0078
www.mstarhomes.com

Diana Hall
11995 Haney Place
City of Maple Ridge

Re: 2016-091-RZ – Development Variance Permit Application – Retaining Wall Height

Diana,

Please find below our Development Variance Permit Application for over height retaining walls at our Marc Road development at 14155 Marc Road, Maple Ridge.

Requested Variances:

Maple Ridge Zoning Bylaw No. 3510-1985 Section 403 (8) *Maximum Retaining Wall Height:*

Rock-face soil nail wall with planted terraces:

- a. To vary the maximum height of the soil nail retaining wall in the rear yards of Lots 10 – 28 from 1.2m up to a minimum of 3.1m to a maximum of 12.3m. This retaining wall will consist of up to 4 individual tiers with maximum tier heights of 4.4m. Each tier is spaced from the next with a planted 1.5m terrace.
- b. To vary the maximum height of the soil nail retaining wall in the rear yards of Lots 72 - 79 from 1.2m up to a minimum of 1.2m to a maximum of 5.6m. This retaining wall will consist of up to 2.5 individual tiers with maximum tier heights of 3.0m. Each tier is spaced from the next with a planted 1.5m terrace.

Vegetated-face sierra slope wall with hill slope features:

- a. To vary the maximum height of the vegetated hill slope retaining wall in the rear yards of Lots 1-9 from 1.2m up to a maximum of 5.2m.
- b. To vary the maximum height of the vegetated hill slope retaining wall in the rear yards of Lots 32-36 from 1.2m up to a maximum of 6.5m.
- c. To vary the maximum height of the vegetated hill slope retaining wall in the rear yards of Lots 83-98 from 1.2m up to a maximum of 9.2m.

Justification for over height walls:

In response to strong public and political feedback against the proposed secondary access point into the site through Anderson Creek Drive that was eventually removed, over height retaining walls were required to create a feasible lot layout as road grade and lot grading requirements posed further restraints.

With thorough feedback from municipal staff and design consultants on the aesthetics and functionality of these retaining walls, two types of walls have been designed and supported: Rock-scape terraced and planted soil nail walls, and vegetated-face hill slope sierra walls. As requested by City Staff, the geotechnical design drawings have been peer-reviewed and supported by GeoWest Consultants. Also, both walls feature native plants that require little to no maintenance, and add an aesthetic and naturalized look to the neighbourhood.

Furthermore, as a developer and builder, we can use the wall systems to comprehensively grade the site to create recommended features outlined in the Silver Valley Area Plan:

- 82 of 109 homes facing significant natural features (Parkland, Forests, Blaney Bog)
- Traffic calming cul-de-sacs with naturalized features
- Pockets of nature throughout the neighbourhood,
- Playground/park area in a central location for the neighbourhood; and
- Useable, functional back yards with incredible westward views of the Blaney Bog

At Morningstar we use in-depth questionnaires that are sent to each new homeowner to find out what they liked best and what we could have done to make their home better. We've done this for all 2,000+ homes we have built and sold in the last 21 years. These questionnaires offer incredible insight to what home owners want when they purchase a new home.

One of the most common comments that we receive is how much people love their functional back yards. As a developer who builds on our own lots, we do not try to create the cheapest lots possible. Over height retaining walls are expensive but on the Marc Road site they will allow Morningstar the opportunity to offer a useable and functional rear yard to as many homes as possible, while creating an eco-cluster inspired neighbourhood with many features outlined in the Silver Valley Neighbourhood Plan.

The images shown below of these typical walls have been shared at development information meetings, neighbourhood meetings, with councillors, city staff and home buyers, resulting in favourable responses prompting our application.


Vegetated-Face Hillslope Sierra Wall



Rock-scape Terraced and Planted Soil Nail Walls







MAPLE RIDGE OFFICIAL COMMUNITY PLAN AMENDING

Bylaw No. 7416-2017
 Map No. 969
 Purpose: To Amend Silver Valley Area Plan Figure 2
 From: Eco Cluster and Conservation

To:  Conservation  Eco Cluster  Neighbourhood Park



--- Urban Area Boundary



SCALE 1:5,000

TO: His Worship Mayor Michael Morden
and Members of Council
FROM: Chief Administrative Officer
MEETING DATE: July 2, 2019
FILE NO: 2018-089-DVP
MEETING: C o W
SUBJECT: Development Variance Permit
14310 256 Street

EXECUTIVE SUMMARY:

Development Variance Permit application 2018-089-VP has been received in conjunction with a application to subdivide the property located at 14310 256 Street in two industrial lots under the current M-2 (General Industrial) zone. The existing services and utilities within 256 Street are sufficient as-is. The requested variance is to omit the requirement to upgrade services and utilities on 256 Street.

It is recommended that Development Variance Permit 2018-089-DVP be approved.

RECOMMENDATION:

That the Corporate Officer be authorized to sign and seal 2018-089-DVP respecting property located at 14310 256 Street.

DISCUSSION:

a) Background Context

Applicant: OTG Developments
Owner: AA-Class Auto Holding Ltd & Nagin Enterprises Inc

Legal Description: Lot 6, District Lot 5326, New Westminster District Plan LMP41830

OCP :
Existing: IND (Industrial)
Proposed: Industrial

Zoning:
Existing: M-2 (General Industrial)
Proposed: M-2 (General Industrial)

Surrounding Uses:
North: Use: Vacant Industrial
Zone: M-2 (General Industrial)
Designation: Industrial
South: Use: Industrial
Zone: M-2 (General Industrial)
Designation: Industrial

East:	Use:	Vacant Industrial
	Zone:	M-2 (General Industrial)
	Designation:	Industrial
West:	Use:	Industrial
	Zone:	M-2 (General Industrial)
	Designation:	Industrial

Existing Use of Property:	Industrial
Proposed Use of Property:	Industrial
Access:	256 Street
Servicing:	Rural
Lot Size:	1.07 ha (2.5 acre)
Concurrent Applications:	2018-089-SD and 2018-089-WP/NFDP

b) Project Description:

The subject property is approximately 2.5 acres in size (see Appendix A) and is located north of 142 Ave and 256 Street, close to the city boundary in the Allco area. The subject property is bound by industrial lots to the south and west, and a large vacant lot stretching north and east. A watercourse, identified as Mud Creek, is on the vacant lot, with a significant sloped ridge west of the creek, extending onto the subject property.

c) Variance Analysis:

The Zoning Bylaw establishes general minimum and maximum regulations for development. A Development Variance Permit allows Council some flexibility in the approval process.

The requested variances and rationale for support are described below (see Appendices B and C):

1. *Subdivision and Development Services Bylaw No. 4800-1993, Schedule A – Services and Utilities:* To omit the requirement to upgrade/construct services and utilities on 256 Street.

Existing services and utilities on 256 Street are sufficient as-is, and no upgrades as described in aforementioned Schedule A, are required. Therefore the variance can be supported. The existing roadside gravel road shoulder horse trail is noted to be maintained as a requirement of subdivision.

In accordance with the *Development Procedures Bylaw No. 5879-1999*, notice of Council consideration of a resolution to issue a Development Variance Permit was mailed to all owners or tenants in occupation of all parcels, any parts of which are adjacent to the property that is subject to the permit.

CONCLUSION:

As existing services and utilities on 256 Street are sufficient as-is, the variance request to omit required upgrades is supportable. It is recommended that this application be favourably considered and the Corporate Officer be authorized to sign and seal Development Variance Permit 2018-089-DVP.

"Original signed by Therese Melser"

Prepared by: **Therese Melser**
Planning Technician

"Original signed by Chuck Goddard"

Reviewed by: **Charles R. Goddard, BA, MA**
Director of Planning

"Original signed by Christine Carter"

Approved by: **Christine Carter, M.PL, MCIP, RPP**
GM Planning and Development

"Original signed by Kelly Swift"

Concurrence: **Kelly Swift, MBA**
Acting Chief Administrative Officer

The following appendices are attached hereto:

Appendix A – Subject Map

Appendix B – Ortho Map



Scale: 1:2,500

Legend

-  Stream
-  Ditch Centreline
-  Edge of Marsh
-  Indefinite Creek
-  Lake or Reservoir
-  Marsh

14310 256 STREET


PLANNING DEPARTMENT




mapleridge.ca

FILE: 2018-089-VP
DATE: Mar 23, 2018

BY: PC



Scale: 1:2,500



14310 256 STREET

PLANNING DEPARTMENT



mapleridge.ca

FILE: 2018-089-VP
DATE: Mar 23, 2018

BY: PC



mapleridge.ca

City of Maple Ridge

TO: His Worship Mayor Michael Morden
and Members of Council
FROM: Chief Administrative Officer

MEETING DATE: July 2, 2019
FILE NO: 2019-210-DVP
MEETING: C o W

**SUBJECT: Development Variance Permit
22768 & 22772 119 Avenue**

EXECUTIVE SUMMARY:

Development Variance Permit application (2019-210-DVP) has been received for a parking reduction for a development proposal on the subject property noted above. A previous development permit for Town Centre Commercial and a development variance permit were approved by Council on March 18, 2018 to permit the construction of a mixed use building combining 1858m² (20,000 ft²) of office space and 94 below market rental housing units. The proposal is being advanced by a non-profit organization (Maple Ridge Pitt Meadows Community Services Council) who will be operating in partnership with BC Housing to provide affordable rental housing to low income individuals and families. The previous variance request included a reduction of 13 stalls. This request for a parking reduction is for 1 less stall, amounting to a total request between the two applications for a variance of 14 parking stalls. This parking reduction is supported by a parking reduction study, prepared by a qualified professional.

The requested variance is to:

- 1. Vary required parking from 126 stalls to 112 stalls.

It is recommended that Development Variance Permit 2019-210-DVP be approved.

RECOMMENDATION:

That the Corporate Officer be authorized to sign and seal 2019-210-DVP respecting property located at 22768 & 22772 119th Avenue.

DISCUSSION:

a) Background Context

Applicant:	Bissky Architecture And Urban Design Inc.
Legal Description:	Lot: B, D.L.: 401, Block: 3, Plan: NWP21553 & Lot: B, D.L.: 401, Block: 3, Plan: NWP21553
OCP :	
Existing:	TCCOMM (Town Centre Commercial)
Proposed:	TCCOMM (Town Centre Commercial)
Zoning:	
Existing:	C-3 (Town Centre Commercial)
Proposed:	C-3 (Town Centre Commercial)

Surrounding Uses:

North:	Use:	Vacant
	Zone:	CS-1 Service Commercial
	Designation:	Low Rise Apartment
South:	Use:	Shopping Mall
	Zone:	C-3 Town Centre Commercial
	Designation:	Town Centre Commercial
East:	Use:	Vacant
	Zone:	RM-6 Highrise Apartment
	Designation:	Medium High Apartment
West:	Use:	Bowling Alley
	Zone:	C-3 Town Centre Commercial
	Designation:	Town Centre Commercial

Existing Use of Property:	Office Building
Proposed Use of Property:	Mixed Use office and non-market housing
Site Area:	2750 m ²
Access:	228 th Street
Servicing:	Urban Standard

b) Project Description:

This parking reduction request follows a previous Development Permit application (2017-385-DP) and Development Variance Permit application (2017-385-DVP) that were both approved previously by Council. This additional request is the further reduction of 1 parking stall.

This development proposal includes a mixed use development comprising approximately 1858 m² (20,000 square feet) of office and program space for Maple Ridge/Pitt Meadows Community Services (MRPMCS) on the first two storeys of the building. A portion of the second storey will also accommodate below market rental housing, for a total of 94 affordable residential units between the second and the sixth storeys. These housing units will conform to BC Housing design requirements varying from studio to 3 bedroom apartments and will include accessible units.

Parking is located mostly underground with some on grade at the south lane and along the west side. Main entries to the various functions occur along the north facade on 119th, although some staff and secondary entries have been designed along the south side of the building. A 2 storey high central lobby is the main focal point for MRPMCS, providing control and a sense of community for the entire building. The residential entry is adjacent. Amenity spaces are provided, including a tenant area and an outdoor deck on the second floor. A secure outdoor play area for children has been provided on grade at the south side as well.

c) Variance Analysis:

The Zoning Bylaw establishes general minimum and maximum regulations for single family development. A Development Variance Permit allows Council some flexibility in the approval process.

The requested variances and rationale for support are described below:
Maple Ridge Off Street Parking and Loading Bylaw No 4350 -1990, (Part 10, Section 10.2): To reduce required parking for multi-family non-market from a total required 88 stalls to 74 stalls (residential use).

The combined residential and commercial parking variance requests amounts to a total variance of 14 stalls. This parking reduction has been supported by a parking reduction study prepared by Creative Transportation Solutions Limited. Their findings included the following:

1. Parking supply exceeds parking demand for apartment dwellings in Maple Ridge
2. Parking demand for renters is lower than for owners.
3. Households near the Frequent Transit Network have fewer vehicles.

This report concludes that the parking demand proposed by this building will likely be 56 stalls, and for this reason, the 74 provided for residential use will be an oversupply of 19 stalls. On this basis, the parking reduction is supportable.

d) Citizen/Customer Implications:

In accordance with the *Development Procedures Bylaw No. 5879-1999*, notice of Council consideration of a resolution to issue a Development Variance Permit was mailed to all owners or tenants in occupation of all parcels, any parts of which are adjacent to the property that is subject to the permit.

CONCLUSION:

The proposed variance is supported because the parking reduction has been justified by a parking reduction study.

It is therefore recommended that this application be favourably considered and the Corporate Officer be authorized to sign and seal Development Variance Permit 2019-210-DVP.

"Original signed by Diana Hall"

**Prepared by: Diana Hall M.PL, MCIP, RPP
Planner 2**

"Original signed by Chuck Goddard"

**Reviewed by: Charles R. Goddard, BA, MA
Director of Planning**

"Original signed by Christine Carter"

**Approved by: Christine Carter, M.PL, MCIP, RPP
GM Planning & Development Services**



"Original signed by Kelly Swift"

**Concurrence: Kelly Swift, MBA
Acting Chief Administrative Officer**

The following appendices are attached hereto:

- Appendix A – Subject Map
- Appendix B – Ortho Map
- Appendix C – Site Plan

APPENDIX A



22768/72 119 AVENUE
PID: 016-029-500

PLANNING DEPARTMENT




mapleridge.ca



Aerial Imagery from the Spring of 2018



Scale: 1:2,500



District of Mission

22768/72 119 AVENUE
PID: 016-029-500

PLANNING DEPARTMENT



mapleridge.ca

2019-210-VP
DATE: Jun 11, 2019

BY: MC

TO: His Worship Mayor Michael Morden
and Members of Council
FROM: Chief Administrative Officer
SUBJECT: Award of Contract ITT-EN19-35: Dewdney Trunk Road Watermain Replacement (Edge Street to 228 Street)

MEETING DATE: July 2, 2019
FILE NO: 11-5255-70-136
MEETING: COW

EXECUTIVE SUMMARY:

The existing watermains along Dewdney Trunk Road (DTR) from Edge Street to 228 Street and on 227 Street 200m north of DTR were installed in the 1970's and have been identified for replacement as part of the City's Annual Watermain Replacement Program. Similar to the successfully completed 2018 watermain project on 232 Street (DTR to 121 Avenue), the City is planning to expand the fibre optic network by installing ducts in the abandoned watermains as part of this work. This project is included in the 2019 Financial Plan.

The Dewdney Trunk Road Watermain Replacement Project from Edge Street to 228 Street consists of the installation of approximately 745m of ductile iron watermain, varying in size from 150mm to 300mm diameter, water service connection transfers, installation of new fire hydrants and pavement surface restoration. There is optional IT work included in the tender to utilize the abandoned watermain for fibre optic ducts, including the installation of junction boxes and pulling three 32mm ducts through the existing watermain. City crews will complete tie-ins of the new watermain to the City water system.

The Invitation to Tender was issued on May 24, 2019 and closed on June 20, 2019 with five (5) bids received. The lowest compliant tender price was submitted by Pedre Contractors Ltd. of \$1,121,237 excluding taxes. The watermain installation is funded from the Water Utility Fund, and additional funding is required for the water tie-ins to the City system and to cover contract costs that are over budget. Funding to install ducting for future fibre optic expansion is coming from the IT Fibre Optic Network project budget.

Council approval to award the contract is required for the work to proceed.

RECOMMENDATION:

That Contract ITT-EN19-35: Dewdney Trunk Road Watermain Replacement (Edge Street to 228 Street), be awarded to Pedre Contractors Ltd. in the amount of \$1,121,237 excluding taxes; and

That a construction contingency of \$112,124 be approved to address potential variations in field conditions; and

That the next Financial Plan Bylaw be amended to increase the project funding by \$220,361.00 from the Water Utility Fund; and further

That the Corporate Officer be authorized to execute the contract.

DISCUSSION:

a) Background Context:

The existing watermain along Dewdney Trunk Road (DTR) from Edge Street to 228 Street and on 227 Street 200m north of DTR were installed in the 1970's and have been identified for replacement as part of the City's Annual Watermain Replacement Program. Similar to the successfully completed 2018 watermain project on 232 Street (DTR to 121 Avenue), the City is planning to expand the fibre optic network by installing ducts in the abandoned watermain as part of this work. This project is included in the 2019 Financial Plan.

The Dewdney Trunk Road Watermain Replacement Project from Edge Street to 228 Street consists of the installation of approximately 745m of ductile iron watermain, varying in size from 150mm to 300mm diameter, water service connection transfers, installation of new fire hydrants and pavement surface restoration. There is optional IT work included in the tender to utilize the abandoned watermain for fibre optic ducts, including the installation of junction boxes and pulling three 32mm ducts through the existing watermain. City crews will complete tie-ins of the new watermain to the City water system.

Tender Evaluation

The Invitation to Tender was issued on May 24, 2019 and closed on June 20, 2019 with five (5) bids received, listed below from lowest to highest price.

	<u>Tender Price</u> <u>(excluding taxes)</u>
Pedre Contractors Ltd.	\$1,121,237
Sandpiper Contracting LLP	\$1,127,558
Complete Utility Contracting Ltd.	\$1,161,680
Richco Contracting Ltd.	\$1,345,258
J. Cote & Son Excavating Ltd.	\$1,510,000

The lowest compliant bid was \$1,121,237 (excluding taxes) from Pedre Contractors Ltd. McElhanney Consulting Services Ltd, the City's consultant, has evaluated the bids and completed satisfactory reference checks and recommends the contract be awarded to Pedre Contractors Ltd.

b) Desired Outcome:

To provide reliable fire protection and high quality drinking water to Maple Ridge residents.

c) Strategic Alignment:

One of the key strategies in the Corporate Strategic Plan is to manage existing infrastructure. Replacement and upgrading of the aging watermain and fire hydrants on Dewdney Trunk Road will ensure reliability of service and provide capacity for future years.

Installation of ducts in the abandoned watermain will support the City's long-term plan to extend fibre optic network and service throughout the City.

d) Citizen/Customer Implications:

The estimated construction duration is approximately eight weeks starting in mid-July 2019. It is anticipated that traffic lanes through the work zone will be reduced during construction by shifting to the south. Most of the watermain replacement works are proposed for the north side of the road adjacent to the sidewalk. Some of the fronting properties may be impacted during water service connection installations, and residents will be notified in advance of the work.

Every effort will be made to minimize the impact to residents and businesses fronting the watermain installation on Dewdney Trunk Road. As well, the general public will be informed of the traffic alerts and construction progress through the City's website and social media sources.

e) Interdepartmental Implications:

The Operations Department has provided input during the design stage. The Information Technology Department has worked closely with Engineering to utilize the abandoned watermain as fibre optic ducting for future use. Tie-ins to the live water system will be completed by the Operations Department. A City staff inspector will provide inspection services during construction.

f) Business Plan/Financial Implications:

The projected expenditures excluding taxes are as follows:

Consulting	\$ 92,000
Water Tie-ins (Operations)	185,000
Construction Contract (Pedre Contractors Ltd.)	1,121,237
Contract Contingency	112,124
Total Projected Project Cost	\$ 1,510,361

The project funding sources are as follows:


Water Capital Fund (WCF) (LTC No. 18018.1)	\$ 1,025,000
Operations Watermain Replacement (LTC No. 002190)	200,000
IT Department Fibre Optics (LTC No. 017093)	65,000
Additional funding from WCF required	220,361
Total Funding Sources	\$ 1,510,361

The project expenditures include a contract contingency of \$112,124 that will only be utilized if required to address potential variations in field conditions.


CONCLUSIONS:

The tender price of \$1,121,237(excluding taxes) by Pedre Contractors Ltd. for the Dewdney Trunk Road Watermain Replacement Project from Edge Street to 228 Street is the lowest compliant tender.

It is recommended that Council approve the award of the contract to Pedre Contractors Ltd. and a contract contingency of \$112,124 be approved. It is also recommended that funds be transferred from the Water Utility Fund to LTC No. 18018.1.




Prepared by: Maria Guerra, PEng., PMP
Acting Manager of Design & Construction




Financial: Trevor Thompson, BBA, CPA, CGA
Concurrence: Chief Financial Officer



Reviewed by: Jeff Boehmer, PEng.
Acting Municipal Engineer




Approved by: David Pollock, PEng.
General Manager Engineering Services




Concurrence: Kelly Swift, MBA
Acting Chief Administrative Officer

Attachments:
(A) Map



-  PROPOSED WATERMAIN REPLACEMENT
-  PROPOSED FIBRE OPTIC DUCT INSTALLATION



SCALE:
N.T.S.



CITY OF MAPLE RIDGE
ENGINEERING
DEPARTMENT

DEWDNEY TRUNK ROAD WATERMAIN REPLACEMENT
EDGE STREET – 228 STREET
ITT-EN19-35

DATE: JUNE 2019

FILE/DWG No SK0421

TO: His Worship Mayor Michael Morden
and Members of Council
MEETING DATE: July 2, 2019
FROM: Chief Administrative Officer
FILE NO:
MEETING: CoW
SUBJECT: 2019 Community Grant

EXECUTIVE SUMMARY:

The City has received an application for a Community Grant in the amount of \$5,000 from the Jamia Riyadhul Jannah British Columbia Foundation (the Foundation). The grant will be used to complete necessary renovations at the heritage property the Foundation is using as a mosque.

This project is eligible for support under Council's Community Grant policy. Supporting this request will leave \$40,000 available for any additional applications that may be received this year.

RECOMMENDATION:

That a Community Grant of \$5,000 be awarded to the Jamia Riyadhul Jannah British Columbia Foundation

DISCUSSION:

a) Background Context:

The Jamia Riyadhul Jannah British Columbia Foundation (the Foundation) purchased a heritage property in Maple Ridge in late 2018 and began using it as a mosque at the beginning of 2019. This is the first community mosque in the City, and offers the local Muslim Community a place of worship.

While we understand BC Assessment will be classifying the property as a place of worship starting with the 2020 property tax year, it was not eligible to be classed as such for 2019, meaning that the property was not eligible for either a statutory or a permissive property tax exemption for the current year. Consequently, the Foundation received a property tax bill for 2019 and there are no legislative avenues available to waive or reduce the amount levied. As a result, the Foundation is faced with having to defer necessary renovations to the building and has asked that Council consider awarding them a Community Grant to allow this work to proceed at this time. This request for one-time funding is aligned with Council's Community Grant Policy.

b) Desired Outcome:

To support the Foundation with necessary renovations to the heritage building they are using as a place of worship.

c) Business Plan/Financial Implications:

The requested funding can be provided within the 2019 budget envelope, leaving \$40,000 available for any additional applications that may be received this year.

d) Alternatives:


Council could chose not to support the request for funding. That would result in the Foundation deferring necessary renovations to the heritage building they are using as a place of worship.

CONCLUSIONS:

The request for funding received from the Foundation is aligned with Council's Community Grant Policy and staff is recommending the request be supported.



Prepared by: Catherine Nolan, CPA, CGA
Corporate Controller



Concurrence: Kelly Swift, MBA
Acting Chief Administrative Officer



mapleridge.ca

City of Maple Ridge

TO: His Worship Mayor Michael Morden
and Members of Council

FROM: Chief Administrative Officer

SUBJECT: Maple Ridge Pitt Meadows Arts Council Proposed Bylaw Amendments

MEETING DATE: July 2, 2019

FILE NO: 2221641

MEETING: CoW

EXECUTIVE SUMMARY:

The Maple Ridge and Pitt Meadows Arts Council Society (MRPMAC) operates the ACT Arts Centre on behalf of the City through an operating agreement. Section 9, Schedule F of the operating agreement requires the MRPMAC to provide advance notice of any constitution or bylaw changes to Council before bringing this forward to their membership.

The MRPMAC Board of Directors is proposing a change to the Society's Constitution and Bylaws to comply with the BC Societies Act, provide further clarity and manage minor housekeeping items. Staff have reviewed the proposed changes and found that they are consistent with the City's terms and conditions in the operating agreement.

RECOMMENDATION:

That the changes to the proposed Maple Ridge and Pitt Meadows Arts Council Society's bylaw referenced in City of Maple Ridge report dated July 2, 2019 be endorsed.

DISCUSSION:

a) Background Context:

The MRPMAC operates the ACT Arts Centre and holds a lease and operating agreement with the City. The MRPMAC Board of Directors conducted a review of their constitution and bylaws to ensure compliance with requirements of the BC Societies Act, provide further clarification to clauses, and to clean up the existing document. The updated Society's Constitution and Bylaws has been reviewed by their legal attorney, Martha Rans and her recommendations have been included in the proposed version. Ms. Rans specializes in the legal needs of non-profits, charities, and digital creatives and has an extensive knowledge of the BC Societies Act. The changes are consistent with the terms and conditions of the operating agreement.

Articles of note include moving previous bylaw/constitution clauses to governance policies such as clauses relating to staff, revenue and expenditure and the election of officers and directors (attached for reference). Ms. Rans provided these recommended changes based on best practices to allow the Board to make regular and timely updates.

A number of articles were amalgamated under the Article 1 – Membership including employees of the society may become non-voting members which was formerly contained in Article 8 – Staff and from Article 9 – Meetings.

Lastly, a number of housekeeping items were addressed including formatting to the document alignment with the BC Societies Act regarding the appointment of replacement Board Members and notification periods.

b) Desired Outcome:

The desired outcome is to ensure that Council is kept informed regarding any constitution and/or bylaw changes, and that the proposed changes meet the terms and conditions set out in the Operating Agreement with the Society.

c) Strategic Alignment:

In the Parks, Recreation & Culture Master Plan (2010) one of the values is a collaborative community which supports independence by citizens and community groups in the provision of Parks, Recreation and Cultural services for the community, utilizing the community development approach as a guideline.

d) Citizen/Customer Implications:

The Arts Council's proposed amendments follow best practices and will not affect resident and visitor access to their services and programs.


e) Business Plan/Financial Implications:

There are no financial implications from these amendments.


CONCLUSION:

The Maple Ridge and Pitt Meadows Arts Council will make some changes to their constitution and bylaws to clarify, reformat sections with numbering and amend some of the clauses. A revised copy of their Society's Constitution and Bylaws will be filed with the City once the changes are approved at their upcoming Annual General Meeting in October.


Prepared by: **Yvonne Chui**
Arts & Community Connections Manager


Reviewed by: **Danielle Pope**
Director of Recreation & Community Engagement


Approved by: **David Boag**
Acting General Manager Parks, Recreation & Culture


Concurrence: **Kelly Swift MBA**
Acting Chief Administrative Officer

Attachments:
(A) Arts Council Societies Act Constitution and Bylaws

**‘SOCIETIES ACT’ CONSTITUTION AND BY-LAWS
OF
MAPLE RIDGE AND PITT MEADOWS ARTS COUNCIL
(Article 1 = name of Society)**

ARTICLE 2 - PURPOSES

The purpose of this Society shall be to increase and broaden the opportunities for citizens to enjoy and to participate in cultural activities, and shall include the following activities:

1. To provide for the coordination and provision of visual, literary and performing arts opportunities for the benefit of residents of the region.
2. To stimulate and encourage the development of cultural projects and activities.
3. To render service to all participating groups.
4. To act as a clearinghouse for information on cultural projects and activities.
5. To foster interest and pride in the cultural heritage of this community.
6. To enlist public interest and promote public understanding of cultural groups to the community.
7. To bring to the attention of civic, provincial and federal authorities the cultural needs of this community.
8. To provide scholarships to students pursuing education in the arts to students in the School District 42 catchment area.

MAPLE RIDGE PITT MEADOWS ARTS COUNCIL

SCHEDULE A

BYLAWS (including proposed amendments 2019)

ARTICLE 1 – MEMBERSHIP

1.1 There are two classes of members voting and non-voting. Regular voting members are:

- a) A person, subscribing to the objects of the Society and engaged in or interested in cultural activities may apply to the directors for membership in the Society and on acceptance by the directors and on payment of the annual dues set forth, shall be a member.
- b) A group or business may apply for membership. Upon acceptance by the Board they must appoint a designated representative to attend and vote at general meetings.

1.2 Employees of the society may become non-voting members of the Society.

1.3 All members are in good standing except a member who has failed to pay the current annual membership fees or any other subscription or debt due and owing by the member to the Society and the member is not in good standing so long as the debt remains unpaid.

1.4 A person shall cease to be a member of the Society:

- a) by delivering their resignation in writing to the secretary of the Society or by mailing or delivering it to the address of the Society, or
- b) on their death or in the case of a group, business, society or corporation on dissolution, or
- c) by being expelled, or
- d) by failing to pay the annual membership fees

1.5 A member may be expelled by a special resolution of the members passed at a general meeting or by a majority vote of the Board of Directors.

1.6 Every member shall uphold the constitution and comply with these by-laws and all Society policies.

1.7 Annual membership fees in the Maple Ridge Pitt Meadows Arts Council shall be determined from time to time by the Board of Directors.

1.8 Meeting of Members

- a) The Annual General Meeting of the Society shall be held within 120 days from the fiscal year end upon a date and at a time set by the Directors.
- b) Special General Meetings may be called by the Board of Directors at any time.
- c) At least fourteen days regular or electronic written notice of all Annual and General Meetings of the Council shall be given the members, specifying the time and place of such meeting.
- d) At all General Meetings of the Society each individual member in good standing who is personally present, shall be entitled to one vote and a group or business member may appoint a representative to vote on their behalf. A member in good standing is one who has paid their membership dues and been ratified by the Board.

- e) No business shall be transacted at any Annual or Special General Meeting unless a quorum consisting of 15 (fifteen) members in good standing shall be present.
- f) If 10% of the members of the society in good standing request the calling of a Special General Meeting in writing, specifying therein the object for which such a meeting is called, the Board of Directors must call the Special Meeting in accordance with the *Societies Act*.
- g) Accidental omission to give notice to, or the non-receipt of notice by, any of the members entitled to receive notice, does not invalidate proceedings at the meeting.

ARTICLE 2 – DIRECTORS

2.1 There shall be a maximum of thirteen elected Directors of the Society including Past President.

ARTICLE 3 – ELECTION OF OFFICERS AND DIRECTORS

3.1 A nominating Committee comprised of a minimum of three members of the society, the Chair of which shall be a member of the Board of Directors, shall be appointed by the Board a minimum of one hundred and twenty days prior to each Annual General Meeting and such Nominating Committee shall present the nominations for Directors to the membership for election at the Annual General Meeting. The Nominating Committee may submit a report of recommendations of Directors to be elected.

3.2 No salaried employee, nor any member of the family of such employee of the Society shall be eligible to election as Director for the duration of such employee's employment with the Society, nor for a period of two years thereafter, nor shall any member of the family of a Director become eligible to be elected a Director during the term of office of such Director.

3.3 For the purposes of the foregoing, "family member" shall be defined as: father, mother, siblings, children, husband, wife, common law partner, same sex partner, grandparents, grandchildren, stepparents, stepchildren, stepbrothers or sisters or step grandparents or step grandchildren.

3.4 Subject to the foregoing, the Directors of the Society shall be elected from and by the membership of the Society at the Annual General Meeting. The Directors of the Society shall each be elected for a three-year term. The three-year terms shall be staggered so that each year four directors are elected. At each succeeding Annual General Meeting, four directors shall be elected for a three-year term. Whenever a Director's position has been vacated midterm it will be specified upon election of a new Director what length of term is being filled.

3.5 The maximum term served by any Director of the Society shall normally be six consecutive years except that the President may remain on the Board for seven years.

3.6 The Directors shall elect from among their number the Executive Committee each year immediately following the Annual General Meeting by a majority vote. The Executive Committee of the Society shall be: Past President, President, Vice President, Secretary, and Treasurer.

ARTICLE 4 – REPLACEMENT AND REMOVAL OF DIRECTORS

4.1 Director vacancies may be filled from the membership by the Directors as needed. The length of time served, whether as an appointee or as an elected Director serving out the remainder of a vacant Director's term, will not count towards the six consecutive year limit.

4.2 The Society may by special resolution remove any director before the expiration of their period of office and may by ordinary resolution appoint another member of the Society in his place in the manner set out in the Societies Act.

ARTICLE 8 – AUDITORS

8.1 The accounts of the Society shall be examined by an independent accountant, and that accountant will prepare an annual financial statement in the form of an audited financial report to be presented to the membership at the Annual General Meeting.

ARTICLE 9– INSPECTION

9.1 The official records of the Society pursuant to s. 20(1) of the *Act* will be open to the inspection of the Members. Members, and other persons, do not have the right to inspect or seek the disclosure of any other official record of the Society, including the Director’s meeting minutes and accounting records, without the Board’s approval and at their sole discretion. The Board of the Society will establish procedures for the inspection and disclosure of any official records.

ARTICLE 10 – AMENDMENTS

10.1 This Constitution may be added to, altered or amended by a two-thirds majority of the members present at any Annual or General Meeting of the Society, provided that notice of such addition, alteration or amendment shall have been delivered to the members 14 days in advance of the meeting.

ARTICLE 11 – NOTICE

11.1 A notice may be given to a Member or a Director either personally, by delivery, courier or by mail posted to such person’s Registered Address, or, where a Member or Director has provided a fax number or e-mail address, by fax or e-mail, respectively.

ARTICLE 12 – MUNICIPAL LIAISONS

12.1 Liaisons from community and civic organizations are received from time to time as deemed appropriate by the Board of Directors and/or as outlined in agreements. All liaisons shall be non-voting members of the Board and shall not attend in camera meetings of the Board.

ARTICLE 13 – DISSOLUTION

13.1 That upon winding up or dissolution of the Society, the assets which remain after payment of all costs, charges and expenses which are properly incurred in the winding up shall be distributed to such, charitable arts organization or organizations registered under the provisions of the *Income Tax Act* (Canada) as may be determined by the members of the Society at the time of winding up or dissolution.

ARTICLE 14 – PLACE OF OPERATION

14.1 The operations of the Maple Ridge Pitt Meadows Arts Council are to be chiefly carried on in the area known as School District 42, in the Province of British Columbia.

Attachment One – Bylaw to Operational Policies

Article 8 - Staff:

- a) The Board of Directors will approve the hiring of the Executive Director and the Executive Director will be responsible for the hiring of additional staff
- b) The Board of Directors will approve the remuneration budget established for employees
- c) Staff who become members of the society will have non-voting status

Article 11 – Revenue and Expenditure

- a) All funds raised by donations, raffles, lotteries, admission charges, and the sale of goods and services or otherwise, by the Society or by any of its sections or committees, acting as such, shall be considered general funds of the Society, and subject to the accounting procedures approved by the Board of Directors
- b) All funds expended by the Society or by any of its sections or committees acting as such, shall be considered general expenditures of the society, and be subjected to the approval of the Board of Directors and to the accounting procedures approved by the Board
- c) Board members are Volunteers and as such are entitled to reasonable out of pocket expenses while conducting board business but are not entitled to any further compensation

Article 5 – Election of Officers and Directors

- a) The Nomination Committee shall issue a call for nominations from the members a minimum of 60 days prior to the Annual General Meeting. Nominations must be presented to the Nominating Committee 45 days in advance of the Annual General Meeting.

**‘SOCIETIES ACT’ CONSTITUTION AND BY-LAWS
OF
MAPLE RIDGE AND PITT MEADOWS ARTS COUNCIL**
(Article 1 = name of Society)

ARTICLE 2 - PURPOSES

The purpose of this Society shall be to increase and broaden the opportunities for citizens to enjoy and to participate in cultural activities, and shall include the following activities:

1. To provide for the coordination and provision of visual, literary and performing arts opportunities for the benefit of residents of the region.
2. To stimulate and encourage the development of cultural projects and activities.
3. To render service to all participating groups.
4. To act as a clearinghouse for information on cultural projects and activities.
5. To foster interest and pride in the cultural heritage of this community.
6. To enlist public interest and promote public understanding of cultural groups to the community.
7. To bring to the attention of civic, provincial and federal authorities the cultural needs of this community.
8. To provide scholarships to students pursuing education in the arts to students in the School District 42 catchment area.

MAPLE RIDGE PITT MEADOWS ARTS COUNCIL

SCHEDULE A BYLAWS

ARTICLE 1 – MEMBERSHIP

UPDATED language for clarity and membership related items under Article 1 as advised by legal counsel.

1.1 There are two classes of members voting and non-voting. Regular voting members are:

- a) A person, subscribing to the objects of the Society and engaged in or interested in cultural activities may apply to the directors for membership in the Society and on acceptance by the directors and on payment of the annual dues set forth, shall be a member.
- b) A group or business may apply for membership. Upon acceptance by the Board they must appoint a designated representative to attend and vote at general meetings.

1.2 Employees of the society may become non-voting members of the Society.

1.3 All members are in good standing except a member who has failed to pay the current annual membership fees or any other subscription or debt due and owing by the member to the Society and the member is not in good standing so long as the debt remains unpaid.

1.4 A person shall cease to be a member of the Society:

- i) by delivering their resignation in writing to the secretary of the Society or by mailing or delivering it to the address of the Society, or
- ii) on their death or in the case of a group, business, society or corporation on dissolution, or
- iv) by being expelled, or
- v) by failing to pay the annual membership fees

1.5 A member may be expelled by a special resolution of the members passed at a general meeting or by a majority vote of the Board of Directors.

1.6 Every member shall uphold the constitution and comply with these by-laws and all Society policies.

1.7 Annual membership fees in the Maple Ridge Pitt Meadows Arts Council shall be determined from time to time by the Board of Directors.

1.8 Meeting of Members

- a) The Annual General Meeting of the Society shall be held within 120 days from the fiscal year end upon a date and at a time set by the Directors.
- b) Special General Meetings may be called by the Board of Directors at any time.
- c) At least fourteen days regular or electronic written notice of all Annual and General Meetings of the Council shall be given the members, specifying the time and place of such meeting.
- d) At all General Meetings of the Society each individual member in good standing who is personally present, shall be entitled to one vote; and a group or business member may appoint a representative to vote on their behalf.

A member in good standing is one who has paid their membership dues and been ratified by the Board.

- e) No business shall be transacted at any Annual or Special General Meeting unless a quorum consisting of 15 (fifteen) or one-third of the membership, whichever is less, in good standing shall be present.
- f) If 10% of the members of the society in good standing request the calling of a Special General Meeting in writing, specifying therein the object for which such a meeting is called, the Board of Directors must call the Special Meeting in accordance with the *Societies Act*.
- g) Accidental omission to give notice to, or the non-receipt of notice by, any of the members entitled to receive notice, does not invalidate proceedings at the meeting.

ARTICLE 2– DIRECTORS

There shall be a maximum of thirteen elected Directors of the Society including Past President.

ARTICLE 3 – ELECTION OF OFFICERS AND DIRECTORS

3.1 A nominating Committee comprised of a minimum of three members of the society, the Chair of which shall be a member of the Board of Directors, shall be appointed by the Board a minimum of one hundred and twenty days prior to each Annual General Meeting and such Nominating Committee shall present the nominations for Directors to the membership for election at the Annual General Meeting. The Nominating Committee may submit a report of recommendations of Directors to be elected.

3.2 No salaried employee, nor any member of the family of such employee of the Society shall be eligible to election as Director for the duration of such employee’s employment with the Society, nor for a period of two years thereafter, nor shall any member of the family of a Director become eligible to be elected a Director during the term of office of such Director.

3.3 For the purposes of the foregoing, “family member” shall be defined as: father, mother, siblings, children, husband, wife, common law partner, same sex partner, grandparents, grandchildren, stepparents, stepchildren, stepbrothers or sisters or step grandparents or step grandchildren.

3.4 Subject to the foregoing, the Directors of the Society shall be elected from and by the membership of the Society at the Annual General Meeting. The Directors of the Society shall each be elected for a three-year term. The three-year terms shall be staggered so that each year four directors are elected. At each succeeding Annual General Meeting, four directors shall be elected for a three-year term. Whenever a Director’s position has been vacated midterm it will be specified upon election of a new Director what length of term is being filled.

3.5 The maximum term served by any Director of the Society shall normally be six consecutive years except that the President may remain on the Board for seven years.

3.6 The Directors shall elect from among their number the Executive Committee each year immediately following the Annual General Meeting by a majority vote. The Executive Committee of the Society shall be: Past President, President, Vice President, Secretary and Treasurer.

ARTICLE 4 – REPLACEMENT AND REMOVAL OF DIRECTORS

- a) Director vacancies may be filled from the membership by the Directors as needed. The length of time served, whether as an appointee or as an elected Director serving out the remainder of a vacant Director's term, will not count towards the six consecutive year limit.
- b) The Society may by special resolution remove any director before the expiration of their period of office and may by ordinary resolution appoint another member of the Society in his place in the manner set out in the Societies Act..

ARTICLE 5 – DUTIES OF OFFICERS AND DIRECTORS

5.1 The Board of Directors shall be responsible for the oversight of the business and activities of the Society.

5.2 The President is the Chair and shall preside over all meetings of the Society and of the Directors unless the members or directors decide otherwise.

5.3 The Vice President shall carry out the duties of the President during his/her absence

5.4 The Board may by resolution create committees for the purposes of conducting Society business. Such committees are to be chaired by a member of the Board but the membership may include members of the Society and other individuals as required. Committees shall operate in a manner consistent with that of the Board and meeting minutes shall be available to all of the Board for their information.

ADDED 5.5 and 5.6 for clarity_as advised by legal counsel.

5.5 The secretary must make the necessary arrangements for the following:

- a) the conduct of the correspondence of the society;
- b) the issuance of notices of meetings of the society and directors;
- c) the keeping of minutes of all meetings of the society and directors;
- d) the proper custody of all records and documents of the society except those required to be kept by the treasurer;
- e) the maintenance of the register of members.

5.6 The treasurer must make the necessary arrangements for the following:

- a) the keeping of the financial records, including books of account, necessary to comply with the *Societies Act*, and
- b) the rendering of financial statements to the directors, members and others when required.

ARTICLE 6– MEETINGS

UPDATED language for clarity_as advised by legal counsel.

6.1 Meetings of the Board of Directors

- a) Meetings of the Board of Directors and of the Executive Committee shall be held on an agreed to schedule by the Board and from time to time at the call of the President.
- b) At least seven days' notice shall be given of all meetings of the Board of Directors.
- c) No business shall be transacted at any meeting of the Board of Directors unless a quorum consisting of 50% of the members entitled to vote, shall be present

- d) A resolution in writing signed by all Directors or individual response by e-mail, and placed with the minutes of the Directors meetings is as valid and effective as if regularly passed at a meeting of Directors.
- e) Discussions at Board meetings shall be confidential within the Directors and the official spokesperson(s) for the Board is the President and the Executive Director or a delegate appointed by the Board.

ARTICLE 7- BORROWING OF MONEY

The Board of Directors may, upon a three-fourths majority vote, raise or borrow any sum or sums of money for the purpose of the Society either at one time, or from time to time, and at such rate of interest, and in such manner and form, and upon such security as shall be specified in such resolution; and for this purpose may mortgage, pledge, hypothecate and charge all or any part of the property of the Society now held or hereafter to be acquired.

ARTICLE 8- AUDITORS

The accounts of the Society shall be examined by an independent accountant, and that accountant will prepare an annual financial statement in the form of an audited financial report to be presented to the membership at the Annual General Meeting.

ARTICLE 9- INSPECTION

The official records of the Society pursuant to s. 20(1) of the *Act* will be open to the inspection of the Members. Members, and other persons, do not have the right to inspect or seek the disclosure of any other official record of the Society, including the Director's meeting minutes and accounting records, without the Board's approval and at their sole discretion. The Board of the Society will establish procedures for the inspection and disclosure of any official records.

ARTICLE 10 - AMENDMENTS

This Constitution may be added to, altered or amended by a two-thirds majority of the members present at any annual or General Meeting of the Society, provided that notice of such addition, alteration or amendment shall have been mailed to the members 14 days in advance of the meeting.

ARTICLE 11 - NOTICE

A notice may be given to a Member or a Director either personally, by delivery, courier or by mail posted to such Person's Registered Address, or, where a Member or Director has provided a fax number or e-mail address, by fax or e-mail, respectively.

ADDED for clarification as advised by legal counsel.

ARTICLE 12 - MUNICIPAL LIAISONS

Liaisons from community and civic organizations are received from time to time as deemed appropriate by the Board of Directors and/or as outlined in agreements. All liaisons shall be non-voting members of the Board and shall not attend in camera meetings of the Board.

ARTICLE 13 – DISSOLUTION

That upon winding up or dissolution of the Society, the assets which remain after payment of all costs, charges and expenses which are properly incurred in the winding up shall be distributed to such, charitable arts organization or organizations registered under the provisions of the *Income Tax Act* (Canada) as may be determined by the members of the Society at the time of winding up or dissolution.

ARTICLE 14 – PLACE OF OPERATION

The operations of the Maple Ridge Pitt Meadows Arts Council are to be chiefly carried on in the area known as School District 42, in the Province of British Columbia.

MOVE from constitution to bylaws, Article 14 as advised by legal counsel.

LIST OF ARTICLES IDENTIFIED FOR REMOVAL FROM BYLAW TO BOARD GOVERNANCE POLICY AS PER LEGAL COUNSEL:

ARTICLE 3 – FISCAL YEAR

The Fiscal Year of the Maple Ridge Pitt Meadows Arts Council shall end on the 30th day of June each year

ARTICLE 3 – ELECTION OF OFFICERS AND DIRECTORS

b) The Nomination Committee shall issue a call for nominations from the members a minimum of 60 days prior to the Annual General Meeting. Nominations must be presented to the Nominating Committee 45 days in advance of the Annual General Meeting. Nominations must be made in writing on the form designated for this purpose which shall be signed by the nominee indicating the nominee's acceptance and eligibility for the position of director. No nominations shall be accepted from the floor at the Annual General Meeting.

ARTICLE 5 – DUTIES OF OFFICERS AND DIRECTORS

a) The Board, in conjunction with the Executive Director and staff will have the responsibility to develop and maintain a strategic plan for the Society which must be available to the membership.

ARTICLE 6 – MEETINGS

d. For purposes of conducting official business at any Board meeting a quorum shall consist of 50% of the Board members entitled to vote. Failing a quorum, ratification of any business will await the next meeting of the Board at which there is a quorum or be ratified through an e-mail circulation to all members of the Board. E-mail ratifications shall allow a minimum of 48 hours for responses and the timelines must be specified in initial e-mail.

ARTICLE 8 – STAFF

- a) The Board of Directors will approve the hiring of the Executive Director and the Executive Director will be responsible for the hiring of additional staff.
- b) The Board of Directors will approve the remuneration budget established for employees.

ARTICLE 11- REVENUE AND EXPENDITURE

- a) All funds raised by donations, raffles, lotteries, admission charges, and the sale of goods and services, or otherwise, by the Society or by any of its sections or committees, acting as such, shall be considered general funds of the Society, and subject to the accounting procedures approved by the Board of Directors.
- b) All funds expended by the Society or by any of its sections or committees acting as such, shall be considered general expenditures of the society, and be subjected to the approval of the Board of Directors and to the accounting procedures approved by the Board.
- c) Board members are Volunteers and as such are entitled to reasonable out of pocket expenses while conducting board business but are not entitled to any further compensation.

1300 *Other Matters Deemed Expedient*

TO: His Worship Mayor Michael Morden
and Members of Council
FROM: Chief Administrative Officer
SUBJECT: First Reading
Zone Amending Bylaw No. 7552-2019;
11678 Burnett Street

MEETING DATE: June 18, 2019
FILE NO: 2019-164-RZ
MEETING: C o W

EXECUTIVE SUMMARY:

An application has been received to rezone the subject property from RS-1 (One Family Urban Residential) to RM-1 (Townhouse Residential) to support a 8 unit market rental residential townhouse development. To proceed further with this application additional information is required as outlined below.

This application is in compliance with the Official Community Plan.

Pursuant to Council Policy, this application is exempt to the Community Amenity Contribution Program at a rate of \$4,100.00 per townhouse dwelling unit, as the applicant is proposing market rental units that will be secured through a Housing Agreement and a Section 219 covenant that the units will be market rental in perpetuity.

The applicant has advised that additional density beyond the permitted FSR of 0.6 under the RM-1 (Townhouse Residential) zone may be sought which would require a site specific text amendment to the zone and Council may want to consider the density bonus policy in the OCP.

RECOMMENDATIONS:

That Zone Amending Bylaw No. 7552-2019 be given first reading; and

That the applicant provide further information as described on Schedules C, D and E of the Development Procedures Bylaw No. 5879-1999.

DISCUSSION:

a) Background Context:

Applicant:	Kevin Urbas
Legal Description:	Lot 2, Section 17, Township 12, New Westminister District, Plan 12588
OCP:	
Existing:	Urban Residential
Proposed:	Urban Residential
Zoning:	
Existing:	RS-1 (One Family Urban Residential)
Proposed:	RM-1 (Townhouse Residential)

Surrounding Uses:

North:	Use:	Single Family Residential
	Zone:	RS-1 (One Family Urban Residential)
	Designation:	Urban Residential
South:	Use:	Single Family Residential
	Zone:	RS-1 (One Family Urban Residential)
	Designation:	Urban Residential
East:	Use:	Single Family Residential
	Zone:	RS-1 (One Family Residential)
	Designation:	Urban Residential
West:	Use:	Apartment
	Zone:	C-3 (Town Centre Commercial)
	Designation:	Apartment-Low Rise and Conservation

Existing Use of Property:	Single Family Residential
Proposed Use of Property:	Townhouse
Site Area:	0.133 HA. (0.32 acres)
Access:	Lougheed Highway
Servicing requirement:	Urban Standard

b) Site Characteristics:

The subject property is located between Lougheed Highway to the west and 229 Street to the east and south of 117 Avenue just outside of the Town Centre Area. The current use of the subject property is single family residential. The property slopes gradually from the north east to the south west.

c) Project Description:

The applicant is proposing to rezone 11678 Burnett Street from RS-1 (One Family Urban Residential) to RM-1 (Townhouse Residential) to support a stacked residential townhouse development. The proposed development will consist of 1, 2 and 3 bedroom units. With the ground floor consisting of 1 and 2 bedroom units and the 3 bedroom 2-storey units stacked above. A total of 8 units are proposed with 12 surface parking stalls. The allowable FSR for the RM-1 (Townhouse Residential) zone is 0.6 and the proposal is 0.66. Further, discussion will be required with respect to the proposed increase in the FSR.

At this time, the current application has been assessed to determine its compliance with the Official Community Plan (OCP) and provide a land use assessment only. Detailed review and comments will need to be made once full application packages have been received. A more detailed analysis and a subsequent report will be required prior to Second Reading. Such assessment may impact proposed lot boundaries and yields, OCP designations and Bylaw particulars, and may require application for further development permits.

d) Planning Analysis:

Official Community Plan:

The OCP designates the subject property as *Urban Residential – Major Corridor*, and is subject to the *Major Corridor Residential* infill policies. The *Major Corridor Residential* policies identify various types of housing forms, including: single detached dwellings, duplexes, triplexes, fourplexes, townhouses, apartments, and small lot intensive residential developments. These policies require

that development be compatible with the surrounding neighbourhood, with particular attention given to site design, setbacks, and lot configuration with the existing pattern of development in the area. The OCP encourages growth within the Urban Area Boundary (UAB) through infill developments, by promoting a mix of housing types and tenures (Policy 3-1). The proposed rezoning of the subject property to RM-1 (Townhouse Residential) zone aligns with the Major Corridor Residential infill policies.

Policy 3-20 b) states: *a maximum height of two and one-half storey with an emphasis on ground oriented units for all developments except for apartments.* However, other OCP policies provide support for the increase in height noting density bonus and the provision of rental housing or a cash-in-lieu contribution are mechanisms for achieving additional density and height. On July 17, 2018 Council reviewed a draft framework of density bonus regulations. As a result of the discussion, Council directed staff to begin preparing bylaw amendments to incorporate the density bonus framework into the New Zoning Bylaw.

Council gave first reading to Bylaw 7418-2018 (2018-180-RZ) at the Council meeting held on May 28, 2019 to allow this application to proceed in which the applicant requested an increase in density similar to this application based on a density bonus as outlined below.

- 10% of the gross floor area being rental units, with rents at minimum 10% below CMHC average market rents for the Ridge-Meadows area; OR
- A cash in-lieu contribution.

Council on the June 4, 2019 Council Workshop clarified that Council preferred that cash-in-lieu option to creating affordable rental and special needs housing to the option of the developer providing 10% of the net floor area of the development to rental units. The applicant has indicated that a cash-in lieu is also the preferred option. The details of the cash-in-lieu option will form part of the second reading report

Council Policy No. 6.31 Community Amenity Contribution Program, applies city-wide, with a CAC contribution of \$4,100 per townhouse. The CAC program provides an exception to the creation of rental housing units that are secured through a Housing Agreement as established in Section 483 of the *Local Government Act* with an associated covenant under Section 219 of the *Land Title Act*. The applicant is proposing that the project will be market rental, secured through a Housing Agreement stating that the units will be market rental in perpetuity. At the June 4, 2019 Council Workshop meeting Council directed staff to bring back further information on how neighbouring municipalities were dealing with CAC rates.

The following OCP policies would also apply to this rezoning application:

3-30 *Maple Ridge will consider density bonus as a means of encouraging the provision of affordable, rental and special needs housing, and amenities.*

3-31 *Maple Ridge supports the provision of rental accommodation and encourages the construction of rental units that vary in size and number of bedrooms.*

3-32 *Maple Ridge supports the provision of affordable, rental and special needs housing throughout the District.*

3-33 *Maple Ridge will encourage housing that incorporates "age-in-place" concepts and senior housing designed to accommodate special needs.*

Housing Action Plan:

Maple Ridge's vision and commitment towards housing is encompassed in this statement contained in the Maple Ridge Housing Action Plan (MRHAP):

"Access to safe, affordable, and appropriate housing that meets the diverse and changing needs of the community is a priority."

The current application will provide approximately 8 new rental residential townhouse units directly adjacent to the Town Centre, and as mentioned above, the development will offers a diverse mix of one, two and three bedroom units.

Zoning Bylaw:

The current application proposes to rezone the property located at 11678 Burnett Street from RS-1 (One Family Urban Residential) to RM-1 (Townhouse Residential) to permit an 8 unit residential townhouse development. In order to facilitate any increase to the permitted FSR of 0.6 a site specific text amendment to the RM-1 (Townhouse Residential) zone would be required. Any variations from the requirements of the proposed zone will require a Development Variance Permit application.

Development Permits:

Pursuant to Section 8.7 of the OCP, a Multi-Family Development Permit application is required to ensure the current proposal enhances existing neighbourhoods with compatible housing styles that meet diverse needs, and minimize potential conflicts with neighbouring land uses.

Advisory Design Panel:

A Multi-Family Development Permit is required and must be reviewed by the Advisory Design Panel prior to Second Reading.

Development Information Meeting:

A Development Information Meeting is required for this application. Prior to Second Reading the applicant is required to host a Development Information Meeting in accordance with Council Policy 6.20.

e) Interdepartmental Implications:

In order to advance the current application, after First Reading, comments and input, will be sought from the various internal departments and external agencies listed below:

- a) Engineering Department;
- b) Operations Department;
- c) Fire Department;
- d) Building Department;
- e) Parks Department;
- f) School District;
- g) Utility companies;
- h) Ministry of Transportation and Infrastructure; and
- i) Canada Post.

The above list is intended to be indicative only and it may become necessary, as the application progresses, to liaise with agencies and/or departments not listed above.

This application has not been forwarded to the Engineering Department for comments at this time; therefore, an evaluation of servicing requirements has not been undertaken. We anticipate that this evaluation will take place between First and Second Reading.

f) Development Applications:

In order for this application to proceed, the following information must be provided, as required by Development Procedures Bylaw No. 5879-1999 as amended:

1. A complete Rezoning Application (Schedule C);
2. A Multi-Family Residential Development Permit Application (Schedule D); and
3. A Development Variance Permit (Schedule E);

The above list is intended to be indicative only, other applications may be necessary as the assessment of the proposal progresses.

CONCLUSION:

The development proposal is in compliance with the OCP, noting there is policy support for density bonusing and the provision for a cash-in-lieu option. Compatibility of this project's design, proposed height, setbacks and density bonus details will be determined prior to second reading. Therefore, it is recommended that Council grant first Reading subject to additional information being provided and assessed prior to Second Reading.

"Original signed by Wendy Cooper"

Prepared by: **Wendy Cooper, MCIP, RPP
Planner**

"Original signed by Chuck Goddard"

Reviewed by: **Charles R. Goddard, BA, MA
Director of Planning**

"Original signed by Christine Carter"

Approved by: **Christine Carter, M.PL, MCIP, RPP
GM Planning & Development Services**

"Original signed by Kelly Swift"

Concurrence: **Kelly Swift, MBA
Acting Chief Administrative Officer**


The following appendices are attached hereto:

Appendix A – Subject Map

Appendix B – Ortho Map

Appendix C – Zone Amending Bylaw No. 7552-2019

Appendix D – Proposed Site Plan



SUBJECT PROPERTY

2017-035-VP
 2017-035-RZ
 2017-035-DP

2017-145-RZ

2018-041-DP
 2018-041-RZ
 2018-041-VP

11790 11791
 11788 11781
 11778 11771
 11768 11761
 22929 22939
 11780
 11770
 11760
 22971

CLIFF AVE.
 22910 22920 22930 22940 22950 22962
 22927 22937 22945 22951 22961 22975 22983
 22976 22984

117 AVE.
 22928 22936 22942 22950 22960 22970
 11686
 11680 22935 22945 22953 22963
 GILLEY AVE.
 22930 22942 22952 22964
 22970

BURNETT ST
 11690 11678 11675 11671 11667 11663 11659
 11644 22890 22894 22900/02 22908/10 22904/06

2019-011-DP

180/90
 11695
 11681
 11669
 11661

228 ST.

GILLEY AVE.
 11670
 11648-54
 11646

22798

11632

11607

11597
 11585



Scale: 1:2,000

Legend

 Active Applications (RZ/SD/DP/VP)

11678 BURNETT STREET
 P.I.D. 009-722-092



FILE: 2019-164-RZ
 DATE: May 9, 2019

BY: PC



Aerial Imagery from the Spring of 2018



Scale: 1:2,000



11678 BURNETT STREET
 P.I.D. 009-722-092

PLANNING DEPARTMENT



mapleridge.ca


FILE: 2019-164-RZ
 DATE: May 9, 2019

BY: PC



MAPLE RIDGE ZONE AMENDING

Bylaw No. 7552-2019
 Map No. 1798
 From: RS-1 (One Family Urban Residential)
 To: RM-1 (Townhouse Residential)



SCALE 1:2,500

